

ENGINEERING INVESTIGATIONS AT INACTIVE HAZARDOUS WASTE SITES

PHASE 1 INVESTIGATION

**Hazardous Waste Disposal
Site No. 152113
Town of Babylon, Suffolk County**

Final - July, 1988



**Prepared for :
New York State
Department of
Environmental Conservation
50 Wolf Road, Albany, New York 12233
Thomas C. Jorling, Commissioner
Division of Hazardous Waste Remediation
Michael J. O'Toole, P. E., Director**

**Prepared by:
Roux Associates, Inc.
Subcontractor to
Gibbs & Hill, Inc.**

317411



ENGINEERING INVESTIGATIONS AT
INACTIVE HAZARDOUS WASTE SITES
IN THE STATE OF NEW YORK
PHASE I INVESTIGATIONS

Hazardous Waste Disposal
Town of Babylon, Suffolk County
New York ID No. 152113


Prepared for:

Division of Hazardous Waste Remediation
New York State Department of Environmental Conservation
50 Wolf Road
Albany, New York 12233-0001

July 1988

ROUX ASSOCIATES, INC.
Huntington Atrium
775 Park Avenue
Suite 255
Huntington, New York 11743

Subcontractor to
GIBBS & HILL, INC.



CONTENTS

	Page
1. EXECUTIVE SUMMARY.....	1
2. PURPOSE.....	3
3. SCOPE OF WORK.....	5
4. SITE ASSESSMENT - HAZARDOUS WASTE DISPOSAL.....	9
4.1 Site History.....	9
4.2 Site Topography.....	11
4.3 Site Hydrogeology.....	13
4.4 Site Contamination.....	18
5. PRELIMINARY HRS.....	20
5.1 Narrative Summary.....	21
5.2 Site Location.....	Following 23
5.3 HRS Worksheets.....	Following 23
5.4 Documentation Records for HRS.....	24
References.....	40
5.5 EPA Form 2070-12.....	Following 42
5.6 EPA Form 2070-13.....	Following 42
5.7 NYSDEC Inactive Hazardous Waste Disposal Report.....	Following 42
6. DATA ADEQUACY AND RECOMMENDATION.....	43
6.1 Data Adequacy.....	43
6.2 Recommendations.....	44
6.2.1 Task 1 - Site Reconnaissance.....	44
6.2.2 Task 2 - Magnetometer Survey.....	45
6.2.3 Task 3 - Soil Borings/Monitoring Wells.....	45
6.2.4 Task 4 - Well Sampling and Analyses.....	48
6.2.5 Task 5 - Quality Assurance/Quality Control.....	49
6.2.6 Task 6 - Health and Safety Plan.....	49
6.2.7 Task 7 - Site Assessment.....	50
6.2.8 Task 8 - Phase II Report.....	51

FIGURES

	Following Page
1. Location of Site.....	1
2. Site Base Map.....	1
3. Proposed Monitoring Well Locations.....	45
4. Proposed Monitoring Well Construction Diagram.....	47

APPENDICES

- A. Copies of relevant information that has not been included in the HRS Documentation Section.
- B. Updated NYS Registry Form

Former location of Hazardous Waste Disposal; it is currently a parking lot for trucks and school buses.




Another view of concrete on which drums of material were formerly stored. The concrete is stained with rings from the 55-gallon drums.



Basin which is located east of the site. (The school buses are located on-site).





1. EXECUTIVE SUMMARY

The Hazardous Waste Disposal site (New York I.D. No. 152113, EPA I.D. No. T000603894) is a suspected waste disposal area located in the Village of Farmingdale, Suffolk County, New York. The site is situated on a 1/2 acre plot in an industrial park at 11A Picone Boulevard (Figure 1). The current owner of the property is Little Joseph Realty of Farmingdale, New York.

The property was rented, via the realty company, to Mr. George Lawrence from about 1979 to 1982. In 1981 the site was identified by the Suffolk County Department of Health Services (SCDHS) when an inspection was conducted in response to a reported vapor release incident.

From the late 1970's to the early 1980's the Hazardous Waste Disposal (HWD) site was used as a temporary storage facility for hazardous and toxic wastes (Figure 2). The Suffolk County Department of Health Services reported that waste materials were contained in 55-gallon drums, large tanks and a sludge pit. Wastes were also recycled and reclaimed for resale.

The HWD site was evaluated using the Hazard Ranking System (HRS). HRS scores for the site consisted of a Migration Score (S_M) = a Ground-Water Score (S_{GW}) = a Surface-Water Score (S_{SW}) = an Air Route Score (S_A) = a Fire and Explosion Score (S_{FE}) = and a Direct Contact Score (S_{DC}) = .

The research of available data and the inspection of the site have produced insufficient data to complete a final HRS score for this site. However, there is reason to believe, based on previous site inspections conducted by state and local agencies, that hazardous wastes may have been released into the soil, thus posing a potential threat to ground-water quality. Analytical data will be necessary to confirm the presence of ground-water contamination.

A Phase II investigation is recommended to obtain analytical data to determine if contaminants from the HWD site have been released into the environment.

The proposed Phase II Investigation includes the installation of 4 soil boring/monitoring wells and the collection and analysis of soil and ground-water samples.

2. PURPOSE

The HWD site is listed on the New York State Registry of Inactive Hazardous Wastes sites because it is suspected of releasing hazardous and toxic wastes into the environment. The Suffolk County Department of Health Services identified the site in 1981 when a site inspection was conducted in response to a vapor release incident.

The purpose of a Phase I investigation is to provide a preliminary characterization of hazardous substances at the site. This characterization includes migration pathways taken by the pollutants and the affect that the pollutants might have on human population and/or natural resources.

A Phase I investigation is a compilation of existing information which includes:

- o Site history - available records obtained from state, federal, county and local agencies.
- o Site hydrogeology and topography.
- o Local demographics, local surface water and ground-water use.

- o Interviews with site owners, operators and other individuals knowledgeable of site history and operations.
- o Site inspection.
- o Phase I report which includes data evaluation, a preliminary Hazard Ranking Score (HRS) and recommendations for a Phase II investigation.

3. SCOPE OF WORK

The Phase I investigation of the Hazardous Waste Disposal site involved a data and records search/assessment, interviews, and a site inspection all conducted by Roux Associates, Inc. The following are the sources contacted and the information gathered from these contacts:

CONTACTINFORMATION COMPILED

Mr. Vic Emanuelo, Attorney
Little Joseph Realty
1637 Broad Hollow Road
Farmingdale, NY 11735
(516) 249-3400

Interview

Mr. Ed Lynch
Facility Superintendent
Little Joseph Realty
1637 Broad Hollow Road
Farmingdale, NY 11735
(516) 249-3400

Interview

Mr. Tony Candela
Senior Sanitary Engineer
New York State Department of
Environmental Conservation
Division of Solid and Hazardous Waste
SUNY - Building #40
Stony Brook, NY 11794
(516) 751-7900

Site file
verbal information

NYS Dept. of Agriculture
and Markets
Division of Rural Affairs
State Campus
Bldg. No. 8, Room 805
Albany, NY 12235
(518) 457-2713

Information

CONTACTINFORMATION COMPILED

NYSDEC
 Division of Fish & Wildlife
 Significant Habitats Unit
 Wildlife Resources Center
 Delmar, NY 12054
 (518) 439-7486

Verbal information

Mr. Frank Randall
 Suffolk County Department
 of Health Services
 225 Rabro Drive East
 Hauppauge, NY 11788
 (516) 451-4633

Site file/ information

Mr. Lawrence J. Alden
 Sanitary Engineer
 New York State Department of
 Environmental Conservation
 Bureau of Hazardous Site Control
 Division of Solid and Hazardous Waste
 50 Wolf Road
 Albany, NY 12233
 (518) 457-0639

Site file/information

Mr. Martin Shea
 Fish and Wildlife Technician
 New York State Department of
 Environmental Conservation
 Bureau of Environmental Protection
 SUNY - Building #40
 Stony Brook, NY 11794
 (516) 751-7900

Wetlands
 information

Mr. George Shultz
 Principle Engineering Technician
 New York State Department of
 Conservation
 Division of Water Supply and Management
 SUNY - Building #40
 Stony Brook, NY 11794
 (516) 751-7900

Ground water
 supply information

CONTACT

Mr. Mark Carerra
 New York State Department
 of Environmental Conservation
 Division of Water Quality
 SUNY - Building #40
 Stony Brook, NY 11794
 (516) 751-7900

Mr. Ron Busciolano
 U.S. Geological Survey
 5 Aerial Way
 Syosset, NY 11791
 (516) 938-8830

Mr. David Obrig
 Suffolk County Department of
 Health Services
 225 Rabro Drive East
 Hauppauge, NY 11788
 (516) 451-4633

Mr. John Ferarra
 E. Farmingdale Water District
 Farmingdale, NY
 (516) 249-4211

Mr. Limblade
 S. Farmingdale Water District
 Farmingdale, NY
 (516) 249-3330

Mr. K. Bonneau
 Huntington Town Water District
 Huntington, NY
 (516) 427-0305

Plainview-Bethpage Water District
 Plainview, NY
 (516) 931-0093

Suffolk County Water Authority
 Babylon Office
 Babylon, NY
 (516) 669-1669

INFORMATION COMPILED

Supply-well/
 observation

Supply-well/
 observation well
 information

Verbal information

Ground-water use/
 information

Ground-water use/
 information

Ground-water use/
 information

Ground-water use/
 information

Ground-water use/
 information

CONTACT

Mr. George Lawrence
Former Operator of HWD
Environmental Services Inc.
Smithtown, NY
(516 273-3150

INFORMATION COMPILED

Site information

4. SITE ASSESSMENT - HAZARDOUS WASTE DISPOSAL

4.1 Site History

The Hazardous Waste Disposal (HWD) site is a paved 1/2 acre lot located in the Village of Farmingdale, Suffolk County, which had been used as a storage facility for hazardous and toxic wastes (Figure 2). The site, owned by Little Joseph Realty, Farmingdale, New York is presently being used as a parking lot. The previous tenant, Mr. George Lawrence of Glenwood Landing, New York, operated his company, HWD, at the site for a period of about three years (Appendix A1 and A2).

HWD was in the industrial waste scavenger business which included the transportation and storage of hazardous wastes. HWD also processed wastes for recovery and resale purposes. In 1979 HWD changed it's address listing from Valley Stream, New York to the Picone Boulevard, Farmingdale address. From 1979 to 1982 HWD used the site for the temporary storage of hazardous and toxic wastes (Appendix A3). These wastes were contained in 55-gallon drums, large holding tanks and a sludge pit (Appendix A4 and A5).

In March of 1981 HWD reported a vapor discharge incident to

the Suffolk County Department of Health Services (SCDHS). HWD identified a faulty valve for allowing nitrogen oxygen compounds (NO_x) and hydrochloric (HCl) vapors to be released into the atmosphere. In response to this incident, the SCDHS investigated the HWD premises. Testimony taken from an HWD neighbor and the local fire department gave the SCDHS sufficient cause to recommend a detailed industrial survey be performed at the site (Appendix A6). The survey discovered that HWD was operating an ammonium-hydroxide scrubbing process on an acid storage tank without a permit and a violation was issued (Appendix A7). SCDHS requested that the New York State Department of Environmental Conservation (NYSDEC) carry out legal actions against HWD for the violation of Article 27 and 71 of the Environmental Conservation Law of the State of New York (Appendix A8, A9 and A10). Legal actions followed and the DEC ordered HWD to cease operations and remove all hazardous waste materials from the property.

The Environmental Protection Agency (EPA) conducted a site inspection in September 1981 and identified 1900 55-gallon drums and a 2500-gallon acid tank on-site (Appendix A4). In June and September of 1982 the SCDHS visited the site and, similar to the EPA inspection, observed no clean-up work and poor site conditions (Appendix A5). However, HWD advised

the SCDHS in November 1982 that all hazardous waste, containers, tanks and miscellaneous items had been removed from the site and had been properly disposed. A SCDHS site inspection in November 1982 and a DEC site inspection in June and July of 1985 confirmed that the site had been cleaned up and wastes had been removed.

Located on the site property are two drywells/storm drains which control drainage. Based on site inspections, poor conditions (leaky drums and spills) were observed during HWD operations (Appendix A4 and A5). It is possible, especially during rainfall events, that runoff containing spilled wastes were collected by the on-site drywells. The drywells are connected to a drainage system which collects run off from other areas of the industrial park and empties into a nearby recharge basin or sump (Figure 2) (Appendix A11).

There is no analytical data available from the site, however, there is reason to believe that a possible threat to ground water exists.

4.2 Site Topography

Located in an industrial park, the site (about 1/2 acre in size) is surrounded by various commercial and industrial

facilities. The site is situated on a glacial outwash plain which gently slopes south at about 20 feet per mile from the moraines, which are located to the north (Pluhowski, et.al. 1964). The site itself is characterized by a relatively flat topography.

Several streams, located over 3 miles south of the site, are widely spaced and have few or no tributaries. Flow in these streams, which are generally about 3 miles long, is to the south. Mean annual discharges are less than 20 cubic feet per second (Ku, et.al. 1981).

Flat topography and the highly permeable outwash deposits (sand and gravel) cause most precipitation falling beyond stream channels to infiltrate quickly into the ground. Run off from most housing, commercial and industrial developments, and highways empty into excavated recharge basins or sumps. Almost all ponds are manmade (Pluhowski, et.al. 1964). The installation of sewer systems in southeastern Nassau County has resulted in the lowering of the water table and a reduction in stream flow (Ku, et.al. 1981).

4.3 Site Hydrogeology

The HWD site is underlain by approximately 1300 feet of unconsolidated glacial deposits of Pleistocene age and coastal-plain deposits of continental and marine origin of late Cretaceous age. These deposits are made up of gravel, sand, silt and clay are underlain by Paleozoic and/or Precambrian bedrock composed mostly of schist and gneiss. Bedrock, due to it's low permeability, is considered the base of the ground-water reservoir on Long Island (Pluhowski, et.al. 1964 and Jensen, et. al. 1974).

The Lloyd aquifer, the Raritan clay, the Magothy aquifer and the Upper Glacial aquifer are the four hydrostratigraphic units which comprise the unconsolidated deposits overlying bedrock. The Lloyd aquifer lies directly on the bedrock surface and is the lower most water-bearing zone in the ground-water reservoir. This deep artesian aquifer is composed of light-colored sand and gravel with lenses of clay and silty clay. The altitude of the top of the Lloyd in the area of study is approximately 900 feet below sea level (Jensen, 1974 and Pluhowski, et.al. 1964).

The Raritan clay consists predominately of clay with varying

amounts of silt and sand, and acts as an effective confining unit for the underlying Lloyd aquifer (Pluhowski, et.al. 1964). In the study area (within a 3-mile radius of the site) the Raritan is about 100 feet in thickness with the upper surface of the unit about 800 feet below sea level (Jensen, et. al. 1974).

Situated above the Raritan clay is an upper Cretaceous unit composed of permeable lenticular deposits of sand, gravel and clay referred to as the Magothy aquifer. Below the study area, the thickness of the Magothy is approximately 900 feet (Jensen, et. al. 1974).

The uppermost zone of the ground-water reservoir is the Upper Glacial aquifer. This unconfined unit lies unconformably on the Magothy and consists of highly permeable upper Pleistocene deposits of sand and gravel. The lower boundary of the Upper Glacial aquifer depends on the presence of low permeable lenses of silt and clay in the Magothy aquifer. However, where the upper Magothy consists of permeable deposits, the Upper Glacial and the Magothy aquifers are considered hydraulically connected (Pluhowski, et. al. 1964). In this report the Upper glacial and the Magothy together will be considered the principal aquifer of concern.

Highly permeable outwash deposits of sand and gravel in the upper part of the principal aquifer (Upper Glacial deposits) yield as much as 1,500 gallons per minute (gpm) with specific capacities commonly 40 to 75 gpm per foot of drawdown. Wells screened in the impermeable to highly permeable Magothy aquifer yield as much as 1,500 gpm with specific capacities ranging from 1 to 49 gpm per foot of drawdown (Pluhowski, et. al. 1964).

Regional ground-water flow is south to southeast, away from the topographic and water-table high to the north. Lateral movement of ground water within the principal aquifer in the study area will mimic the regional flow direction (Donaldson, et. al. 1979).

Located within a 3-mile radius of the site are over 20 public-supply wells and numerous observation wells. These wells are screened both in the Upper Glacial and Magothy aquifers. Downgradient (direction of ground-water movement), about 1 3/4 miles southeast of the site, a pumping well (S66556) is located. Two public-supply wells (NYSDEC #20041 and #20042) are located approximately 1400 feet to the northwest (upgradient) of the site. In 1961, the depth to water recorded in both wells was 25 feet below land surface

(Krulikas, 1981). This coincided with measurements reported in 1979 (Donaldson, et. al. 1979).

REFERENCES FOR THIS SECTION

Pluhowski, E.J. 1964. Hydrology of the Babylon - Islip Area Suffolk County Long Island, New York. USGS Water-supply Paper 1768 (Appendix A19).

Krulik, R.K. 1981. Hydrogeologic Data from Selected Wells and Test Holes in Suffolk County, Long Island, New York, 1972-80. USGS Open-file report 81-500 (Appendix A20).

Jensen, H.M. and Soren, J. 1974. Hydrologic Investigations Atlas. USGS Atlas HA-501 (Appendix A21).

Ku, H.F.H. and Simmons, D.L. 1981. Base flow of streams in Nassau County Sewer District 2 and 3, Long Island, New York, 1978-79. Water-Resources Investigation Open-file report 81-420 (Appendix A22).

Donaldson, C.D. and Koszalka, E.J. 1979. Water Table on Long Island, New York, March 1979. Open-File Report 82-163. Plate IA West (Appendix 23).

4.4 Site Contamination

Waste Types and Quantities

No analytical data is available for wastes which had been stored on-site. Documents state that hazardous wastes such as oils, paint sludge and various solvents were handled by HWD. HWD also operated a reclamation process for spent solvents. Observations recorded during a site inspection by the EPA stated that 1900 55-gallon drums and one 2500 gallon tank were present at the facility. This information produces an estimated waste quantity at the time of the site inspection at about 107,000 gallons (Appendix A4).

Ground Water

No data available.

Surface Water

Not applicable. Natural surface-water bodies are located over 3-miles from site.

Air

No data available. During the site inspection conducted by Roux Associates on June 25, 1987, a photoionization meter (TIP II) was employed. Readings recorded were not above background.

5. PRELIMINARY HRS

Documentation records and work sheets required to develop Hazard Ranking System (HRS) scores are included in this section. Information was obtained from private, county, state and federal agencies and utilized to prepare as completely as possible the included HRS scores. Documents included in this section are:

- o Preliminary Hazard Ranking System (HRS) work sheets,
- o Preliminary Assessment Form (EPA form 2070-12)
- o Site Inspection Report (EPA Form 2070-13)
- o Updated NYSDEC Inactive Hazardous Waste Disposal Report

5.1 Narrative Summary

Hazardous Waste Disposal, Village of Farmingdale, Town of Babylon, Suffolk County

The Hazardous Waste Disposal (HWD) site is a suspected industrial waste disposal area located in the Village of Farmingdale, Suffolk County, New York (Figure 1). The site property, owned by Little Joseph Realty of Farmingdale, New York, is about 1/2 acre in size and is presently being used as a parking lot by a school bus terminal. The previous tenant, Mr. George Lawrence of Glenwood Landing, New York rented the property from the late 1970's to early 1980's. During this time Mr. Lawrence operated Hazardous Waste Disposal, Inc. The Suffolk County Department of Health Services (SCDHS) identified the site in 1981 when an industrial survey was conducted in response to a reported vapor release incident.

HWD conducted business at the site from 1979 to 1981. HWD was a waste scavenger company which removed, transported and disposed of hazardous and toxic waste materials. The HWD site was utilized as a temporary storage facility for wastes which HWD collected from their clients. Wastes were allegedly disposed of at the Applied Environmental Science


facility in Glenwood Landing, New York which was also operated by Mr. Lawrence. Wastes were allegedly contained at the HWD site in 55-gallon drums, large tanks and a sludge pit. In addition to waste storage, HWD recycled spent solvents for resale.

Numerous site inspections by federal, state and local agencies revealed poor site conditions which included corroded and leaking drums. HWD was accused of violating New York State Conservation Laws which resulted in a consent order for HWD to cease operations and perform a site clean-up. In November of 1982, the site had been removed of all hazardous materials and cleaned.


No analytical data are available for the site. However, the on-site drywells may have acted as pathways for which contaminants could travel and enter the subsurface. It is possible that contaminated run-off may have entered the on-site drywells. These drywells are allegedly connected to a subsurface drainage system which discharges into a recharge basin adjacent to the site. Depending on the discharge capacity of the drywells, contaminated run-off may have traveled to the recharge basin during periods of high discharge events, and vertically through the material beneath the drywells at times of low discharge.

Contaminants introduced into the permeable soil could pose a potential threat to ground-water quality. The principal aquifer of concern supplies ground water to over 90,000 people within a 3-mile radius of the site. Two public-supply wells (S20041 and S20042) are located approximately 1400 feet up-gradient from the site. Located down-gradient (in the direction of ground-water flow), approximately 1 3/4 miles to the southeast of the site, is a public-supply well (S66556).

5.2 Site Location



TITLE	
LOCATION OF HAZARDOUS WASTE DISPOSAL SITE	
PREPARED FOR	
N.Y.S.D.E.C.	
ROUX	Consulting Ground-Water Geologists ROUX ASSOCIATES INC.
SCALE 1"=2000'	FIGURE 1
DATE 8/87	



5.4 DOCUMENTATION RECORDS FOR HAZARD RANKING SYSTEM

INSTRUCTIONS: The purpose of these records is to provide a convenient way to prepare an auditable record of the data and documentation used to apply the Hazard Ranking System to a given facility. As briefly as possible, summarize the information you used to assign the score for each factor (e.g., "Waste quantity = 4,230 drums plus 800 cubic yards of sludges"). The source of information should be provided for each entry and should be a bibliographic-type reference that will make the document used for a given data point easier to find. Include the location of the document and consider appending a copy of the relevant page(s) for ease in review.

FACILITY NAME: Hazardous Waste Disposal

LOCATION: 11A Picone Boulevard, Village of Farmingdale,
Town of Babylon, Suffolk County, New York.

DATE SCORED: June 25, 1987

PERSON SCORING: Joseph Byrnes

PRIMARY SOURCES OF INFORMATION:

Suffolk County Department of Health Services.
New York State Department of Environmental Conservation,
Division of Hazardous Waste Remediation.

FACTORS NOT SCORED DUE TO INSUFFICIENT INFORMATION:

Toxicity of wastes currently at site.
Waste quantity is based on amount of waste stored at site during a September, 1981 EPA inspection.

(#) = Reference number. See end of section for reference.

GROUND WATER ROUTE

1 OBSERVED RELEASE

Contaminants detected (5 maximum):

No data available.

Rationale for attributing the contaminants to the facility:

Not applicable.

Assigned value = 0

2 ROUTE CHARACTERISTICS

Depth to Aquifer of Concern

Name/description of aquifer(s) of concern:

The Magothy and Upper glacial aquifers are designated as the aquifers of concern within a 3-mile radius of the site. The Magothy aquifer consists mainly of fine to medium sand and the Upper glacial aquifer is made up of fine to coarse sand and gravel.

There is no major confining layer between the two aquifers, thus a hydraulic connection does exist between the two aquifers (1).

Depth(s) from the ground surface to the highest seasonal level of the saturated zone (water table(s)) of the aquifer of concern:

Two public-supply wells (NYSDEC No. S20041 and S20042) drilled to a depth of 268 and 585 feet, respectively are located just northwest of the site approximately 1,400 feet away. A depth to water of 25 feet was measured in both wells in 1961 (2). In addition, a water table map for March 1979 shows depth to ground water at about 25 feet below land surface at the site (3).

Depth from the ground surface to the lowest point of waste disposal/storage:

Wastes were allegedly stored at or above land surface. The depth to water (water table) is approximately 25 feet (2,3,4.13.22 and 4.14.22)

Assigned value = 2

Net Precipitation

Mean annual or seasonal precipitation:

46 inches (1).

Mean annual lake or seasonal evaporation:

30 inches (5).

Net precipitation (subtract the above figures):

16 inches.

Assigned value = 3

Permeability of Unsaturated Zone

Soil type in unsaturated zone:

Outwash - plain deposits consisting of stratified sand and gravel (1).

Permeability associated with soil type:

Highly permeable, estimated range of hydraulic conductivity $>10^{-3}$ cm/sec (5).

Assigned value = 3.

Physical State of Waste

Liquid/sludge/solid:

Chlorinated and non-chlorinated solvents, paint sludge, waste resins and acids (4.1.22 thru 4.16.22).

Assigned value = 3

3 CONTAINMENT

Containment

Containers - a large number of drums were allegedly stored on-site. Site inspections revealed many of the drums incompatible with wastes resulting in leaks and corrosion. The storage area is cement paved, however, on-site drywells would collect mishandled wastes and spills. These drywells are connected to a system which drains into a nearby recharge basin (4.1.22 thru 4.16.22 and 6).

Assigned value = 3

4 WASTE CHARACTERISTICS

Toxicity and Persistence

Available analytical data or disposal invoices do not indicate any specific chemical compound. A broad description of wastes include solvents, paint sludge, resins, oils and acids. A vapor release incident was reported. HWD admitted releasing NO_x and HCl vapors into the atmosphere.

Compound with highest score:

Hydrochloric acid (4 and 5).

Assigned value = 9

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

Approximately 1945 drums.

Assigned value = 5

Basis of estimating and/or computing waste quantity:

Based on a site inspection performed by the EPA on September 2, 1981, 1900 55-gallon drums of waste materials (spent solvents and acids) and a 2500-gallon tank containing acid were present on-site. This brings the total quantity of wastes present on-site in 1981 to about 107,000 gallons (4.1.22).

5 TARGETS

Ground Water Use

Use(s) of aquifer(s) of concern within a 3-mile radius of the facility:

Drinking water (1).

Assigned value = 3

Distance to Nearest Well

Location of nearest well drawing from aquifer(s) of concern or occupied building not served by a public water supply:

Two (2) public-supply wells (S20041 and S20042) are located approximately 1400 feet north of the site (2,7.1 and 7.4).

Assigned value = 4

Population served by Ground-Water Wells within a 3-Mile Radius

Public Water supplies:

E. Farmingdale Water District - 4 pumping wells serving 5,200 people. The entire district is within the 3-mile radius (7.1 and 9).

S. Farmingdale Water District - serving 48,000 people. Approximately 1/2 of the district is located within the 3-mile radius (7.2).

Table 2. Hydrogeologic units and well completion data from selected wells and test holes in Suffolk County, New York.

EXPLANATION OF COLUMNAR DATA AND ABBREVIATIONS

Well Number

Well numbers are assigned by the New York State Department of Environmental Conservation. A prefix letter S, which designates Suffolk County, is omitted from the well number; thus, the official number of well 40161, for example, is S 40161. Wells are listed in numerical order.

Location of Well

Locations of wells are given by map coordinates, based on latitude and longitude, as shown on plate 1. Map coordinates are based on a latitude and longitude grid system established for Long Island (Veatch and others, 1906; Jensen and Soren, 1971). In this system, 5-minute intervals of latitude are lettered consecutively from south to north, and 5-minute intervals of longitude are numbered consecutively from west to east. The grid coordinates for Suffolk County are shown along the margins of plate 1. Thus, a well whose map coordinates are D15 is in the grid square bounded by lat 40°45' and 40°50'N and long 72°55' and 72°50'W.

Wells are also numbered according to the national well-numbering system of the U.S. Geological Survey. This system locates wells to the nearest second of latitude and longitude and gives a sequence number to the well to denote the chronological order in which wells within a 1-second quadrangle were recorded. For example, in well number 404707N0731905.01 (S 18075), the first six numbers indicate latitude 40°47'07" North; the remaining numbers before the period indicate longitude 073°19'05". The 01 after the period is the sequence number. Thus this well was the first one recorded in the 1-second quadrangle defined by the latitude and the longitude.

Well depth

The figures give well depth or total depth of the drilled test hole, in feet below land surface.

Hydrogeologic Unit Penetrated and Elevation of Unit Surface

Elevations of the tops of the hydrogeologic units penetrated by wells are given in feet above or below National Geodetic Vertical Datum of 1929. A minus (-) sign preceding the elevation figure indicates that the elevation is below National Geodetic Vertical Datum of 1929. The number in the "upper glacial aquifer" column is the elevation of the land surface at the well site. Absence of an elevation figure indicates that the test hole did not penetrate the unit.

Table 2.--Explanation (continued)

Year Completed

Year completed refers to the year in which the well was reported to have been completed or accepted by the original well owner. It may not always be the year in which the well was actually drilled.

Elevation of Land-Surface Datum (LSD)
(feet above National Geodetic Vertical Datum of 1929)

The elevation of land surface at the well was estimated from U.S. Geological Survey 7-1/2-minute quadrangle topographic maps.

Use of Water

The following abbreviations indicate the primary purpose in 1977 for which the water from the well was reported to be used.

ARCD	air conditioning	IND	industrial
COM	commercial	IRR	irrigation
DOM	domestic	OTHR	other
FRPT	fire protection	P.S.	public supply
INST	institutional		

Use of Well

The following abbreviations indicate the principal use of the well or the purpose for which the well or hole was drilled.

DEST	well destroyed	TEST	test hole
OBS	observation well	UNSD	well unused
RECH	recharge water	WTDR	withdrawal of water

Screen Setting and Total Screen Length

The elevations of the top and bottom of the screened interval are given in feet above or below (-) National Geodetic Vertical Datum of 1929. The total length of screen or perforated pipe in that interval is given in feet. In some wells, screen was set at two or more intervals; in such cases the difference between the elevations of the two screen settings is different from the total screen length.

Diameter of Well

The diameter of the well is the inside diameter of the smallest casing at land surface, in inches.

Plainview - Bethpage Water District - Serves 8,300 people. The district is located almost entirely within the 3-mile radius (7.3).

Huntington Town Water District - Has 9,000 accounts (9000 x 3.8 people). this district supplies about 34,200 people with ground water. Only 1/4 of the district falls within the 3-mile radius (7.3 and 7.5).

Suffolk County Water Authority -

At least 15 public-supply wells are located within a 3-mile radius of the site in the Babylon Water District. An estimated 3,500 people are served per pumping well. Population served in the Babylon District within a 3-mile radius of the site (3500 x 15) = about 52,500 people (7.3, 8 and 9).

Total population served by ground water within a 3-mile radius:

± 90,000 people.

Assigned value = 5

Combined value = 40

SURFACE WATER ROUTE

1 OBSERVED RELEASE

Contaminants detected in surface water at the facility or downhill from it (5 maximum):

No data available to confirm release.

Assigned value = 0

2 ROUTE CHARACTERISTICS

Facility Slope and Intervening Terrain

Average slope of facility in percent:

Average slope = 0. Paved parking lot intervening terrain has slope <1% (6).

1-Year, 24-Hour Rainfall in Inches

2.5 - 3.0 inches (5).

Assigned value = 2

Distance to Nearest Downslope Surface Water

Several creeks emptying into the Great South Bay are located over 3 miles away, to the south of site. Almost all pond water is manmade (10).

Assigned value = 0

Physical State of Waste

Liquid/Sludge: Allegedly solvents, acids, paint sludge, resin wastes and waste oils were stored at site. No Analytical data available (4.1.22 - 4.16.22).

Assigned value = 3

3 CONTAINMENT

Containment

Containers - a large number of drums were stored on-site. Site inspections revealed many of the drums incompatible with wastes resulting in leaks and corrosion. The storage area is cement paved. However, on-site drywells would collect mishandled wastes and spills (4 and 6).

Assigned value = 3

4 WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

No Analytical data collected from wastes. However, HWD did admit to releasing acid vapors into the atmosphere (4.17.22 and 4.18.22).

Compound with highest score:

Hydrochloric acid (5).

Assigned value = 9

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

Approximately 1945 drums.

Assigned value = 5

Basis of estimating and/or computing waste quantity:

Based on a site inspection performed by the DEC on September 2, 1981, 1900 55-gallon drums of waste materials (spent solvents and acids) and a 2500-gallon tank containing acid were present on-site. Thus, the total quantity of waste in 1981 was about 107,000 gallons (4.1.22).

Distance to critical habitat of an endangered species or national wildlife refuge, if 1 mile or less:

None (11).

Assigned value = 0

Population Served by Surface Water

Location(s) of surface water with water intake within 3 miles (free-flowing) or 1 mile (static) downstream from facility and population served:

None (10).

5 TARGETS

Surface Water Use

Use of surface water within three miles downstream of hazardous substance:

None (12).

Assigned value = 0

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

None (12).

Assigned value = 0

Land area irrigated by surface water intake(s):

None (10).

Assigned value = 0

Total population served:

None.

Assigned value = 0

Name/description of nearest of above waterbodies:

None.

Distance to surface water intakes:

None.

Assigned value = 0

Combined value = 0

AIR ROUTE

1 OBSERVED RELEASE

Contaminants detected:

A vapor discharge incident was reported on March 11, 1981 at the facility. A faulty valve resulted in the release of NO_x and HCl gases into the atmosphere. No personal or property damage reported. The contaminant levels were not recorded. During the Roux site inspection organic vapors were measured using the TIP II. No reading above background was recorded (4.17.22, 4.18.22 and 6).

Assigned value = 0

Date and location of detection of contaminants:

N/A

Methods used to detect the contaminants:

N/A

Rationale for attributing the contaminants to the site:

N/A

2 WASTE CHARACTERISTICS

Reactivity and Incompatibility

Most reactive compound:

N/A

Most incompatible pair of compounds:

N/A

Toxicity

Most toxic compound:

N/A

Hazardous Waste Quantity

Total quantity of hazardous waste:

N/A

Basis of estimating and/or computing waste quantity:

N/A

3 TARGETS

Population Within 4-Mile Radius

Underline radius used, give population, and indicate how determined:

0 to 4 mi 0 to 1 mi 0 to 1/2 mi 0 to 1/4 mi

>7,500 people but <10,000 (7).

Assigned value = 27

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

>2 miles (12).

Assigned value = 0

Distance to a 5-acre (minimum) freshwater wetland, if 1 mile or less:

>1 mile (12).

Assigned value = 0

Distance to critical habitat of an endangered species, if 1 mile or less:

>1 mile (11).

Assigned value = 0

Land Use

Distance to commercial/industrial area, if 1 mile or less:

<1/4 mile (6).

Assigned value = 3

Distance to national or state park, forest, or wildlife reserve if 2 miles or less:

1 mile (10).

Assigned value = 2

Distance to residential area, if 2 miles or less:

3/4 mile (10).

Assigned value = 2

Distance to agricultural land in production within past 5 years, if 1 mile or less:

>1 mile (10).

Assigned value = 0

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

>2 miles (10).

Assigned value = 0

Is a historic or landmark site (National Register of Historic Places and National Natural Landmarks) within the view of the site?

No (6).

Assigned value = 0

FIRE AND EXPLOSION

Site visit did not demonstrate a fire or explosion threat. During Roux site visit, all photoionization meter readings were at background levels.

DIRECT CONTACT

1 OBSERVED INCIDENT

Date, location, and pertinent details of incident:

None reported and no visual wastes were observed (6).

Assigned value = 0

2 ACCESSIBILITY

Describe type(s) of barrier(s):

Site enclosed with a fence (6).

Assigned value = 0

3 CONTAINMENT

Type of Containment:

No visible wastes at site (6).

Assigned value = 0

4 WASTE CHARACTERISTICS

Toxicity

N/A

5 TARGETS

Population within a one-mile radius

>10,000 people (7).

Assigned value = 5

Distance to a critical habitat (of an endangered species

>1 mile (11).

Assigned value = 0

REFERENCES

<u>Reference #</u>	<u>Description of Reference</u>
1	Pluhowski, E.J. and Kantrowitz, I.H. 1964. Hydrology of the Babylon- Islip Area, Suffolk County Long Island, New York. USGS Water Supply Paper 1768.
2	Krulik, R.K. 1981. Hydrogeologic Data from Selected Wells and Test Holes in Suffolk County, Long Island, New York, 1972-80. USGS Open-File Report 81-500.
3	Donaldson, C.D. and Koszalka, E.J. 1979. Water Table on Long Island, New York, March 1979. Open-File Report 82-163. Plate IA West.
4	New York State Department of Environmental Conservation, Hazardous Waste Disposal Site file.

- 5 U.S. EPA 1984. Uncontrolled Hazardous Waste Site Ranking System. A Users Manual (HW-10). Originally published in the July 16, 1982 Federal Register.
- 6 Roux Site Inspection, June 25, 1987. Notes Available at Roux Associates.
- 7 J. Byrnes (Roux Associates) telephone conversations with John Fererra (East Farmingdale Water District), Mr. Limblade (S. Farmingdale Water District), Mr. Bonneau (Huntington Town Water District), and representative for Plainview/Bethpage Water District. Public-Supply Well location map.
- 8 Suffolk County Water Authority, 1986 Annual Report.
- 9 USGS Header File - Well information.

- 10 USGS 7.5-Minute Series Topographic:
Amityville Quadrangle, 1969 and
Huntington Quadrangle, 1979.
- 11 NYSDEC Bureau of Environmental
Protection, Region I. National
Wildlife Inventory Map. Available
at NYSDEC, Region I. Copy not
available for this report.
- 12 NYSDEC Bureau of Environmental
Protection, Region I. National
Wetlands Inventory Map.

ROUX ASSOCIATES

Hydrology of the Babylon-Islip Area Suffolk County Long Island, New York

GEOLOGICAL SURVEY WATER-SUPPLY PAPER 1768

*Prepared in cooperation with the Suffolk
County Board of Supervisors, Suffolk
County Water Authority, and the New
York State Water Resources Commission*



INTRODUCTION

PURPOSE

The rapid expansion of population and industry in southwestern Suffolk County, particularly since 1950 (fig. 2), has resulted in sharply increased withdrawals from the ground-water reservoir which, at present, supplies all water used in the area. However, the fact that there is substantial streamflow from the area indicates that additional development of the water resources is possible. Because an adequate water supply is essential to the continued growth of the area, knowledge of the occurrence, quality, and availability of water, both underground and in streams, is required by industry and the public. Because the source of all water on Long Island is precipitation, evaluation of the water potential of the area requires following the path of water from its inception as precipitation to its ultimate return to the atmosphere.

The objectives of the investigation were (a) to evaluate and summarize present data on quantity, quality, and availability of both ground water and surface water; (b) to determine the interrelation of ground water and surface water; (c) to evaluate the water balance for the ground-water reservoir, and (d) to evaluate any existing or potential water-supply problems.

This report is part of a continuing cooperative program sponsored jointly by the U.S. Geological Survey, the Suffolk County Water Authority, the Suffolk County Board of Supervisors, and the New York State Water Resources Commission.

LOCATION AND EXTENT OF AREA

The report area includes the Town of Babylon, virtually all of the Town of Islip, and small parts of the Towns of Huntington, Smithtown, and Brookhaven in southwestern Suffolk County, and a small area in the southeastern part of Nassau County (fig. 1). The area comprises about 270 square miles, of which 190 square miles are on the main part of Long Island; the barrier beaches, islands, and Great South Bay comprise the remainder. The area is roughly rectangular in shape; it is about 20 miles long and from 11 to 13 miles wide. The western boundary is mainly along the interstream ground-water divide west of Carman Creek near Amityville (pl. 7). The eastern boundary is mainly along the interstream ground-water divide east of Tuthills Creek near Patchogue (pl. 7). Both eastern and western boundaries extend south to the barrier beaches. The northern boundary is along the main ground-water divide that traverses Long Island and the southern boundary is the Atlantic Ocean.




FIGURE 1.—Map of Long Island, New York, showing area of investigation.

METHODS OF INVESTIGATION

Fieldwork began in July 1958 and was completed in March 1961. Well and geologic data were obtained from the files of the New York State Water Resources Commission and from records collected in the field. During the summer of 1958, 44 water-table observation wells were driven in areas where data were scanty. Water-level measurements were obtained at all available observation wells and at several public, industrial, and institutional supply wells. Water samples were collected from the observation wells and analyzed for selected constituents. In October 1958, a water-temperature and water-stage recorder was installed at Champlin Creek at Islip. In November 1958, four temporary recorders were placed in operation on streams for which continuous records of stage were not previously available. The partial-record stream-gaging program in Suffolk County was expanded to include several streams that had never been measured. Three streams, Santapogue River at Lindenhurst, Sampawams Creek at Babylon, and Champlin Creek at Islip, were selected for seepage studies, and discharge measurements were obtained bimonthly at selected sites. In December 1958, a three-element thermograph was placed in operation at Sampawams Creek at Babylon to obtain stream, air, and ground-water temperatures simultaneously.

During May 1959, three lines of shallow observation wells, each line consisting of four wells, were driven adjacent to Champlin Creek to study the relation of ground water to surface water. In addition, three wells were driven directly into the streambed at selected sites to study vertical changes in hydraulic head below the stream. Another line of four wells was driven, in October 1960, just upstream from the gaging station to aid in preparation of a water-table map and to provide additional sampling points for obtaining data on quality of water. To study the effect of ground-water evapotranspiration, a shallow water-table well was dug in August 1960 adjacent to Sampawams Creek, and a recorder was installed to detect water-level fluctuations.

Water samples were collected from selected wells and streams in August 1959, March 1960, September 1960, and March 1961 for determination of synthetic-detergent content. Water samples from four selected wells tapping different aquifers were collected for chemical analysis.

To facilitate office computations of streamflow data, the records of six primary gaging stations in the area and the records for Massapequa Creek at Massapequa in Nassau County were processed by an electronic computer. The processed data included duration tables of daily flow by water years and minimum-mean discharge for each

PREVIOUS INVESTIGATIONS

A study of the water resources of Long Island by Veatch and others (1906), contains some descriptive data on ground water and surface water in the Babylon-Islip area. Maps of the water table of Long Island including the report area have been prepared by Burr and others (1904), Veatch (1906), Suter (1937), Jacob (1945), and Lusczynski and Johnson (1952). A map of the surficial geology of Long Island (Fuller, 1914) and contour maps of the subsurface formations (Suter, deLaguna, and Perlmutter, 1949) contain geologic data on the report area. A report on the geology and hydrology of the nearby Towns of Huntington and Smithtown (Lubke, 1961) has been freely drawn upon for data in the parts of those towns included in the area covered by this report. Perlmutter and Crandell (1959) have described geologic conditions and the occurrence of ground water beneath the barrier beaches. Many of the well logs utilized in the subsurface mapping of geologic units are included in publications of the New York State Water Resources Commission (Leggette and others, 1938; Roberts and Brashears, 1945; and Johnson and others, 1952). Water-level measurements for some observation wells, records of daily discharge for gaging stations, and results of discharge measurements made at partial-record sites, are published in annual water-supply papers and open-file reports of the U.S. Geological Survey.

ACKNOWLEDGMENTS

The writers acknowledge the assistance of well drillers, the New York State Department of Public Works, and the Suffolk County Water Authority, in furnishing hydrologic and geologic data. The New York State Department of Health, the Suffolk County Department of Health, the Suffolk County Water Authority, and several privately owned laboratories furnished much of the chemical data included in the report. R. L. Barnell, formerly of the U.S. Geological Survey, supervised the construction of observation wells, and prepared a preliminary map of the water table.

GEOGRAPHY

TOPOGRAPHY

The Babylon-Islip area lies within the Atlantic Coastal Plain physiographic province and may be subdivided into a small northern region of irregular hills and a large southern region composed of a broad gently sloping plain. These topographic features are mostly

geologic units mapped as Ronkonkoma terminal moraine and Manetto Gravel (pl. 1). The highest land surface altitude on Long Island, about 400 feet above sea level, is on the Ronkonkoma terminal moraine, about 3 miles southwest of Huntington Station. Summit altitudes on the terminal moraine and adjacent hills are commonly as much as 150 feet or more above the outwash plain, which abuts the hills at an altitude of about 120 feet above sea level. The outwash plain is characterized by a gently rolling land surface, which slopes southward at about 20 feet per mile.

Marshlands, at or slightly above mean sea level, fringe the south shore of the area, adjacent to Great South Bay. The bay, which separates the main part of Long Island from the narrow low-lying barrier beaches, is generally less than 3 feet deep in the western part of the area and less than 10 feet deep in the eastern part. In boat channels the depth may be as much as 30 feet.

POPULATION

The substantial population upsurge in Suffolk County since 1950 is primarily the result of migration from New York City. Figure 2 illustrates the rate of population growth in the Towns of Babylon and Islip. The combined population of both towns was 117,021 in 1950, and 315,268 in 1960, an increase of nearly 170 percent. The Town of Babylon had a slightly greater rate of growth than the Town of Islip between 1950 and 1960, which was probably due to its closer location to New York City. The major factor contributing to urbanization of western Suffolk County is the improved rail and highway transportation.

With the exception of the northwestern part which is largely an area of cemeteries, population density in the Town of Babylon is fairly uniform (pl. 6). Centers of greatest population are near the south shore and in eastern parts of the town. In the Town of Islip, population density is greatest west of Connetquot River. Pilgrim State Hospital, the largest hospital in the world, is in the extreme northwestern part of the Town of Islip. Another center of high population density is Central Islip State Hospital, northeast of the headwaters of Champlin Creek. Large areas adjacent to and east of Connetquot River are still in their natural state. The extensive construction activity in western Suffolk County has just begun to reach the eastern part of the Town of Islip, which is still predominantly rural (1961).

INDUSTRY

Industrial growth in the Towns of Babylon and Islip has paralleled population growth. Industrialization of the area has resulted in large measure from decentralization of New York City's industrial core.




FIGURE 2.—Population of the Towns of Babylon and Islip, 1910-60.

Nearly two-thirds of the companies in the area have been established since the end of World War II. Most concerns are small, employing fewer than 100 people; however, two large plants, Republic Aviation Corp. and Fairchild Engine and Aircraft Co., each employ several thousand. Republic Aviation Corp., which is in the northwestern part of the Town of Babylon, is the largest industrial concern in Suffolk County, and employed 16,000 persons in 1958. Of the 625 industrial plants in Suffolk County in June 1956, nearly 60 percent were in the Towns of Babylon and Islip (Leonard and Stonier, 1956, p. 51).

The major industries in Suffolk County are aviation, instruments, electronics, and fabrication of metals; smaller industries include furniture, printing and publishing, textiles, and apparel. The aviation industry has been well established on Long Island since the end of World War I. Production of scientific and professional instruments came as a natural adjunct to the aviation industry. Similarly

21.4.12

8 HYDROLOGY OF THE BABYLON-ISLIP AREA, NEW YORK

the development of the all-metal airplane created a need for metal-fabricating shops. The post-World War II boom in electronics and electrical equipment found Suffolk County well prepared for the new industry owing to its established aviation firms, and the presence of the required skilled personnel.

AGRICULTURE AND VEGETATION

Although the value of crops produced and marketed in Suffolk County ranks highest of all the counties in New York State, agricultural production in the Babylon-Islip area is relatively small. The soils in the southern and eastern parts of the area have been classified by Lounsberry and others (1928, p. 13) as Sassafras Sandy Loam and Dukes Loamy Sand. These soils are not as productive as the soils in the northern and eastern parts of the county. The Sassafras Loam soils in the northwestern and north-central parts of the area are fairly productive. Proximity of this area to metropolitan markets spurred the development of numerous truck farms. The major crops produced by these farms are tomatoes, cauliflower, corn, string beans, peas, and cucumbers. Intensive urbanization, however, has reduced farm acreage so sharply that only a few farms remained in 1961.

Extensive tracts of natural vegetation are limited principally to the northern and eastern parts of the area. Much of the hilly area of the Ronkonkoma terminal moraine is forested with well-developed stands of deciduous trees. Low moisture retention characterizes the sandy, well-drained soils of the eastern part of the area and thereby precludes extensive forest development. Stands of scrub oak or pitch pine are common here in conjunction with an undergrowth of huckleberry, sweetfern, and wintergreen.

GEOLOGY

The composition, thickness, and geologic history of the deposits underlying the Babylon-Islip area determine the water-bearing characteristics, and the lateral and vertical extent of aquifers and aquicludes that form the hydrologic environment. The stratigraphy of the geologic formations is known almost exclusively from well records and samples, as outcrops, especially those of Cretaceous age, are rare.

STRATIGRAPHY

The Babylon-Islip area is underlain by unconsolidated sediments of Cretaceous, Tertiary, and Quaternary age, which lie on crystalline

GEOLOGY

9

member. Above the Raritan Formation is a thick sequence of deposits of late Cretaceous age which is in part, correlative with the Magothy Formation of New Jersey, but also includes some formations that are younger than the Magothy (Perlmutter and Crandell, 1959, p. 1066). Pending a more specific identification, these beds are referred to as the Magothy(?) Formation. Deposits of Quaternary, and possibly Tertiary age overlie the Cretaceous deposits. These consist, from oldest to youngest, of the Mannetto Gravel of doubtful Tertiary (Pliocene ?) age, the Gardiners Clay, and the upper Pleistocene and Recent deposits.

TABLE 1.—Summary of stratigraphy of the Babylon-Islip area

Era	Period	Epoch	Geologic unit	Remarks
Cenozoic	Quaternary	Recent	Recent deposits	Stream, beach, and marsh deposits; small areal extent.
		Pleistocene	Upper Pleistocene deposits	Till and outwash deposits of the Wisconsin Glaciation.
			Gardiners Clay	Fossiliferous marine clay of probable Sangamon age.
	Tertiary(?)	Pliocene(?)	Mannetto Gravel	Formerly believed to be an outwash deposit but now regarded as a stream-terrace deposit; small areal extent.
Mesozoic	Cretaceous	Late Cretaceous	Magothy(?) Formation	Interbedded sand, silt, and clay.
			Raritan Formation	Dominantly clay but may contain some silty and sandy zones locally.
			Lloyd Sand Member	Sand, gravel, and interbedded clay and silt.
Precambrian and early Paleozoic(?)			Bedrock	Schist and gneiss containing some granitic intrusions.

THE BEDROCK

No wells in the Babylon-Islip area have reached bedrock. However, information obtained from wells in nearby parts of Long Island (Suter and others, 1949, p. 30-32, pls. 8 and 9) suggests that the bedrock in the area consists chiefly of schist and gneiss and contains some granitic intrusions. The bedrock is probably correlative in part with igneous and metamorphic rocks of Connecticut.

The bedrock surface dips southeastward at a rate of approximately 50 to 100 feet per mile. The altitude of the surface ranges from about 1,200 feet below sea level in the northwestern part of the area to about 1,800 feet below sea level in the extreme southeastern part. This bedrock surface represents the lower limit of the ground-water

1.5.12

RARITAN FORMATION

The Raritan Formation of Late Cretaceous age directly overlies the bedrock. It is divided into the Lloyd Sand Member below and an unnamed clay member above, and has been correlated with the Raritan Formation of New Jersey on the basis of lithology and stratigraphic position. Because the Raritan Formation has been penetrated by only one test well in the area, its lithology, thickness, and altitude are inferred from data obtained in adjacent areas.

LLOYD SAND MEMBER

The Lloyd Sand Member of the Raritan Formation lies directly on the bedrock surface. It has an estimated thickness of 150 to 300 feet, and is thickest in the southern part of the area. The altitude of the top of the Lloyd is estimated to be approximately 800 to 1,500 feet below sea level, being lowest in the southeast, under Fire Island. It is inferred from examination of cores from wells N3355¹ and S6409 (1½ miles northwest of the northwest corner of the Town of Babylon, and approximately 15 miles east of Lake Ronkonkoma, respectively), and the log of well S42 (pl. 1) that the Lloyd Sand Member underlying the area is probably composed of light-colored sand and gravel and lenses of clay and silty clay. Logs of several wells in eastern Suffolk County, indicate that the Lloyd Sand Member may be more clayey in that area, possibly because of a facies change along the northeasterly strike of the formation.

CLAY MEMBER

On the basis of descriptions of samples from wells in other parts of Long Island and the log of well S42 in the area, the clay member of the Raritan Formation probably consists of 170 to 300 feet of gray, blue, black, red and white clay, silt, and some very fine to fine sand. The altitude of the top of the clay member at well S42 in the northwest corner of the Town of Islip is 670 feet below sea level, and under Fire Island the clay member may be as much as 1,300 feet below sea level.

MAGOTHY(?) FORMATION

The Magothy(?) Formation of Late Cretaceous age has been completely penetrated by only one well (S42) in the area; therefore, its thickness and the nature of its contact with the underlying clay member of the Raritan Formation is known only approximately. The Magothy(?) is about 600 to 700 feet thick in the northern part of the area, and 1,000 to 1,200 feet thick in the southern part. The

¹ Wells in each county on Long Island are numbered serially by the New York State Water Resources Commission. The well number is prefixed by the initial letter of the county in which the well is located. Thus, well N3355 is in Nassau County and well S6409 is in Suffolk County.

altitude of the top of the formation ranges from 200 feet above to more than 100 feet below sea level. Relief on the Magothy(?) surface is due to stream erosion, mostly during late Pliocene and Pleistocene time. Contour lines on the Magothy(?) surface are shown on plate 2.

The Magothy(?) Formation consists mostly of nonfossiliferous beds and lenses of gray and white fine quartz sand, clayey and silty sand, and clay. However, the upper 50 to 200 feet of the formation beneath the barrier beaches consists of beds of fossiliferous green and gray glauconitic clay and sandy clay, which have been tentatively correlated with the Monmouth Group of New Jersey (Perlmutter and Crandell, 1959, p. 1066). Layers of lignite, pyrite, and iron-oxide concretions are common. Medium to coarse sand occurs in lenses irregularly throughout the formation, particularly in the upper and lower zones. West and north of the Babylon-Islip area, where the formation has been more fully explored, a gravel-bearing zone as much as 200 feet thick is found in the lower (basal) zone of the Magothy(?). Records of a few wells suggest that the gravelly zone occurs also in the area.

MANNETTO GRAVEL

The Mannetto Gravel, which consists of stratified and crossbedded quartz gravel, containing some highly weathered erratic material, was considered by Veatch (1906) and Fuller (1914) to represent the earliest deposit of Pleistocene age on Long Island. Currently it is considered to be of doubtful Tertiary (Pliocene(?)) age (Suter and other, 1949, p. 9) and probably correlative with the Bryn Mawr terrace-gravel deposits of Pennsylvania (Cooke, Gardiner, and Woodring, 1943).

The Mannetto Gravel has been recognized only in the northwestern part of the Babylon-Islip area where it crops out in the West and the Half Hollow Hills. It is difficult to distinguish the Mannetto in drillers' logs from the overlying glacial deposits, and its subsurface distribution is not well known.

PLEISTOCENE DEPOSITS

Deposits of Pleistocene age comprise the uppermost 50 to 150 feet of sediments in most of the area. The Jameco Gravel, a major aquifer in western Long Island, is not found in the Babylon-Islip area. The oldest formation of Pleistocene age is the Gardiners Clay, an interglacial deposit. The Gardiners Clay is overlain by upper Pleistocene deposits of Wisconsin age.

GARDINERS CLAY

The Gardiners Clay is a marine interglacial deposit of probable Sangamon age and has been recognized in wells along the south shore.

of the area (pl. 2). Generally it is not found more than a mile north of Great South Bay, although it occurs in the middle of Long Island, at Brookhaven National Laboratory (Weiss, 1954), 11 miles east of the Babylon-Islip area. The Gardiners Clay is overlain by upper Pleistocene deposits of Wisconsin age. It is difficult to determine the lower boundary of the Gardiners Clay from drillers' logs in some places because the underlying Magothy(?) Formation contains beds of similar lithology. The abundance of biotite and chlorite and the presence of foraminifers are used to differentiate the Gardiners from the Magothy(?) Formation where samples are available.

The Gardiners Clay is generally 20 to 40 feet thick, and the altitude of the top of the formation ranges from about 50 to 110 feet below sea level (p. 2). The formation consists of dark-colored clay, lenses of green silt and very fine sand, and thin layers of fine gravel. The layers of clay and silt are generally fossiliferous.

UPPER PLEISTOCENE DEPOSITS

The upper Pleistocene deposits include (a) outwash deposits of stratified medium to coarse sand and gravel, (b) terminal moraine deposits consisting of till and ice-contact deposits of stratified sand and gravel, (c) till, composed of unstratified clay, sand, gravel, and boulders in the form of ground moraine (not exposed), and (d) glacio-lacustrine deposits of clay and silt (not exposed). The surficial distribution of the till and outwash deposits is shown on Plate 1.

Outwash is the most extensive upper Pleistocene deposit in the area. The outwash is underlain by the Gardiners Clay and Magothy(?) Formation, and is partly overlain by younger glacial and Recent deposits. The thickness of the outwash ranges from zero where it abuts Cretaceous and Tertiary sediments in the northwestern part of the area, to more than 100 feet in the eastern part. In parts of the area as much as 120 feet of poorly to well stratified ice-contact deposits are found above the outwash. These deposits form the bulk of the Ronkonkoma terminal moraine, a discontinuous ridge marking the maximum advance of a continental glacier. Quartz is by far the most abundant mineral in the outwash and ice-contact deposits; however, igneous and metamorphic rock particles, muscovite, biotite, and some heavy minerals are common in many beds.

A buried till sheet probably underlies the outwash deposits north of the Ronkonkoma moraine, but the till has not been definitely identified (Lubke, 1961, p. 38). A glacial clay, which underlies much of the Town of Smithtown (Lubke, 1961, p. 39), extends into the northeastern part of the area, but the data are too scanty to define the southern limit.

RECENT DEPOSITS

Deposits of Recent age are found along stream channels, in marshes and ponds, on the barrier beaches, and under Great South Bay. Stream channel deposits consist of a veneer of discontinuous reworked outwash deposits. Beds of very fine sand, silt, and clay are accumulating in marshes and ponds, and under Great South Bay. The barrier beaches consist of beach and dune sands as much as 50 feet thick. The Recent deposits commonly contain shells of mollusks.

GEOLOGIC HISTORY

A knowledge of the geologic history is important in understanding the nature and distribution of the geologic formations. The following summary is adapted largely from a report by Suter, and others (1949, p. 29-46).

During the Cretaceous Period, sediments derived from highlands in northeastern North America were deposited on a relatively flat bedrock surface sloping in a general southeasterly direction. The sediments thus deposited form a part of the present-day coastal plain extending from Long Island to the Gulf of Mexico. Long Island, which was approximately at the strand line of the Cretaceous sea, received mostly continental deposits. The great thickness of sediments deposited near sea level suggest concurrent depression of the bedrock surface during deposition. The variable and lenticular nature of the Cretaceous sediments indicates that deposition took place in shifting river channels, flood plains, swamps, and marshes.

The apparent absence of deposits of Tertiary age on Long Island, except for the nonmarine Mannetto Gravel, suggests either nondeposition or deposition followed by extensive erosion. The present distribution of the Mannetto Gravel is a remnant of the formerly extensive stream deposit.

Large continental glaciers, which were formed at the beginning of the Pleistocene Epoch, resulted in a general lowering of sea level. This lowering, in turn, caused stream rejuvenation and widespread erosion of pre-Pleistocene sediments and deepening of existing valleys. The area was drained then, as now, primarily by southward flowing streams, which cut partly into the Magothy(?) deposits but probably nowhere removed them completely. The eroded surface of the Magothy(?) is shown by contours on plate 2. The high area on the Cretaceous surface in the northwestern part of the area is a remnant of a dissected former divide between northward- and southward-flowing streams.

It is generally believed that the Pleistocene Epoch included four major glaciations, and therefore four cycles of eustatic sea level changes. The first three glacial advances did not reach Long Island

The only evidence of their presence near Long Island is the Jameco Gravel, an outwash deposit found in some parts of the island, but not in the Babylon-Islip area. The Gardiners Clay was deposited in shallow water during an interglaciation (Sangamon) when sea level was relatively high, but about 50 feet below its present altitude. The final, or Wisconsin glaciation of the Pleistocene Epoch, consisted of the Ronkonkoma and Harbor Hill stades. During the first Wisconsin ice advance, meltwater deposited outwash, which was partially overridden by the ice until stagnation occurred. During this stagnation period, stratified sand and gravel in the form of outwash was deposited south of the glacier by meltwater streams, and stratified ice-contact deposits were deposited along the southern terminus of the glacier to form the Ronkonkoma terminal moraine. Melting of the ice left a thin sheet of unstratified ground moraine, which was subsequently buried by younger outwash. The second Wisconsin ice advance did not move as far south as the first. Meltwater streams from the second advance deposited stratified sand and gravel north of the Ronkonkoma terminal moraine and, in places, breached the moraine so that Harbor Hill outwash may be found above the outwash of the Ronkonkoma Stade from which it cannot be distinguished readily.

Some of the large streams in the area did not erode their present valleys, but occupy valleys eroded by streams which issued from glaciers during the Pleistocene Epoch. The largest valleys in the area, those of Carls River, Connetquot River, and Sampawams Creek, can be traced northward to breaches in the Ronkonkoma moraine (pl. 1).

Melting of the continental glaciers was accompanied by a rise in sea level to its present position. Erosion by stream and wave action is presently occurring simultaneously with deposition by these same agents.

HYDROLOGY

HYDROLOGIC ENVIRONMENT

Water in the Babylon-Islip area occurs in the interstices of unconsolidated sediments and in streams and ponds. The ground-water reservoir consists of saturated unconsolidated deposits ranging in thickness from 1,300 to 1,800 feet. The water table, which forms the boundary between the zone of saturation and the overlying zone of aeration (unsaturated zone), is the upper limit of the reservoir, and the impervious bedrock is the lower limit. Water in marshes, ponds, or streams in the Babylon-Islip area is nearly always hydraulically connected with the water table. The availability of ground water and surface water for man's use is controlled to a large extent by the

physical characteristics of the aquifers, streams, and ponds. These characteristics include the capacity of ponds, size and gradient of streams, and the extent, nature of boundaries, and water-bearing properties of aquifers.

AQUIFERS

Three aquifers of wide areal extent are recognized in the deposits underlying the Babylon-Islip area: (a) a shallow water-table aquifer, (b) an intermediate artesian aquifer, and (c) a deep artesian aquifer. Perched water may occur locally in the northern part of the area in lenses of sand and gravel separated from the main water table by deposits of clay or glacial till. The hydrologic environment of perched-water bodies is similar to that of the water-table aquifer; except that perched-water bodies are small and localized and generally are not a dependable source of supply.

WATER-TABLE AQUIFER

The water-table aquifer is composed almost entirely of highly permeable upper Pleistocene deposits that constitute the uppermost zone of the ground-water reservoir. The upper surface of this aquifer is the water table, or top of the zone of saturation. The configuration of the water table (pl. 3) is controlled by the topography, and by the thickness, water-bearing properties, and quantity of recharge to and discharge from the aquifer.

The water table is a subdued replica of the topography. A conspicuous "high" on the water table occurs under the West Hills, south of Huntington Station, where the land surface reaches altitudes as high as 400 feet. Another "high" northeast of Lake Ronkonkoma is coincident in part with the Ronkonkoma terminal moraine where the land surface altitude is commonly as high as 300 feet. The saddle in the ground-water divide south of Hauppauge is probably largely the result of substantial quantities of ground-water discharge into the relatively deep valleys of the Nissequogue and Connetquot rivers, situated north and south of the divide, respectively.

Depth of the water table below land surface is shown on plate 4. In general, the depth to water increases northward from zero along Great South Bay and stream channels to as much as 200 to 300 feet beneath parts of the Ronkonkoma terminal moraine, West Hills, and Half Hollow Hills. The southern half of the area is drained by many effluent streams and depths to water are commonly 25 feet or less.

The lower boundary of the water-table aquifer is defined in most of the area by the occurrence of beds of predominantly low permeability in the upper part of the Magothy(?) Formation. Where the upper part of the Magothy(?) is composed of permeable material, these beds form a part of the water-table aquifer, and the lower surface of the

aquifer is at the first impermeable zone below the top of the Magothy(?). In the extreme southern part of the area, the Gardiners Clay forms the lower boundary of the water-table aquifer.

The water-table aquifer is present everywhere in the Babylon-Islip area, but it very thin in some places and contains salt water in others. In the northwestern part of the area, the water table is mainly in the Magothy(?) Formation rather than in upper Pleistocene deposits. As a result, the water-table aquifer is thin, owing to the clayey nature of most of the saturated beds. The Recent and upper Pleistocene deposits which compose the water-table aquifer beneath Great South Bay contain only salt water. Beneath the barrier beaches, fresh water in the water-table aquifer occurs in small discontinuous lenses in beach and dune deposits of Recent age. These fresh-water lenses are underlain by salt water.

The approximate thickness of the water-table aquifer may be determined by subtracting algebraically the altitude of the top of the Magothy(?) Formation, or Gardiners Clay where it is present (pl. 2), from that of the water table (pl. 3). The thickness of the water-table aquifer ranges from almost zero in the northwestern part of the Babylon-Islip area to more than 100 feet in the eastern part. The average thickness is about 75 feet. Wells screened in the outwash deposits yield as much as 1,500 gpm (gallons per minute). Specific capacities may be as high as 135 gpm per foot of drawdown, but are commonly 40 to 75 in thoroughly developed, large-diameter wells. The specific capacity of a well is a useful parameter for estimating water-bearing properties of an aquifer. Coefficients of transmissibility estimated from specific capacities (Theis and others, 1954) were used to compute the approximate coefficients of permeability of the outwash deposits given in the following table:

Estimated permeabilities of outwash deposits in the water-table aquifer

Well	Screened zone (ft below land)	Yield (gpm)	Specific capacity (gpm per ft)	Approximate thickness of aquifer (feet)	Field coefficient of permeability (gpd per sq ft)
S10,780T.....	50-61	500	37	73	800
S11,151.....	50-61	60	20	64	300
S12,016.....	50-65	1,625	98	67	2,200
S12,421.....	54-76	380	45	70	1,000
S12,710.....	60-70	1,500	100	75	1,800
S12,873.....	78-103	1,212	76	91	1,100
S13,478.....	85-90	830	42	70	900
S16,176.....	81-117	1,625	71	85	1,200
S16,808.....	110-140	1,000	77	88	1,200

The hydraulic coefficients of the water-table aquifer at one well near Central Islip State Hospital are given below:

Hydraulic coefficients of outwash deposits in the water-table aquifer

[Determination by the Hydrologic Laboratory, U.S. Geol. Survey]

Well	Depth (feet)	Specific retention (percent)	Specific yield (percent)	Porosity (percent)	Coefficient of permeability (gpd per sq ft)
S16,808.....	27-32	2.2	25	27.2	700

Because of the high permeability of the beds and generally shallow depth to the water table, wells are both productive and economical in most of the area underlain by outwash deposits (pl. 1). The water-table aquifer presently (1961) supplies approximately 84 percent of the total pumpage of ground water in the Babylon-Islip area.

INTERMEDIATE ARTESIAN AQUIFER

The intermediate artesian aquifer is composed of lenticular permeable deposits of the Magothy(?) Formation. The upper surface of the clay member of the Raritan Formation defines the lower boundary of the aquifer. Clayey and silty lenses in the upper part of the Magothy(?) Formation and the Gardiners Clay, where present, constitute the upper boundary. Unlike the top of the water-table aquifer, the upper boundary of the intermediate artesian aquifer generally is not a sharply defined surface such as the water table, but is a transitional zone of relatively low permeability. Where clayey confining beds are replaced by sandy zones, hydraulic continuity exists between the water-table and intermediate artesian aquifers.

Because permeable zones in the Magothy(?) Formation are lenticular, it is difficult to predict their occurrence and thickness, except for a basal zone. As in many parts of western Long Island, an extensive zone of sand and gravel about 100 feet thick probably lies immediately above the clay member of the Raritan Formation in the Babylon-Islip area but the data are too scanty to permit mapping the zone as a separate unit. (See well S42, pl. 1.) Test drilling is generally necessary to locate permeable zones which can yield as much as 1,500 gpm to individual wells. Specific capacities of wells range from 1 to 49 gpm per foot of drawdown. Those wells tapping zones composed chiefly of sand and gravel commonly have specific capacities ranging from 20 to 40 gpm per ft. The method of computing transmissibilities

from specific capacities (Theis and others, 1954) yields only approximate values for the intermediate artesian aquifer because of the unknown effects of partial penetration and the heterogeneous nature of the aquifer. However, in the absence of other laboratory or field determinations, the specific capacity is used as a means of estimating the coefficients of transmissibility of the aquifer. Coefficients of transmissibility estimated from specific capacities of four wells screened in various zones of the aquifer were used to compute the coefficients of permeability listed in the following table:

Estimated permeabilities of water-bearing zones in the intermediate artesian aquifer
(Thickness of water-bearing zone determined from well log)

Well	Screened zone (feet below mean sea level)	Thickness of water-bearing zone (feet)	Specific capacity (gpm per ft)	Field co- efficient of permeability (gpd per sq ft)
S11279	270-306	36	2.5	400
S14583	106-132	26	13.9	400
S15775	180-220	40	21.7	800
S16256	500-552	52	26.7	1,200

Wells S15775 and S16256 are screened in coarse sand and gravel whereas wells S11279 and S14583 are screened in fine to medium sand. Hence on the basis of data in the above table, approximate coefficients of permeability of 1,000 gpd (gallons per day) per square foot and 400 gpd per sq ft may be assumed for coarse sand and gravel and for fine to medium sand, respectively. The aquifer also consists of lenses of very fine to fine sand, silt, and clay, for which an average permeability of 20 gpd per sq ft may be assumed (Wenzel, 1942, p. 13). Based on the geologist's log of well S42 (Leggette and others, 1938, p. 30-32) 29 percent of the intermediate aquifer is sand and gravel, 52 percent is predominantly sand, and 19 percent is fine sand, silt, and clay. On the basis of these data, the average coefficient of permeability of the intermediate aquifer is estimated to be about 500 gpd per sq ft.

DEEP ARTESIAN AQUIFER

The deep artesian aquifer is the lowermost water-bearing zone in the ground-water reservoir. Its boundaries coincide with those of the Lloyd Sand Member of the Raritan Formation. Although no wells penetrate the deep artesian aquifer, it probably underlies the entire area. The bedrock, which contains only small quantities of water, marks the lower limit of the deep aquifer. The upper limit is at the base of the clay member of the Raritan Formation which acts as an effective confining unit for the deep artesian aquifer.

Specific capacities of 10 to 20 gpm per ft of drawdown are commonly reported for wells tapping the Lloyd Sand Member in Nassau

County. Test wells screened in the Lloyd in central Suffolk County at Brookhaven National Laboratory had specific capacities of only 2.0 and 2.5 gpm per ft. If the Lloyd becomes increasingly clayey to the east (as the scanty data suggest), specific capacities of wells may range from about 10 to 20 gpm per ft in the western part of the area and 5 to 15 gpm per ft in the eastern part.

STREAMS AND PONDS

Surface-water resources have played a significant role in the growth of Long Island since its original settlement. Early industrial requirements focused on a need for power to operate sawmills and gristmills. The first gristmill in the Babylon-Islip area was constructed about 1860 on Connetquot River (Sander, 1954, p. 64). Artificial ponds were developed on many streams to supply the head required to drive water wheels. When steam and electric power came into use, gristmills and sawmills were abandoned, and now the principal use of streams and ponds is for recreation.

To meet demands for water by New York City, the surface-water resources of Nassau County were intensively developed in the early 1900's. A plan was proposed shortly thereafter to tap about 10 large streams in Suffolk County for additional supplies. The plan was abandoned only after strong protests were voiced throughout the county, especially by officials who envisioned the day when this invaluable resource might be required for local use. A county-wide plan is now in effect to purchase and preserve, in its natural state, land bordering on the few remaining undeveloped streams to be used for recreation and conservation.

All major streams in the area flow in a southerly direction, and, in general, are less than 3 miles long. The largest streams are Carlls River in the Town of Babylon, and Connetquot River in the Town of Islip. Both streams have fairly well developed tributary systems, and extend approximately 5 miles above the head of tidalwater. All streams have gentle gradients that average about 2 feet per 1,000 feet.

With the exception of Lake Ronkonkoma, almost all ponds in the area are manmade. In the late 1800's ponds were utilized for industrial purposes; however, most are used only for recreation at present. Lake Ronkonkoma occupies a kettle hole whose bottom extends about 60 feet below the water table. The lake has a surface area of about 220 acres. The total area of all ponds and lakes is about 1.4 square miles or 0.7 percent of the total Babylon-Islip area.

HYDROLOGIC CYCLE

The term "hydrologic cycle" denotes the general circulation of water in its various states (liquid, solid, or gaseous) from ocean to

1.10.1

atmosphere, from the atmosphere over and through the ground, and back to the ocean again.

Atmospheric water vapor will, if favorable conditions exist, condense into tiny droplets which increase in size until they can no longer be supported by air currents. If temperatures are above freezing, water vapor will precipitate as rain. If temperatures are at or below freezing during the condensation process, water vapor will precipitate as snow, sleet, or hail.

The time required for precipitation to return to the atmosphere depends principally upon the nature of the incident surface. Impervious or water-saturated surficial deposits cause precipitation to flow overland into streams or ponds. Precipitation falling upon and retained by vegetal surfaces will evaporate and return directly to the atmosphere. Some of the precipitation reaching the land surface will also evaporate; however, a substantial part will infiltrate into the ground if the soil is permeable. The first demand the infiltrating water must satisfy is that of the soil. Soil moisture is depleted primarily by vegetation and direct-surface evaporation. After soil-moisture requirements are fulfilled, residual water percolates slowly downward through interstices in the earth materials underlying the soil zone until it reaches the ground-water reservoir. While in the ground-water reservoir, the water moves slowly down gradient and is discharged into streams, bays, and the ocean. After discharge into the ocean, water completes the hydrologic cycle by eventually returning to the atmosphere by evaporation.

QUANTITATIVE HYDROLOGY

One of the principal objectives of this report was to evaluate the water balance for the ground-water reservoir. The accomplishment of this objective requires the collection and interpretation of data on precipitation, ground-water levels, and streamflow. These data are

In evaluating the water balance, the inflow or recharge to the ground-water reservoir is equated to the outflow or discharge, plus or minus changes in the reservoir storage. Recharge is essentially equal to discharge if the period of study selected is long enough to minimize the effect of changes in ground-water storage. The hydrologic factors affecting the water balance include precipitation, ground-water runoff, direct runoff, evapotranspiration, and underflow.

Precipitation, the largest factor, is fortunately the easiest to measure. Five U.S. Weather Bureau cooperative stations in or near the area have records of sufficient length to be of value in determining average precipitation. The average streamflow of the area was computed

from the existing network of primary, secondary, and partial-record gaging stations. That part of total streamflow which reflects direct runoff was computed from an analysis of the discharge hydrographs of the primary gaging stations; the remainder of the streamflow represents ground-water runoff. Precipitation and streamflow are the factors most amenable to quantitative analysis. Estimates of evapotranspiration losses are much more difficult to obtain. These estimates depend on studies made in nearby areas where geologic conditions do not preclude computing evapotranspiration indirectly. Ground-water evapotranspiration was computed from an analysis of water-table fluctuations in a part of the area where such losses are significant. The only unknown factor in the water-balance equation for the area is underflow at the north shore of Great South Bay (submarine outflow) which, therefore, may be computed from the equation.

To evaluate the various hydrologic factors, it is desirable to compute data for a period common to all. Too, as previously noted, it is essential to choose a period of sufficient length to eliminate the effect of change in storage in the ground-water reservoir. The period selected for study was the 1944-59 water years which corresponds to the length of the longest streamflow record in the Babylon-Islip area. Hence, all computations represent the averages for this period and may be assumed to be approximately equivalent to the true long-term averages.

PRECIPITATION

Precipitation in its various forms is the source of all water on Long Island. A favorable geographic location with respect to available sources of moisture provides Long Island with an abundant and fairly uniform supply of precipitation throughout the year. The two principal meteorological factors which produce precipitation on Long Island are the active extra-tropical cyclonic disturbances, most prevalent from November through April, and local convective summer storms. A secondary source of precipitation is tropical cyclones, often of spectacular size, but fortunately of infrequent occurrence. The primary sources of moisture for all storms affecting Long Island are the Gulf of Mexico and the southwestern part of the North Atlantic Ocean.

There are no long-term rainfall stations within the Babylon-Islip area; however, the records for Farmingdale, Babylon, and Brentwood (pl. 7), are of sufficient length to be of value in computing the mean annual precipitation for the base period. In addition, the rainfall stations at Patchogue (pl. 7) and Setauket (fig. 1), although outside the area, are considered to be sufficiently close that their records may be given some weight in determination of mean annual precipitation. With the

1.11.12

exception of the records for Setauket, which data back to 1886, the records of these stations go back less than 25 years.

Precipitation is heaviest in the south-central part of the Babylon-Islip area, as comparison of the mean annual precipitation at Babylon with other stations in or near the area shows (table 2). Somewhat heavier precipitation than that recorded at Babylon may occur in the hilly region of the northern part of the area; however, owing to lack of data, the orographic influence is not known. The apparent heavier rainfall at Babylon may be due to any one, or to a combination of, the following reasons: (a) proximity to the ocean, (b) local effects such as rain-gage exposure, or (c) to chance. A comparison of the mean annual precipitation at New York City and Setauket for the base period (1944-59 water years) with the long-term averages in table 2 indicates only slight variations. For example, average precipitation during the base period was about three-quarters of an inch greater than that for the long-term period at New York City, and less than a quarter of an inch lower than at Setauket. It may be inferred, therefore, that a water balance computed for the base period will be representative of the long-term averages. For the Babylon-Islip area, the mean annual precipitation for the base period was computed to be 46.3 inches by the Thiessen method (Williams, 1950, p. 276-278). Only slight weight was given to the Setauket record in the computations and none at all to that of New York City, which is too distant from the area.

TABLE 2.—Mean, maximum, and minimum annual precipitation, in inches, for selected stations

Station	Period of record	Mean	Maximum	Minimum	Mean for base period (1944-59)
New York City.....	1929-1959	42.3	59.7	28.8	43.0
Setauket.....	1886-1960	45.0	59.3	33.6	44.8
Farmingdale.....	(¹)	45.9	56.6	39.4	46.3
Babylon.....	1939-59	45.6	56.7	35.7	46.7
Hewlettwood.....	1942-59	46.0	60.0	36.4	45.9
Patchogue.....	1938-59	45.0	58.5	36.0	45.0

¹ 1921-22, 1926-33, 1940-50.

² Adjusted to base period.

On the basis of the records for Setauket and New York City for the period 1886-1960, annual precipitation may be expected to range from 30 to 60 inches in the area (fig. 3). If the 74-year record at Setauket is considered representative of average precipitation in the area, the curve in figure 3 may be used to predict future rainfall. For example, the probability is about three chances in five that annual precipitation in any one year will be between 40 and 50 inches.





FIGURE 3.—Annual precipitation-duration curves for New York City and Setauket, 1886-1960.

1.12.12

2. 1. 16

**Hydrogeologic Data from Selected Wells
and Test Holes in Suffolk County,
Long Island, New York, 1972-80**



U.S. GEOLOGICAL SURVEY
Open-File Report 81-500

Prepared in cooperation with
SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
SUFFOLK COUNTY WATER AUTHORITY



2.2.16

HYDROGEOLOGIC DATA FROM SELECTED WELLS
AND TEST HOLES IN SUFFOLK COUNTY,
LONG ISLAND, NEW YORK, 1972-80
By Richard K. Krulikas

U.S. GEOLOGICAL SURVEY
Open-File Report 81-500

Prepared in cooperation with
SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
SUFFOLK COUNTY WATER AUTHORITY



Syosset, New York

1981

2.5.16

Table 2.--Explanation (continued)

Water Level (feet below land-surface datum)

The water level given is the reported original static water level, in feet above or below land surface, when the well was completed.

Date of Measurement

The date of water-level measurement is given by month (M), day (D), and year (Y).

Lift Type

The following abbreviations indicate the type of pump or other conveyance known or assumed to have been used in 1977 to bring water to the surface.

CENT	centrifugal	TURB	turbine
JET	jet	NONE	no pump in well
SUBM	submersible	OTHR	some other type of lift

Aquifer Developed

The following abbreviations indicate the hydrogeologic unit that yields water to the well. Where two or more units yield water to the well, the probable principal unit is given.

UPGLAC	Upper glacial aquifer
GARD	Gardiners Clay
MONMOUTH	Monmouth greensand
MAGOTHY	Magothy aquifer
RARITAN	Raritan clay
LLOYD	Lloyd aquifer

Table 2.--Explanation (continued)

Specific Capacity

The value in this column is the number of gallons per minute pumped from the well per foot of drawdown in the well, as reported by drillers.

Abbreviations

COORD	coordinates
D	day
DIAM	diameter
FT	feet
GPM/FT	gallons per minute pumped per foot of drawdown in the well
IN	inches
LSD	land surface datum
M	month
MEAS	measurement
NGVD	National Geodetic Vertical Datum of 1929.
Y	year

Table 2.--Hydrologic units and well-completion data

HYDROLOGIC UNIT PENETRATED AND ELEVATION OF UNIT SURFACE, IN FEET ABOVE OR BELOW NATIONAL GEODETIC VERTICAL DATUM OF 1929											
Location of well			Well depth (ft)	Upper glacial aquifer	Gardiners Clay	Monmouth greensand	Magothy aquifer	Raritan clay	Lloyd aquifer	Bedrock	
Well number	Map coord	Latitude and Longitude									
18075	D10	404707 0731905.01									
18261	D10	404707 0731905.01	627	110							
18621	D10	404704 0731914.01	388	110			-155				
19767	F10	405506 0731801.01	201	110							
20041	C 8	404444 0732511.01	28	15							
			268	80							
20042	C 8	404444 0732511.02					-280				
21734	F 8	405519 0732919.01	585	80							
22303	R10	404321 0731820.01	453	64			-298				
22548	D10	404705 0731907.01	285	10	- 62			-145			
22823	D11	404918 0731326.01	415	114				-151			
			400	125							
23433	D18	404841 0723935.01	321	15							
23462	D11	404813 0731328.01	400	125			-103				
23524	E13	405158 0730300.01	446	110							
23609	E12	405319 0730829.01	484	125							
26247	E 9	405058 0732338.01	447	178			-324				
26490	D11	404505 0731317.01	110	40							
26600	E12	405209 0730855.01	323	123							
26681	E 8	405246 0732523.01	600	10							
29743	F24	405356 0720639.01	302	50	-113			-390	-470		
29823	D 9	404521 0732252.01	622	76		-120	-239				
							- 6				
30008	E 9	405058 0732338.01	488	185							
30114	B 9	408800 0732034.01	327	10							
30118	D12	404914 0730956.03	192	58	-100		-133				
30421	D 9	404718 0732453.01	272	125							
30506	D 9	404515 0732253.01	621	75							
31269	F13	405512 0730105.03	337	138							
31711	E11	405143 0731100.01	600	125			- 94				
31734	E13	405455 0730258.02	1125	163							
31976	F18	405936 0723542.01	112	65			- 55	-573	-730		
32821	F12	405614 0730610.01	600	75							
33060	E12	405157 0730740.01	410	95			3	-495			
33203	E12	405149 0730756.01	580	95							
33204	E12	405149 0730752.01	517	95							
33205	E12	405150 0730748.01	436	93							
33206	E12	405154 0730801.01	581	93							
33991	D11	404511 0731127.01	696	35							
34016	E13	405156 0730451.01	712	95	-68		- 93				
34651	E12	405147 0730740.01	417	94							
34652	E12	405148 0730755.01	102	94							
34653	E12	405149 0730801.01	700	93							
34893	F14	405517 0725749.01	840	125							
36448	F15	405627 0725407.01	404	132			-555	-719			
36711	E14	405333 0725629.01	143	81							
36965	F22	405639 0721811.01	181	52			- 83				
37140	D11	404510 0731123.01	330	35	-69		- 86				
37276	D11	404918 0731330.01	400	40							
37494	D14	404717 0725956.03	622	60							
37991	E15	405456 0725327.01	141	102			-300				
38035	D 9	404723 0732453.01	430	130							
38194	F14	405652 0725900.02	775	157							
38320	D13	404756 0730255.02	173	75			-593				
38321	D13	404756 0730255.03	303	63							
38595	E12	405257 0730501.01	605	108			-133				
38784	E13	405256 0730456.02	603	105			-200				
38785	E 9	405135 0732355.01	701	202			-200				

2.8.16

from selected wells and test holes in Suffolk County, New York.

WELL-COMPLETION DATA												
Well Number	Year Completed	Elevation of LSD (ft above or below NGVD)	Use of Water	Use of Well	Screen Setting (ft above or below NGVD)	Total Screen Length (ft)	Diam of Well (in)	Water level (ft below LSD)	Date of Meas. (M-D-Y)	Lift Type	Acquirer Device used	Specific Capacity (GPM/ft)
18075	1959	110	UNSD	TEST							MAGOTHY	
18261	1960	110	P.S.	WTDR	-180 TO -263	83	16	60	01-13-60		MAGOTHY	
18621	1960	110	P.S.	WTDR	- 34 TO - 91	57	36	51	05-23-60		UPCLAC	34
19767	1961	15	IRR	WTDR							UPCLAC	
20041	1962	80	P.S.	WTDR	-110 TO -188	78	12	25	09-05-61	TURB	UPCLAC	75
20042	1962	80	P.S.	WTDR	-444 TO -505	61	20	25	07-15-61	TURB	MAGOTHY	40
21734	1962	64	CON	WTDR	-377 TO -389	12	6				UPCLAC	
22303	1963	10	CON	WTDR	-263 TO -275	12	4				MAGOTHY	
22548	1964	114	UNSD	UNSD	-233 TO -289	56	42				MAGOTHY	
22823	1964	125	IND	WTDR	-224 TO -275	51	12				MAGOTHY	
23433	1965	15	IRR	WTDR	-255 TO -306	51	10	4	03-02-65		MAGOTHY	
23462	1965	125	UNSD	UNSD	-249 TO -275	26	12				UPCLAC	
23524	1965	110	P.S.	WTDR	-210 TO -326	116	16	66	08-25-65	TURB	UPCLAC	41
23609	1965	125	FRPT	WTDR	-329 TO -359	30	10	94	05-01-65	TURB	MAGOTHY	30
26247	1965	178	P.S.	WTDR	- 86 TO -269	183	20	133	12-14-65	TURB	MAGOTHY	79
26490	1965	40	P.S.	WTDR	- 32 TO - 67	35	30	17	06-26-65	TURB	UPCLAC	60
26600	1966	123	UNSD	TEST	-147 TO -167	20	8	82	03-11-66		UPCLAC	3
26681	1966	10	P.S.	WTDR	-515 TO -587	72	16	7	04-24-66		UPCLAC	18
29743	1967	50	UNSD	OBS	- 89 TO -100	11	6	45	01-11-67		MAGOTHY	2
29823	1967	76	UNSD	TEST							MAGOTHY	
30008	1967	185	P.S.	WTDR	-238 TO -298	60	20	137	03-20-67	TURB	MAGOTHY	61
30114	1967	10	IRR	WTDR	-134 TO -200	66	10	8	05-22-67	TURB	MAGOTHY	4
30118	1967	58	P.S.	WTDR	- 93 TO -134	51	16				UPCLAC	
30421	1967	125	ARCD	WTDR				67	07-07-67	TURB	UPCLAC	6
30506	1967	75	P.S.	WTDR	-471 TO -543	62		26	07-25-67		MAGOTHY	41
31269	1967	138	UNSD	TEST			6				MAGOTHY	
31711	1967	125	UNSD	TEST							MAGOTHY	20
31734	1967	165	UNSD	TEST							MAGOTHY	
31976	1967	65	IND	WTDR	- 16 TO - 47	31	12			TURB	UPCLAC	
32821	1968	75	UNSD	TEST							MAGOTHY	
33060	1968	95	ARCD	WTDR	-262 TO -315	53	16				UPCLAC	
33203	1968	95	OTHR	RECH	-425 TO -485	60	16	50	08-29-68		UPCLAC	75
33204	1968	95	OTHR	RECH	-361 TO -422	61	16	53	09-17-68		UPCLAC	37
33205	1968	93	ARCD	WTDR	-282 TO -343	61	16	50	09-20-68	TURB	UPCLAC	36
33206	1968	93	OTHR	RECH	-428 TO -488	60	16	53	08-13-68		UPCLAC	40
33991	1968	35	UNSD	TEST							MAGOTHY	
34016	1968	95	UNSD	OBS			8				MAGOTHY	
34651	1969	9-	ARCD	WTDR	-258 TO -318	60	16	46	04-10-69	TURB	UPCLAC	27
34652	1969	9-	ARCD	WTDR	- 45 TO - 76	31	16	32	03-12-69	TURB	UPCLAC	52
34653	1969	93	UNSD	OBS	-505 TO -607	102	8	49	03-13-69		UPCLAC	54
34893	1969	125	UNSD	OBS							MAGOTHY	
36448	1969	132	UNSD	OBS			10				UPCLAC	
36711	1970	81	UNSD	OBS	- 28 TO - 58	30	12	55			UPCLAC	239
36965	1970	52	P.S.	WTDR	- 71 TO -101	30	12	36	04-15-70	TURB	UPCLAC	
37140	1970	35	P.S.	WTDR	-225 TO -295	70	20	18	05-13-70		MAGOTHY	39
37276	1970	40	ARCD	WTDR	-309 TO -359	50	36	13	05-01-70	TURB	UPCLAC	40
37494	1970	60	UNSD	UNSD			42				MAGOTHY	
37991	1970	102	P.S.	WTDR	- 13 TO - 39	26	16	45	09-14-70	TURB	UPCLAC	49
38035	1970	130	UNSD	UNSD			38				UPCLAC	
38194	1970	157	P.S.	WTDR	-513 TO -573	60	20	133	12-10-70		UPCLAC	21
38320	1970	75	P.S.	WTDR	- 35 TO - 82	47	20	39	11-18-70		UPCLAC	54
38321	1971	63	P.S.	WTDR	-176 TO -237	61	20	38	01-08-71		MAGOTHY	40
38595	1970	105	UNSD	TEST							MAGOTHY	
38784	1970	105	P.S.	WTDR	-422 TO -492	70	20	44	09-23-71	TURB	MAGOTHY	
38785	1971	202	P.S.	WTDR	-370 TO -461	91	20	157	03-30-71		UPCLAC	67

2.9.16

Table 2.—Hydrologic units and well-completion data

HYDROLOGIC UNIT PENETRATED AND ELEVATION OF UNIT SURFACE, IN FEET ABOVE OR BELOW NATIONAL GEODETIC VERTICAL DATUM OF 1929										
Location of well			Well depth (ft)	Upper glacial aquifer	Gardiners Clay	Monmouth greensand	Magothy aquifer	Raritan clay	Lloyd aquifer	Bedrock
Well number	Map coord	Latitude and Longitude								
38916	E12	405418 0730649.02	845	227			- 27	-563		
39184	E12	405147 0730804.01	700	93						
39185	E12	405147 0730805.02	619	93						
39186	E12	405147 0730803.03	683	93						
39187	E12	405147 0730804.04	698	95						
39333	E11	405208 0731314.01	658	64			-422			
39347	E12	405054 0730949.01	176	128						
39518	E11	405118 0731238.01	725	76			- 64	-684		
39531	D11	404614 0731230.01	289	53			-105			
39535	B11	403819 0731117.01	461	5	- 92	- 98	-313			
39536	E 9	405345 0732038.01	615	173						
39709	C 8	404556 0732522.01	705	85			-268			
40057	E12	405016 0730903.01	623	110			-154			
40161	E14	405335 0725628.02	138	80						
40331	E13	405221 0730212.01	694	87			-408			
40333	E10	405236 0731709.01	525	110						
40407	F19	405636 0732648.01	140	10						
40497	D10	404606 0731746.02	284	74	- 50		- 64			
40498	C 9	404230 0732041.01	748	24	- 54		- 60			
40709	E13	405223 0730219.01	485	90						
40710	E11	405207 0731314.01	463	70			-295			
40711	E11	405209 0731314.01	273	70						
40818	D12	404610 0730507.01	754	55	-101		-113			
40837	F13	405510 0730453.02	810	195			- 81	-573		
40838	F13	405510 0730453.02	294	195			- 81			
40980	E12	405418 0730649.01	578	225			1			
40981	D12	404820 0730735.01	694	100			-124			
41341	D14	404807 0725907.01	703	73			-127			
41342	E12	405021 0730624.01	663	130			-384			
41343	E13	405217 0730116.01	650	110			-186			
41344	D11	404919 0731428.01	693	79			- 47			
41345	E10	405249 0731928.01	807	237						
41358	B10	403817 0731633.02	290	10	- 73		-280			
41313	E12	405120 0730824.01	719	108			-149			
42053	E11	405032 0731407.01	713	50			- 56			
42054	E11	405043 0731229.01	723	40			-240			
42225	E 9	405015 0732342.01	790	110						
42226	E12	405015 0730902.01	270	110						
42227	E12	405016 0730903.01	253	110						
42270	E11	405119 0731237.00	649	76			- 64			
42473	E11	405119 0731237.02	649	76			- 64			
42504	E13	405215 0730115.01	223	110						
42505	E13	405213 0720113.02	233	110						
42760	E12	405054 0730508.02	173	130						
42761	D13	404756 0730255.01	333	75			-115			
42762	C10	404305 0731614.01	714	26	- 56		- 64			
42827	D11	404511 0731123.01	663	35	- 62		- 92			
43001	E 8	405113 0732609.01	590	230				-337		
43010	D16	404804 0724838.01	700	20	- 76	- 94	-144			
43088	D10	404640 0731521.01	902	90			- 80	-772		
43101	E13	405140 0730240.01	703	40			-116			
43117	E13	405256 0730456.03	552	102			-305			
43516	D13	404618 0730356.01	803	55			-101			
43808	C 8	404323 0732534.01	59	66						
43810	C 9	404124 0732416.02	76	30						

2.10.16

from selected wells and test holes in Suffolk County, New York.

WELL-COMPLETION DATA

Well Number	Year Completed	Elevation of LSD (ft above or below NGVD)	Use of Water	Use of Well	Screen Setting (ft above or below NGVD)	Total Screen Length (ft)	Diam of Well (in)	Water level (ft below LSD)	Date of Meas. (M-D-Y)	Lift Type	Aquifer Developed	Specific Capacity (GPM/ft)
38916	1971	227	UNSD	TEST							MAGOTHY	
39184	1971	93	ARCD	RECH	-507 TO -607	100	10				UPGLAC	
39185	1971	93	ARCD	RECH	-426 TO -526	100	10				UPGLAC	
39186	1971	93	ARCD	RECH	-490 TO -590	100	10				UPGLAC	
39187	1971	95	ARCD	RECH	-503 TO -603	100	10				UPGLAC	
39333	1971	64	UNSD	TEST	-546 TO -568	22	16	33	04-09-71		MAGOTHY	
39347	1971	128	P.S.	WTDR	- 8 TO - 48	40	10	69	07-06-71		UPGLAC	109
39518	1971	76	UNSD	TEST	-514 TO -614	100	8	47			MAGOTHY	
39531	1971	53	P.S.	WTDR	-149 TO -219	70	20	23	10-01-71	TURB	MAGOTHY	37
39535	1971	5	P.S.	WTDR	-313 TO -456	143	12	FLOWING	12-20-72	TURB	MAGOTHY	
39536	1971	173	P.S.	WTDR	-362 TO -442	80	20	155	09-01-71	TURB	UPGLAC	30
39709	1971	55	P.S.	WTDR	-565 TO -620	55	20	36	07-21-71	TURB	MAGOTHY	3
40057	1971	110	UNSD	TEST							MAGOTHY	
40161	1971	80	P.S.	WTDR	- 14 TO - 54	40	20	43	07-28-71	TURB	UPGLAC	35
40331	1971	87	P.S.	WTDR							UPGLAC	
40333	1972	110	UNSD	WTDR	-405 TO -415	10	6	74	08-27-72	SUBH	UPGLAC	7
40407	1971	10	FRPT	WTDR	-109 TO -129	20	16	4	09-13-71		UPGLAC	
40497	1971	74	P.S.	WTDR	-150 TO -210	60	10	32		TURB	MAGOTHY	44
40498	1972	24	P.S.	WTDR	-648 TO 718	70	20	4	05-10-72	TURB	MAGOTHY	54
40709	1971	90	P.S.	WTDR	-330 TO -390	60	20	37	10-12-71		UPGLAC	87
40710	1971	70	P.S.	WTDR	-297 TO -387	90	20	33	10-28-71		MAGOTHY	126
40711	1971	70	P.S.	WTDR	-153 TO -203	50	20	37	09-08-71		UPGLAC	80
40818	1971	55	UNSD	TEST			6				MAGOTHY	
40837	1972	195	P.S.	WTDR	- 38 TO - 92	54	20	160	01-10-72	TURB	MAGOTHY	9
40838	1972	195	P.S.	WTDR	- 44 TO - 99	55	20	162	04-04-72	TURB	UPGLAC	10
40980	1972	225	P.S.	WTDR	-279 TO -348	69	20	191	02-10-72	SUBH	MAGOTHY	30
40981	1971	100	UNSD	TEST	-555 TO -575	20	8	58	11-02-71		MAGOTHY	7
41341	1972	73	UNSD	TEST							MAGOTHY	
41342	1972	130	UNSD	TEST							MAGOTHY	
41343	1971	110	UNSD	TEST							MAGOTHY	
41344	1971	79	UNSD	TEST							MAGOTHY	
41345	1972	237	UNSD	TEST							UPGLAC	
41358	1972	10	UNSD	UNSD			14				MAGOTHY	
41513	1972	108	UNSD	TEST							MAGOTHY	
42053	1972	50	UNSD	TEST							MAGOTHY	
42054	1972	40	UNSD	TEST			18				MAGOTHY	
42225	1972	110	P.S.	WTDR	-580 TO -680	100	20	114	04-21-72	SUBH	MAGOTHY	48
42226	1972	110	P.S.	WTDR	- 95 TO -157	62	20	65	04-10-72		UPGLAC	73
42227	1972	110	P.S.	WTDR	- 78 TO -140	62	20	65	01-31-72		UPGLAC	54
42270	1972	76	UNSD	UNSD	-499 TO -573	74	20	47	01-31-72		MAGOTHY	23
42473	1972	76	UNSD	UNSD	-503 TO -573	70	20	45	02-08-72	TURB	MAGOTHY	24
42504	1972	110	P.S.	WTDR	- 51 TO -117	66	20	53	06-28-72		UPGLAC	
42505	1972	110	P.S.	WTDR	- 63 TO -123	60	60	68	06-26-72		UPGLAC	
42760	1972	130	P.S.	WTDR	- 7 TO - 43	36	20	72	08-28-72	TURB	UPGLAC	102
42761	1972	75	P.S.	WTDR	- 91 TO -238	167	20	50	05-23-72	TURB	MAGOTHY	46
42762	1972	26	P.S.	WTDR	-624 TO -684	60	20	8	04-10-72		MAGOTHY	43
42827	1972	35	P.S.	WTDR	-563 TO -625	62	20				MAGOTHY	
43001	1972	230	P.S.	WTDR	-216 TO -296	80	20	189	09-07-72	TURB	UPGLAC	95
43010	1972	20	UNSD	TEST	-660 TO -680	20				SUBH	MAGOTHY	
43088	1972	90	UNSD	TEST							MAGOTHY	
43101	1972	40	UNSD	TEST							MAGOTHY	
43117	1972	102	P.S.	WTDR	-366 TO -451	85	20	49	05-08-72	TURB	MAGOTHY	55
43516	1972	55	UNSD	TEST							MAGOTHY	
43808	1972	66	UNSD	OBS	22 TO 12	10	6	5			UPGLAC	
43810	1972	30	UNSD	OBS	- 31 TO - 41	10	6				UPGLAC	

2.11.16

Table 2.--Hydrologic units and well-completion data

HYDROLOGIC UNIT PENETRATED AND ELEVATION OF UNIT SURFACE. IN FEET ABOVE OR BELOW NATIONAL GEODETIC VERTICAL DATUM OF 1929											
Location of well				Well depth (ft)	Upper glacial aquifer	Cardiner's Clay	Monmouth greensand	Magothy aquifer	Raritan clay	Lloyd aquifer	Bedrock
Well number	Map coord	Latitude and Longitude									
✓43811	D 9	404530 0732411.01	90	102							
✓43813	C 9	404158 0732258.02	78	35							
✓43814	C 9	404455 0732150.01	50	60							
✓43816	C 9	404237 0732206.02	80	40							
✓43817	D 9	404618 0732050.01	56	70							
✓43819	C 9	404250 0732023.02	78	30							
✓43820	D10	404649 0731840.01	98	110							
✓43822	C10	404302 0731855.02	74	20							
44032	E12	405147 0730649.01	753	118				-136			
44137	C10	404432 0731513.01	720	39	- 46			- 73			
44186	E13	405004 0730227.01	673	180				- 88			
44378	E 9	405322 0732114.01	467	27				-107			
44467	E15	405122 0725407.00	713	105							
44640	F14	405710 0725713.01	205	135							
44774	D11	404920 0731428.01	293	79							
44775	E13	405407 0730009.01	755	150							
✓44914	E 9	405254 0732142.01	25	30							
✓44918	D13	404812 0730412.01	85	85							
✓45053	E 9	405330 0732424.01	125	185							
✓45207	E10	405132 0731814.01	146	165							
✓45208	E 9	405005 0732337.01	137	150							
✓45210	D10	404943 0731745.01	109	125							
✓45212	E10	405356 0731920.01	114	120							
45220	C12	404305 0730853.00	724	10	- 76	-104		-202			
45347	D10	404726 0731626.01	643	130				-200			
45348	D10	404729 0731628.01	650	130				-200			
✓45402	E10	405259 0731622.01	170	180							
✓45446	C10	404400 0731544.02	41	38							
✓45467	D12	404606 0730500.01	82	52							
✓45594	D10	404920 0731509.01	85	105							
45610	E 9	405322 0732114.04	313	15							
✓45637	D12	404508 0730809.01	82	13							
45638	D 9	404804 0732037.01	725	170							
45639	D 9	404804 0732037.02	740	170							
✓45717	D10	404618 0731645.01	75	93							
✓45719	D11	404635 0731016.01	82	26							
✓45720	D11	404716 0731316.02	81	90							
✓45722	D11	404516 0731228.01	91	37							
45808	E15	405201 0725442.00	707	93				-105			
45839	D11	404503 0731312.04	726	40				-105			
45935	D10	404851 0731851.01	605	285				-344			
46165	F11	405521 0731005.01	481	15							
46235	C10	404432 0731513.01	713	39	- 46			- 73			
✓46281	E 8	405237 0732505.00	51	34							
✓46283	D 9	404823 0732118.00	239	275							
✓46284	D12	404848 0730734.01	108	110							
✓46286	D11	404836 0731109.01	107	120							
46400	E13	405002 0730226.00	266	180				- 84			
46509	C12	404317 0730859.01	315	15	- 75	-115		-201			
46712	D16	404803 0724840.01	100	20							
46713	D16	404804 0724941.01	444	20	- 76	- 95		-144			
46830	D10	404606 0731746.01	655	76	- 46			- 60			
46871	E 8	405041 0732515.01	836	196					-428		
✓46911	D16	404920 0724845.02	34	41							
46912	D16	404919 0724845.01	32	42							

2.12.16

Table 2.--Hydrologic units and well-completions

HYDROLOGIC UNIT PENETRATED AND ELEVATION OF UNIT SURFACE, IN FEET ABOVE OR BELOW NATIONAL GEODETIC VERTICAL DATUM OF 1929										
Location of well			Well depth (ft)	Upper glacial aquifer	Cardinera Clay	Monmouth greensand	Magothy aquifer	Raritan clay	Lloyd aquifer	Bedrock
Well number	Map coord	Latitude and Longitude								
46928	E13	405455 0730258.01	654	166			- 35			
✓46963	E12	405226 0730957.01	133	147						
✓46964	E10	405225 0731322.00	114	123						
✓46965	E10	405230 0731644.00	152	166						
46966	D16	404952 0724705.01	86	89						
47002	E19	405300 0723052.01	163	90						
47024	D17	404628 0724308.04	377	10		-210	-321			
47157	D11	404933 0731342.01	25	105						
47218	E14	405335 0725629.00	703	71			-307			
✓47222	C10	404200 0731636.01	28	75						
✓47223	C12	404351 0730541.01	30	55						
✓47224	D15	404817 0723325.00	33	20						
47225	E14	405218 0725611.01	31	51						
47227	E16	405240 0724914.01	100	40						
47228	E16	405306 0724827.01	101	40						
✓47231	F18	405541 0723753.00	40	40						
✓47233	Q20	410348 0722729.00	51	11						
✓47234	G21	410213 0722327.00	27	7						
47235	G23	410037 0721451.01	22	5						
47236	G23	410156 0721336.01	60	35						
47281	E17	405349 0724415.02	275	140	- 78		- 90			
47282	E17	405849 0724415.03	283	140	- 87		- 95			
47436	E15	405124 0725408.01	196	105						
47437	E15	405124 0725408.02	179	105						
47438	E15	405124 0725408.03	269	105			-103			
47439	D14	404739 0725627.02	707	71			-114			
47453	D12	404804 0730513.00	443	100	- 86		-102			
47672	D11	404810 0731132.00	734	100			-341			
47673	E11	405142 0731058.01	279	109						
47675	E12	405111 0730658.01	90	80						
47698	E12	405307 0730609.01	104	133						
47711	C 9	404119 0732219.01	221	25	- 47		- 68			
47718	D12	404941 0730654.01	51	68						
47741	E 8	405211 0732507.00	559	70						
✓47743	D13	404642 0730058.01	100	35						
47745	E14	405417 0725727.01	32	62						
✓47746	D14	404847 0725713.00	84	90						
✓47747	D15	404740 0725452.00	35	31						
47748	F15	405638 0725147.00	36	110						
47750	E15	405004 0725154.00	95	95						
✓47752	D14	404607 0725947.01	100	23						
47755	E16	405136 0724645.00	58	63						
47756	D14	404922 0725950.01	69	89						
47757	E13	405008 0730255.01	138	180						
47758	D12	404852 0730504.01	102	121						
47886	C 9	404204 0732420.01	509	43			- 47			
47887	C 8	404046 0732321.02	648	26	- 56		- 64			
47945	F14	405648 0725351.01	142	143						
47973	F12	405604 0730645.01	90	94						
47974	F13	405532 0730257.01	150	149						
47975	E14	405050 0725953.01	129	153						
47976	F14	405605 0725915.01	138	150						
47977	D15	404711 0725150.00	55	38						
48014	E12	405203 0730855.01	343	124			-109			
48193	D 9	404515 0732255.02	534	80						

Table 2.--Hydrologic units and well-completion data

HYDROLOGIC UNIT PENETRATED AND ELEVATION OF UNIT SURFACE, IN FEET ABOVE OR BELOW NATIONAL GEODETIC VERTICAL DATUM OF 1929													
Location of well			Well depth (ft)	Upper glacial aquifer	Gardiners Clay	Monmouth greensand	Magothy aquifer	Raritan clay	Lloyd aquifer	Bedrock			
Well number	Map coord	Latitude and Longitude											
✓ 3326	G20	410229 0722957.01	92	60									
✓ 3327	G20	410022 0722936.01	46	24									
✓ 3328	G21	410234 0722436.01	41	20									
✓ 3329	G20	410140 0722816.01	71	30									
✓ 3330	H21	410706 0722032.01	52	15									
✓ 3331	H21	410753 0722055.01	70	47									
✓ 3332	F19	405843 0723243.01	45	25									
✓ 3333	F19	405924 0723423.01	74	51									
✓ 3334	F19	405959 0723039.01	53	32									
✓ 3335	G20	410304 0722627.01	37	16									
✓ 3336	G19	410017 0723155.01	42	18									
✓ 3337	H22	410906 0721713.01	52	20									
✓ 3338	G20	410412 0722613.01	65	39									
✓ 3339	G20	404722 0730305.01	798	50	-122		-140						
✓ 3360	E10	405032 0731628.02	703	141			-88						
✓ 3361	E10	405133 0731559.01	521	148			-75						
✓ 33-97	D12	404950 0730850.01	173	90									
✓ 33-98	D12	404950 0730850.02	721	90									
✓ 3352	E17	405230 0724300.01	137	167	-69		-180						
✓ 3353	E18	405124 0723536.03	161	47			-81						
✓ 33747	E10	405140 0731910.01	453	171			-117						
✓ 33851	E17	405230 0724300.02	291	167	-69		-81						
✓ 34099	E13	405029 0730321.01	703	170			-90						
✓ 34155	C10	404326 0731735.01	721	38			-97						
✓ 34162	E10	405359 0731828.01	543	151									
✓ 34305	D12	404805 0730515.02	313	100	-78		-96						
✓ 34308	D11	404759 0731225.01	797	109			-106						
✓ 34377	B12	403936 0730525.01	630	5			-329						
✓ 34473	E13	405030 0730321.03	312	170	-69		-130						
✓ 34478	F18	405906 0723528.01	125	65			-481						
✓ 34479	F18	405857 0723538.01	467	65			-481						
✓ 34568	C 8	404210 0732502.02	423	45	-38		-53						
✓ 34731	B10	403822 0731550.01	750	8			-117						
✓ 34957	D11	404618 0731233.01	378	50			-74						
✓ 35028	E25	405332 0722420.01	161	50			-158						
✓ 35076	F18	405856 0723540.01	343	68									
✓ 35094	E 9	405122 0732327.01	180	185									
✓ 35733	C10	404326 0731741.01	233	38			-97						
✓ 36133	E10	405434 0731942.02	333	70									
✓ 36423	C10	404418 0731718.01	800	50	-50		-75						
✓ 36508	D13	404542 0730133.01	709	6	-116	-135	-184						
✓ 36674	D13	404950 0730015.01	179	107	-71								
✓ 36980	F18	405935 0723548.01	1104	35			-285	-715	-875	-1015			
✓ 37008	D10	404658 0731642.01	635	111			-160						
✓ 37354	E 8	405126 0732737.01	257	50									
✓ 37357	G26	410249 0715545.01	93	32		-110							
✓ 37666	D 9	404604 0732458.01	270	105									
✓ 37723	C13	404322 0730450.01	807	38			-152						
✓ 37748	F 8	405520 0732939.01	418	82				-282	-300				
✓ 37979	F12	405614 0730515.01	582	100			-55						
✓ 37980	F13	405510 0730452.01	703	187			-98	-573					
✓ 38708	D10	404936 0731525.01	423	132			-16						
✓ 38755	E13	405052 0730205.01	252	240									
✓ 38761	E13	405342 0730307.01	723	130			-165						
✓ 38921	G25	410040 0720025.01	75	48									

2.14.16

from selected wells and two miles in Suffolk County, New York.

WELL-COMPLETION DATA											
Well Number	Year Completed	Elevation of top of well (ft above or below M.V.L.)	Use of Water	Use of Well	Screen Setting (ft above or below NCVD)	Total Screen Length (ft)	Diam of Well (in)	Water level (ft below LSD)	Date of Meas. (M-D-Y)	Lift Type	Specific Capacity (GPM/ft)
53326	1974	100	UNSD	OBS	- 19 TO - 29	10	4				
53327	1974	100	UNSD	OBS	- 8 TO - 18	10	4				
53328	1974	100	UNSD	OBS	- 9 TO - 19	10	4				
53329	1975	100	UNSD	OBS	- 26 TO - 41	15	8				
53330	1975	100	UNSD	OBS	- 17 TO - 37	20	4				
53331	1974	100	UNSD	OBS	- 11 TO - 21	10	4				
53332	1974	100	UNSD	OBS	- 8 TO - 18	10	4				
53333	1974	100	UNSD	OBS	- 11 TO - 21	10	4				
53334	1974	100	UNSD	OBS	- 9 TO - 19	10	4				
53335	1974	100	UNSD	OBS	- 9 TO - 19	10	4				
53336	1974	100	UNSD	OBS	- 12 TO - 22	10	4				
53337	1975	100	UNSD	OBS	- 12 TO - 32	20	4				
53338	1974	100	UNSD	OBS	- 14 TO - 24	10	4				
53339	1974	100	UNSD	TEST							
53360	1975	100	P.S.	WTDR	-407 TO -526	119	20	80	02-27-75	TURB	76
53361	1975	100	P.S.	WTDR	-289 TO -369	80	20	111	05-15-75	TURB	61
53497	1975	100	P.S.	WTDR	- 25 TO - 80	55	42				
53498	1975	100	P.S.	WTDR	-573 TO -628	55	42				
53522	1976	100	P.S.	WTDR							
53593	1974	100	P.S.	WTDR	- 71 TO -111	40	20	38	12-17-74	TURB	
53747	1975	100	P.S.	WTDR	-199 TO -277	78	20	111	10-03-75	TURB	51
53851	1975	100	P.S.	WTDR							
54099	1975	100	UNSD	TEST				114	02-27-75		
54155	1975	100	UNSD	TEST							
54162	1975	100	P.S.	WTDR	-304 TO -374	70	20	130	03-18-75		82
54305	1975	100	P.S.	WTDR	-149 TO -210	61	20	55	06-02-75		26
54308	1975	100	P.S.	WTDR	-613 TO -683	70	20	72	03-06-75	TURB	50
54377	1975	100	P.S.	WTDR	-375 TO -625	50	12	10	04-03-75	TURB	20
54473	1975	100	P.S.	WTDR	- 78 TO -139	61	20	115	07-16-75	TURB	44
54478	1975	100	UNSD	TEST	- 29 TO - 60	31	12	56	03-31-75		66
54479	1975	100	UNSD	OBS	-392 TO -402	10	6				
54568	1975	100	P.S.	WTDR	-293 TO -376	83	20	23	05-12-75	TURB	41
54731	1975	100	P.S.	WTDR	-691 TO -742	51	14	4	07-21-75		21
54957	1976	100	P.S.	WTDR	-268 TO -323	55	20	19			10
55028	1975	100	P.S.	WTDR	- 75 TO -110	35	10	43	08-01-75		175
55076	1975	100	UNSD	UNSD							
55094	1975	100	UNSD	UNSD							
55733	1975	100	P.S.	WTDR	-142 TO -192	50	20	14	09-25-75	TURB	56
56133	1976	100	UNSD	TEST	-157 TO -261	104	20	23	03-12-76		108
56423	1975	100	UNSD	TEST		0		21			13
56508	1976	100	UNSD	TEST		0					
56674	1975	100	P.S.	WTDR	- 15 TO - 65	50	20	56	12-26-75		88
56980	1976	100	UNSD	TEST							
57008	1976	100	P.S.	WTDR	-418 TO -521	103	20	62	02-23-76	TURB	50
57354	1976	100	P.S.	WTDR	-163 TO -204	41	12	19	04-29-76	TURB	48
57357	1976	100	UNSD	UNSD	- 26 TO - 57	31	10	29	03-18-76		152
57666	1976	100	UNSD	TEST	-135 TO -165	30	8	43	08-10-76	TURB	13
57723	1976	100	UNSD	TEST							
57748	1977	100	DOM	WTDR	-331 TO -336	5	4	78	05-15-76	SUM	2
57979	1976	100	P.S.	WTDR	-389 TO -479	90	20	59	05-26-76	TURB	56
57980	1977	100	P.S.	WTDR	-443 TO -513	70	20	144	01-03-77	TURB	24
58708	1976	100	P.S.	WTDR	-197 TO -257	60	20	81	09-28-76	TURB	50
58755	1976	100	DOM	WTDR	- 6 TO - 12	6	4				
58761	1977	100	UNSD	UNSD	-522 TO -593	71	20	82	02-15-77	SUM	22
58921	1976	100	UNSD	OBS	- 19 TO - 24	5	4				

2.15.16

Table 2.--Hydrologic units and well-completion data

HYDROLOGIC UNIT PENETRATED AND ELEVATION OF UNIT SURFACE, IN FEET ABOVE OR BELOW NATIONAL GEODETTIC VERTICAL DATUM OF 1929									
Location of well			Well depth (ft)	Upper glacial aquifer	Gardiners Clay	Monmouth greensand	Hagothy aquifer	Raritan clay	Lloyd aquifer
Well number	Map coord	Latitude and Longitude							Bedrock
64847	D11	404505 0731320.01	634	40			-114		
64927	E 9	405306 0732331.01	621	95					
64928	D11	404651 0731203.01	742	65	- 58		- 71		
65196	D10	404529 0731719.01	124	69	- 39		- 48		
65321	E17	405243 0724117.01	304	259	- 35				
65340	D12	404636 0730709.01	804	70			-282		
65505	C 9	404352 0732158.01	650	54			-132		
65766	D11	404759 0731228.01	796	100			-110		
✓ 66132	D 9	404605 0732417.01	140	100			40		
✓ 66133	C 9	404330 0732441.01	161	66			- 30		
✓ 66134	C 9	404235 0732411.01	150	51			- 53		
✓ 66135	C11	404430 0731233.01	168	34	- 56		- 59		
✓ 66136	B 9	403935 0732350.01	143	7	- 57		- 69		
✓ 66137	D 9	404618 0732121.01	143	140			70		
✓ 66138	C 9	404430 0732156.01	150	63	- 27		- 41		
✓ 66139	C 9	404332 0732122.01	153	42			- 44		
✓ 66140	C 9	404205 0732100.01	112	21			- 54		
✓ 66141	C 9	404058 0732025.01	133	5	- 53		-105		
✓ 66142	D10	404815 0731632.01	203	140	- 15		- 33		
✓ 66143	D10	404541 0731803.01	185	70	- 36		- 45		
✓ 66144	C10	404448 0731641.01	143	59	- 51		- 59		
✓ 66145	C10	404435 0731712.01	175	42			- 58		
✓ 66146	C10	404201 0731638.01	143	12	- 39		- 63		
✓ 66147	C12	404251 0730959.01	184	12	- 87	-104	-143		
✓ 66148	D11	404614 0731336.01	133	66			- 53		
✓ 66149	D11	404524 0731234.01	183	38			- 76		
✓ 66150	C11	404430 0731233.01	163	26	- 58		- 77		
✓ 66151	C11	404308 0731318.01	150	7	- 68		- 98		
✓ 66152	D11	404810 0731219.01	193	107			- 57		
✓ 66153	D11	404645 0731053.01	163	50			- 68		
✓ 66154	D11	404548 0731010.01	153	31	- 64		- 91		
✓ 66155	C11	404447 0731041.01	155	28	- 73		- 91		
✓ 66156	C12	404334 0730955.01	173	18	- 92		-112		
✓ 66183	D13	404722 0730305.03	543	71	-139		-159		
✓ 66366	E 9	405158 0732548.01	479	170					
66496	E12	405058 0730509.01	793	127	- 53		- 78		
66556	C 9	404308 0732431.01	753	50			- 48		
66733	F23	405814 0721008.01	607	45			-485		
66823	F13	405623 0730052.01	646	160					
66825	E21	405333 0722417.01	385	50			-162		
66880	E19	405031 0722850.01	216	5		-124	-239		
67074	D12	404632 0730706.01	832	70			-374		
67081	B11	403301 0731227.01	125	4	- 87	-102			
67082	B11	403739 0731432.01	234	12	- 73	-100	-206		
67083	B10	403729 0731701.01	125	12	- 80	- 97			
67084	B10	403825 0731823.01	205	9	- 73	- 91	-147		
67085	B 9	403813 0732007.01	122	10	- 70				
67086	B 9	403739 0732201.01	125	10	- 74				
67087	B 9	403657 0732421.01	205	10	- 74	- 95	-140		
67088	B 8	403640 0732527.01	225	10	- 74	- 95	-151		
67197	D11	404652 0731203.01	763	65	- 58		- 71		
67974	D14	404552 0725617.01	790	30		- 98	-130		

2.16.16

from selected wells and test holes in Suffolk County, New York.


WELL-COMPLETION DATA												
Well Number	Year Completed	Elevation of LSD (ft above or below NGVD)	Use of Water	Use of Well	Screen Setting (ft above or below NGVD)	Total Screen Length (ft)	Diam of Well (in)	Water level (ft below LSD)	Date of Meas. (M-D-Y)	Lift Type	Aquifer Developed	Specific Capacity (GPM/ft)
64847	1979	40	P.S.	WDR	-488 TO -590	112	20	14	01-08-79		MAGOTHY UPGLAC	39
64927	1978	95	UNSD	TEST							MAGOTHY	
64928	1978	65	UNSD	TEST							MAGOTHY	
65196	1978	69	UNSD	TEST							MAGOTHY	
65321	1978	259	UNSD	UNSD	2 TO - 8	10	4				UPGLAC	
65340	1978	70	UNSD	TEST							MAGOTHY	70
65505	1979	54	P.S.	WDR	-521 TO -591	70	20	21			MAGOTHY	
65766	1978	100	UNSD	UNSD							MAGOTHY	
66132	1978	100	UNSD	OBS	10 TO 0	10	6	73	07-11-79		MAGOTHY	
66133	1979	66	UNSD	OBS	- 66 TO - 76	10	6	47	07-11-79		MAGOTHY	
66134	1979	51	UNSD	OBS	- 83 TO - 93	10	6	34	07-11-79		MAGOTHY	
66135	1979	34	UNSD	OBS	- 93 TO -103	10	6	21	07-11-79		MAGOTHY	
66136	1979	7	UNSD	OBS	-118 TO -128	10	6	4	07-11-79		MAGOTHY	
66137	1979	140	UNSD	OBS	20 TO 10	10	6	71	07-11-79		MAGOTHY	
66138	1979	63	UNSD	OBS	- 56 TO - 66	10	6	41	07-11-79		MAGOTHY	
66139	1979	42	UNSD	OBS	- 76 TO - 86	10	6	34	07-11-79		MAGOTHY	
66140	1979	21	UNSD	OBS	- 62 TO - 72	10	6	16	07-11-79		MAGOTHY	
66141	1979	5	UNSD	OBS	-105 TO -115	10	6	4	07-11-79		MAGOTHY	
66142	1979	140	UNSD	OBS	- 32 TO - 42	10	6	60	07-11-79		MAGOTHY	
66143	1979	70	UNSD	OBS	- 96 TO -106	10	6	47	07-11-79		MAGOTHY	
66144	1979	59	UNSD	OBS	- 67 TO - 77	10	6	41	07-11-79		MAGOTHY	
66145	1979	42	UNSD	OBS	-105 TO -115	10	6	27	07-11-79		MAGOTHY	
66146	1979	12	UNSD	OBS	-101 TO -111	10	6	8	07-11-79		MAGOTHY	
66147	1979	12	UNSD	OBS	-145 TO -155	10	6	11	07-11-79		MAGOTHY	
66148	1979	66	UNSD	OBS	- 69 TO - 79	10	6	42	07-11-79		MAGOTHY	
66149	1979	38	UNSD	OBS	-119 TO -129	10	6	23	07-11-79		MAGOTHY	
66150	1979	26	UNSD	OBS	- 84 TO - 94	10	6	17	07-11-79		MAGOTHY	
66151	1979	7	UNSD	OBS	-117 TO -127	10	6	9	07-11-79		MAGOTHY	
66152	1979	107	UNSD	OBS	- 68 TO - 78	10	6	45	07-11-79		MAGOTHY	
66153	1979	50	UNSD	OBS	- 98 TO -108	10	6	31	07-11-79		MAGOTHY	
66154	1979	31	UNSD	OBS	- 97 TO -107	10	6	21	07-11-79		MAGOTHY	
66155	1979	28	UNSD	OBS	-107 TO -115	10	6	16	07-11-79		MAGOTHY	
66156	1979	18	UNSD	OBS	-134 TO -144	10	6	12	07-11-79		MAGOTHY	
66183	1979	71	UNSD	UNSD							MAGOTHY	59
66366	1979	170	P.S.	WDR	-230 TO -290	60	20	133	04-04-79		UPGLAC	
66496	1979	127	UNSD	UNSD							MAGOTHY	
66556	1979	50	UNSD	UNSD							MAGOTHY	
66733	1979	45	UNSD	UNSD							MAGOTHY	
66823	1979	160	UNSD	TEST							UPGLAC	
66825	1979	50	UNSD	OBS							MAGOTHY	
66880	1979	5	UNSD	OBS	-201 TO -211	10	2				MAGOTHY	
67074	1979	70	UNSD	OBS							UPGLAC	
67081	1979	4	UNSD	TEST	-208 TO -218	10	6				MAGOTHY	
67082	1979	12	UNSD	OBS							UPGLAC	
67083	1979	12	UNSD	TEST							MAGOTHY	
67084	1979	9	UNSD	OBS	-158 TO -168	10	6				UPGLAC	
67085	1979	10	UNSD	TEST							MAGOTHY	
67086	1979	10	UNSD	TEST							MAGOTHY	
67087	1979	10	UNSD	OBS							MAGOTHY	
67088	1979	10	UNSD	TEST							MAGOTHY	
67197	1979	65	UNSD	OBS							MAGOTHY	
67974	1980	30	UNSD	OBS							MAGOTHY	

UNITED STATES DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

**Water Table on Long Island, New York,
March 1979**

By

Cynthia D. Donaldson and Edward J. Koszalka




Prepared in cooperation with

**NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
SUFFOLK COUNTY WATER AUTHORITY**

**U.S. GEOLOGICAL SURVEY
Open-File Report 82-163**

**Syosset, New York
1983**

3.2.2



4.1.22

RCRA TREATMENT, STORAGE AND DISPOSAL FACILITY INSPECTION FORM
FOR TSD FACILITIES ONLY

COMPANY NAME: HAZARDOUS WASTE DISPOSAL, INC. EPA I.D. Number: NYT 0000025-74

COMPANY ADDRESS: 11A PILEONE BLVD.
FAIR HAVEN, CT 06424

COMPANY CONTACT OR OFFICIAL: ALB. GREGG R. LAWRENCE OTHER ENVIRONMENTAL PERMITS HELD

BY FACILITY: ☐ NPDES

TITLE: PRESIDENT

☐ AIR

☒ OTHER

NY 300 PERMIT
HALLS PERMIT

INSPECTOR'S NAME:

DATE OF INSPECTION: 9-2-81

ALB. GREGG R. LAWRENCE
HAZARDOUS WASTE DISPOSAL, INC.
BRANCH/ORGANIZATION:

TIME OF DAY INSPECTION TOOK PLACE: 2:15 P.M.

SOLID WASTE

(1) Is there reason to believe that the facility has hazardous waste on site?

RECEIVE

a. If yes, what leads you to believe it is hazardous waste?
Check appropriate box:

OCT 26 1981

☒ Company admits that its waste is hazardous during the inspection.

DIRECTOR'S OFFICE
DIVISION OF SOLID WASTE

☒ Company admitted the waste is hazardous in its RCRA notification and/or Part A Permit Application.

☒ The waste material is listed in the regulations as a hazardous waste from a nonspecific source (\$261.31)

☐ The waste material is listed in the regulations as a hazardous waste from a specific source (\$261.32)

☐ The material or product is listed in the regulations as a discarded commercial chemical product (\$261.33)

☐ EPA testing has shown characteristics of ignitability, corrosivity, reactivity or extraction procedure toxicity, or has revealed hazardous constituents (please attach analysis report)

☐ Company is unsure but there is reason to believe that waste materials are hazardous. (Explain)

YES NO DON'T
KNOW

b. Is there reason to believe that there are hazardous wastes on-site which the company claims are merely products or raw materials?

☒ ☐ ☐

Please explain:

COMPANY CLAIMS THAT A LOT OF THE SOLVENT IS USED AS AN ALTERNATE FILL SUPPLY.

c. Identify the hazardous wastes that are on-site, and estimate approximate quantities of each.

SPENT SOLVENTS AND ACIDS.
1900 DRUMS. PLUS A 2500 GAL. ACID TANK.

(2) Does the facility generate hazardous waste?

☒ ☐ ☐

(3) Does the facility transport hazardous waste?

☒ ☐ ☐


(4) Does the facility treat, store or dispose of hazardous waste?

☒ ☐ ☐

NATIONAL WETLANDS INVENTORY

UNITED STATES DEPARTMENT OF THE INTERIOR

12.1.1



4.2.22

VISUAL OBSERVATIONS

- | | YES | NO | DON'T KNOW |
|--|-------------------------------------|-------------------------------------|--------------------------|
| (5) <u>SITE SECURITY</u> (\$265.14) | | | |
| a. Is there a 24-hour surveillance system? | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <i>24-HOUR SECURITY GUARD - 7 DAYS PER WEEK.</i> | | | |
| b. Is there a suitable barrier which completely surrounds the active portion of the facility? | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <i>FENCE</i> | | | |
| c. Are there "Danger-Unauthorized Personnel Keep Out" signs posted at each entrance to the facility? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| <i>THERE IS A WARNING SIGN, BUT IS NOT THE ONE REQUIRED BY THE REGULATIONS.</i> | | | |
| (6) Are there <u>ignitable</u> , reactive or incompatible wastes on site? (\$265.27) | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| a. If "YES", what are the approximate quantities? | | | |
| <i>1900 DRUMS COMPRISED OF HAZARDOUS AND NONHAZARDOUS WASTE.</i> | | | |
| b. If "YES", have precautions been taken to prevent accidental ignition or reaction of ignitable or reactive waste? | | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| <i>NATHAN BENJAMIN WASTE AND EXPLOSION-PROOF WASTE ARE USED, THE SPILL DRUMS ARE TAKING AND EXPOSED TO THE ELEMENTS.</i> | | | |
| c. If "YES", explain | | | |
| d. In your opinion, are proper precautions taken so that these wastes do not: | | | |
| - generate extreme heat or pressure, fire or explosion, or violent reaction? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| - produce uncontrolled toxic mists, fumes, dusts, or gases in sufficient quantities to threaten human health? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| - produce uncontrolled flammable fumes or gases in sufficient quantities to pose a risk of fire or explosions? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| - damage the structural integrity of the device or facility containing the waste? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| - threaten human health or the environment? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |

Please explain your answers, and comment if necessary.

- e. Are there any additional precautions which you would recommend to improve hazardous waste handling procedures at the facility?
- YES, A COMPLETE RENOVATION OF THE STORAGE AREA. THE IMPRESSION IS THAT THE OWNER OF THE FACILITY SIMPLY PUTS THE DRUMS WHEREVER THERE IS AVAILABLE SPACE, WITH MINIMAL ATTENTION TO SAFETY, PUBLIC HEALTH AND THE ENVIRONMENT.*
- (7) Does the facility comply with preparedness and prevention requirements including maintaining: (\$265.32)

4.3.22

3

YES	NO	DON'T KNOW
-----	----	------------

- an internal communications or alarm system? ☒ ☐ ☐
- a telephone or other device to summon emergency assistance from local authorities? ☒ ☐ ☐
- portable fire equipment? ☒ ☐ ☐
- adequate aisle space? ☐ ☒ ☐
- in your opinion, do the types of wastes on site require all of the above procedures, or are some not needed? Explain. ☒ ☐ ☐

ALL OF THE ABOVE PROCEDURES ARE NEEDED.

In your opinion, do the types of wastes on site require all of the above procedures, or are some not needed? Explain.

ALL OF THE ABOVE PROCEDURES ARE NEEDED

- "(8) Have you inspected to verify that the groundwater monitoring wells (if any) mentioned in the facility's groundwater monitoring plan (see no. 19 below) are properly installed? ☐ ☒ ☐

N/A.
FACILITY IS NOT A LANDFILL. MONITORING A DRY WELL IS LOCATED WITHIN 30 FEET OF THE STORAGE AREA.
If you have, please comment, as appropriate.

- (9) a. Is there any reason to believe that groundwater contamination already exists from this facility? If "YES", explain. ☐ ☒ ☐

- b. Do you believe that operation of this facility may affect groundwater quality? ☒ ☐ ☐

c. If "YES", explain. THE LOCATION OF THE DRYWELL IS SUCH THAT MODERATE (OR HEAVY) PRECIPITATION WILL RESULT IN GROUNDWATER RE CONTAMINATION ASSUMING GROUND WATER TO EXIST UNDER THE FACILITY. ADDITIONALLY, THE SPACE BETWEEN THE STORAGE AREA AND THE RECORDS INSPECTION DRY WELL IS SIMPLY UNCOVERED GROUND.

- (10) Has the facility received hazardous waste from an off-site source since Nov. 19, 1980 (effective date of the regulations)? ☒ ☐ ☐

- a. If "YES", does it appear that the facility has a copy of a manifest for each hazardous waste load received? ☒ ☐ ☐

- b. How many post-November 19 manifests does it have? (If the number is large, you may estimate)
COMPANY RECEIVES WASTES A FEW TIMES PER WEEK.

- c. Does each manifest (or a representative sample) have the following information?
- a manifest document number ☒ ☐ ☐

4.4.22

(13) PERSONNEL TRAINING (\$265.16)

a. Is there written documentation of the following:

- job title for each position at the facility related to hazardous waste management and the name of the employee filling each job? ☐ ☐ ☐
- type and amount of training to be given to personnel in jobs related to hazardous waste management? ☐ ☐ ☐
- actual training or experience received by personnel? ☐ ☐ ☐

INADVERTENTLY
NOT
OBTAINED

(14) Does the facility have a written contingency plan for emergency procedures designed to deal with fires, explosion or any unplanned release of hazardous waste? ☐ ☐ ☐

(\$265.51)

a. Does the plan describe arrangements made with local authorities? ☒ ☐ ☐

b. Has the contingency plan been submitted to local authorities? ☒ ☐ ☐

How do you know?

c. Does the plan list names, addresses, and phone numbers of Emergency Coordinators? ☒ ☐ ☐

d. Does the plan have a list of what emergency equipment is available? ☒ ☐ ☐

e. Is there a provision for evacuating facility personnel? ☒ ☐ ☐

f. Was an Emergency Coordinator present or on call at the time of the inspection? ☒ ☐ ☐

(15) Does the owner/operator keep a written operating record with: (\$265.73)

- a description of wastes received with methods and dates of treatment, storage or disposal? ☒ ☐ ☐

- location and quantity of each waste? ☒ ☐ ☐

- detailed records and results of waste analysis and treatability tests performed on wastes coming into the facility? ☒ ☐ ☐

(ATTACHED ENVIRONMENTAL STUDIES) KSPS DETAILED RECORDS OF ALL ANALYSES, LAG IS LOCATED THERE.

- detailed operating summary reports and description of all emergency incidents that required the implementation of the facility contingency plan? ☒ ☐ ☐

*(16) Does the facility have written closure and post-closure plans? (\$265.110) ☒ ☐ ☐

FACILITY IS UNDER COURT ORDER TO SHUT DOWN, PARTIALLY SATISFYING CLOSURE REQUIREMENTS.

a. Does the written closure plan include: (SEE ATTACHED COURT ORDER)

- a description of how and when the facility will be partially (if applicable) and ultimately closed? ☐ ☐ ☐

* Effective date for this requirement is May 19, 1981.

4.5.22

SEE
SECRET
ORDER

- an estimate of the maximum inventory of wastes in storage or treatment at any time during the life of the facility? ☐ ☐ ☐
- a description of the steps necessary to decontaminate facility equipment during closure? ☐ ☐ ☐
- a schedule for final closure including the anticipated date when wastes will no longer be received and when final closure will be completed? ☐ ☐ ☐
- b. What is the anticipated date for final closure? ☐ ☐ ☐
- †c. Does the owner/operator have a written post-closure plan identifying the activities which will be carried on after closure and the frequency of these activities? ☐ ☐ ☐
- d. Does the written post-closure plan include:
 - a description of planned groundwater monitoring activities and their frequencies during post-closure? ☐ ☐ ☐
 - a description of planned maintenance activities and frequencies to ensure integrity of final cover during post-closure? ☐ ☐ ☐
 - the name, address and phone number of a person or office to contact during post-closure? ☐ ☐ ☐
- *(17) Does the owner/operator have a written estimate of the cost of closing the facility? (\$265.142) What is it? ☐ ☒ ☐
ORAL ESTIMATE BY MR. LAWRENCE IS \$200,000
- *(18) Does the owner/operator have a written estimate of the cost for post-closure monitoring and maintenance? What is it? (\$265.144) ☐ ☐ ☐
- *(19) Has a groundwater monitoring plan been submitted to the Regional Administrator for facilities containing a surface impoundment, landfill or land treatment process? (This requirement does not apply to recycling facilities.) (\$265.90) ☐ ☒ ☐ N/A
 - a. Does the plan indicate that at least one monitoring well has been installed hydraulically upgradient from the limit of the waste management area? ☐ ☒ ☐ N/A
 - b. Does the plan indicate that there are at least three monitoring wells installed hydraulically downgradient at the limit of the waste management area? ☐ ☒ ☐ N/A

† This section applies only to disposal facilities.

* Effective date for this requirement is May 19, 1981.

4.6.22

7

SITE-SPECIFIC

Please circle all appropriate activities and answer questions on indicated pages for all activities circled. When you submit your report, include only those site-specific pages that you have used.

<u>STORAGE</u>	<u>TREATMENT</u>	<u>DISPOSAL</u>
Waste Pile p. 9	Tank p. 8	Landfill pp. 10-11
Surface Impoundment p. 8	Surface Impoundment pp. 8-9	Land Treatment pp. 9, 10
Container p. 7	Incineration pp. 12-13	Surface Impoundment p. 8
Tank, above ground p. 8	Thermal Treatment pp. 12-13	Other _____
Tank, below ground p. 8	Land Treatment pp. 9-10	
Other _____	Chemical, Physical p. 13 and Biological Treatment (other than in tanks, surface impoundment or land treatment facilities)	YES NO DON'T KNOW
	Other _____	

CONTAINERS (\$265.170)

1. Are there any leaking containers?
If "YES", explain. MAJORITY OF CONTAINERS WERE LEAKING (SEE COMMENTS IN GENERATOR INSPECTION FORM, P. 4.)
2. Are there any containers which appear in danger of leaking?
If "YES", explain. ✓
3. Do wastes appear compatible with container materials? ✓
4. Are all containers closed except those in use? ✓
5. Do containers appear to be opened, handled or stored in a manner which may rupture the containers or cause them to leak? ✓
6. How often does the plant manager claim to inspect container storage areas? _____
7. Does it appear that incompatible wastes are being stored in close proximity to one another?
If "YES", explain. ✓
8. Are containers holding ignitable or reactive wastes located at least 15 meters (50 feet) from the facility's property line? ✓
9. What is the approximate number and size of containers with hazardous wastes? _____

1900

4. 7.22

- | | <u>TANKS (\$265.190)</u> | <u>YES</u> | <u>NO</u> | <u>DON'T
KNOW</u> |
|---|--------------------------|------------|--------------|-----------------------|
| 1. Are there any leaking tanks?
If "YES", explain. | | --- | <u>✓</u> | --- |
| 2. Are there any tanks which appear in danger of
leaking.
If "YES", explain. | | --- | <u>✓</u> | --- |
| 3. Are wastes or treatment reagents being
placed in tanks which could cause them to
rupture, leak, corrode or otherwise fail?
If "YES", explain. | | --- | --- | <u>✓</u> |
| 4. Do uncovered tanks have at least 2 feet
of freeboard or an adequate containment
structure? | | <u>N/A</u> | --- | --- |
| 5. Where hazardous waste is continuously
fed into a tank, is the tank equipped with
a means to stop this inflow? | | <u>✓</u> | --- | --- |
| 6. Does it appear that incompatible wastes
are being stored in close proximity to one
another, or in the same tank?
If "YES", explain. | | <u>✓</u> | --- | --- |
| 7. How often does the plant manager claim to
inspect container storage areas? | | | <u>DAILY</u> | |
| 8. Are ignitable or reactive wastes stored in
a manner which protects them from a source
of ignition or reaction?
If "YES", explain. | | <u>N/A</u> | --- | --- |
| 9. What is the approximate number and size of
tanks containing hazardous wastes? | | | | |

ONE 2520 GALLON ACID TANK.

- | | <u>SURFACE IMPOUNDMENTS (\$265.220)</u> | <u>YES</u> | <u>NO</u> | <u>DON'T
KNOW</u> |
|--|---|------------|-----------|-----------------------|
| 1. Is there at least 2 feet of freeboard
in the impoundment? | | --- | --- | --- |
| 2. Do all earthen dikes have a protective
cover to preserve their structural integrity?
If "YES", specify type of covering. | | --- | --- | --- |
| 3. Is there reason to believe that incompatible
wastes are being placed in the same surface
impoundment?
If "YES", explain. | | --- | --- | --- |

YES

NO

DON'T
KNOW

4.8.22

4. Are ignitable or reactive wastes being placed in surface impoundments without being treated to remove these characteristics?
If "YES", explain.
5. Are there any leaks, failures or is there any deterioration in the impoundments?
If "YES", explain.
6. Give the approximate size of surface impoundments (gallons or cubic feet).

WASTE PILES (\$265.250) *N/A*

1. Is the waste pile protected from wind erosion?
- a. Does it appear to need such protection?
- b. Explain what type of protection exists.
2. Does it appear that incompatible wastes are being stored in the same waste pile?
If "YES", explain.
3. Is leachate run-off from a pile a hazardous waste?
If "YES", explain this determination and answer (a) and (b) below.
- a. Is the pile placed on an impermeable base that is compatible with the waste?
- b. Is the pile protected from precipitation and run-on?
4. In your judgment, are ignitable or reactive wastes managed in such a way that they are protected from any material or conditions which may cause them to ignite?
Please explain or indicate if no such wastes are present.
- Are they placed on an existing pile so that they no longer meet the definition of ignitable or reactive waste?
Please explain.

5. How many waste piles are on site, and approximately how large are they?

LAND TREATMENT (\$265.270) *N/A*

1. Can the facility operator demonstrate that the hazardous waste has been made less or non-hazardous by biological degradation or chemical reactions occurring in or on the soil?
Please explain.

4.9.22

- "2. Is run-on diverted away from the active portions of the land treatment facility? — — —
- "3. Is run-off collected? — — —
4. Are food chain crops being grown on the facility property? — — —
- a. If "YES", can the facility operator document that arsenic, lead and mercury:
- will not be transferred to the crop or ingested by food chain animals or — — —
 - will not occur in greater concentrations in the crops grown on the land treatment facility than in the same crops grown on untreated soils. — — —
- b. Has notification of the growing of the food chain crops been made to the Regional Administrator? — — —
5. Is there a written and implemented plan for unsaturated zone monitoring? — — —
6. Are there records of the application dates, application rates, quantities and location of each hazardous waste placed in the facility? — — —
7. Do the closure and post-closure plans address:
- a. control of migration of hazardous wastes into the groundwater? — — —
 - b. control of run-off, release of airborne particulate contaminants? — — —
 - c. compliance with requirements for the growth of food-chain crops (if they are present)? — — —
8. Is ignitable or reactive waste immediately incorporated into the soil so the resulting waste no longer meets that definition? — — —
If "YES", explain.
9. Are incompatible wastes placed in the same land treatment area? — — —
If "YES", explain.
10. What is the area of the land receiving hazardous waste treatment? — — —

LANDFILLS (\$265.300) N/A

- †1. Is run-on diverted away from the active portions of the landfill? — — —
- †2. Is run-off from active portions of the landfill collected? — — —

* Effective date for these requirements is May 19, 1981.

† These requirements are effective November 19, 1981.

3. Is waste which is subject to wind dispersal controlled?
Explain. _____
4. Does the owner/operator maintain a map with:
- the exact location and dimensions of each cell _____
- the contents of each cell and approximate location of each hazardous waste type _____
5. Do the closure and post-closure plans address:
- control of pollutant migration via ground water? _____
- control of surface water infiltration? _____
- prevention of erosion? _____
6. Is ignitable or reactive waste treated before being placed in the landfill?
Explain how you know. _____
7. Are precautions taken to insure that incompatible wastes are not placed in the same landfill cell?
If "NO", explain. _____
8. Are bulk or non-containerized wastes containing free liquids placed in the landfill?
If "YES",
a. Does the landfill have a liner which is chemically and physically resistant to the added liquid? _____
b. Is the waste treated and stabilized so that free liquids are no longer present? _____
9. Are containers holding liquid waste or waste containing free liquids placed in the landfill? _____
10. Are empty containers (e.g. those containing less than 1/2 inch of liquid) placed in the landfills? _____
If so, are they crushed flat, shredded or similarly reduced in volume before they are buried? _____
11. What is the approximate area of the hazardous waste landfill? _____

* Effective date for this requirement is November 19, 1981.

4.11.22

INCINERATORS AND THERMAL TREATMENT
 (\$5265.340 and 265.379)

N/A
 YES NO DON'T KNOW

1. What type of incinerator or thermal treatment is at the site (e.g. waterwall incinerator, boiler, fluidized bed, etc.)? _ _ _
2. Was hazardous waste being incinerated or thermally treated during your inspection?
 If "YES", answer all following questions.
 If "NO", answer only questions 3 and 7. _ _ _
3. Has waste analysis been performed (and written records kept) to include:
 - heating value of the waste _ _ _
 - halogen content _ _ _
 - sulfur content _ _ _
 - concentration of lead _ _ _
 - concentration of mercury _ _ _

NOTE: Waste analysis need not be performed on each waste load if if there are documented data available to show waste characteristics that do not vary. If there are such documented data available, check here .

4. Does it appear that the owner/operator brings his thermal treatment process to steady state (normal) conditions of operation before introducing hazardous wastes? _ _ _
5. Did it appear during your inspection that there was adequate monitoring and inspection by owner/operator every 15 minutes during hazardous waste incineration for:
 - waste feed _ _ _
 - auxiliary fuel feed _ _ _
 - air flow _ _ _
 - incinerator temperature _ _ _
 - scrubber flow _ _ _
 - scrubber pH _ _ _
 - relevant level controls _ _ _

Every hour for:

- stack plume (color and opacity) _ _ _

5. Is there open burning of hazardous waste? _ _ _

4.12.22

a. If "YES", what is being burned?
(only burning or detonation
of explosives is permitted)

b. If open burning or detonation of explosives is taking
place, approximately what is the distance from the open
burning or detonation to the property of others?

- | | YES | NO | DON'T
KNOW |
|---|-----|-----|---------------|
| 6. Does the incinerator appear to be operating properly? (Do emergency shutdown controls and system alarms seem to be in good working order?) Please explain. | --- | --- | --- |
| a. Is there any evidence of fugitive emissions? | --- | --- | --- |
| 7. Is the residue from the incinerator treated by the owner as a hazardous waste? Please explain. | --- | --- | --- |
| 8. What types of air pollution control devices (if any) are installed on the incinerator? | --- | --- | --- |

CHEMICAL, PHYSICAL AND BIOLOGICAL TREATMENT (\$265,400) N/A

- | | | | |
|---|-----|-----|-----|
| 1. Does the treatment process system show any signs of ruptures, leaks, or corrosion? Please explain. | --- | --- | --- |
| 2. Is there a means to stop the inflow of continuously-fed hazardous wastes? | --- | --- | --- |
| 3. Is there ignitable or reactive waste fed into the treatment system? | --- | --- | --- |

If "YES", has it been treated or protected from any material or conditions which may cause it to ignite or react? If so, explain how.


Are the incompatible wastes placed in the same treatment process? If "YES", explain.

- | | | | |
|--|-----|-----|-----|
| 5. Describe the treatment system at this facility. | --- | --- | --- |
|--|-----|-----|-----|

SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
INDUSTRIAL WASTE AND HAZARDOUS MATERIALS CONTROL
65 JETSON LA., P.O. BOX G, CENTRAL ISLIP, NY. 11722
(516) 234-2622

File
4.13.72

NAME OF FACILITY		OWNER/OFFICER <u>George Lawrence</u>		PAGE 1 OF	
COMPANY NAME <u>HWD INC.</u>		CONTACT		TEL.	
PLANT ADDRESS <u>PICONE BLVD.</u>		VILLAGE <u>Farmingdale</u> TOWN <u>Bab.</u>		ZIP	
MAILING ADDRESS					
DATE <u>14 Sept. 82</u>	TIME <u>9:00 AM</u>	ORIG. PERIODIC <u>RE</u>	WASTE	NO WASTE <u>HBM</u>	SEWAGE SYSTEM PUBLIC PRIVATE
INDUSTRY <u>Industrial Waste Sweeper.</u>					
SPOES OR NPDES PERMIT? YES NO PERMIT NO.			360 PERMIT? YES NO PERMIT NO.		
SCAVENGER TEL.					
SCAVENGER APPROVED YES NO		PICK UP RECORDS AVAILABLE YES NO		RECORDS CONSISTENT WITH EXPECTED WASTE GENERATION YES NO	
HEATING SYSTEM-MFG. NAME				FUEL TYPE	FIRING RATE
INCIN. NAME				WASTE BURNED	RATE
DRUM STORAGE <u>YES</u> NO	NUMBER OF <u>840-CONTAIN MATERIAL</u> DRUMS STORED <u>420-EMPTY</u>		TYPE OF MATERIAL STORED WASTE RAW <u>BOTH</u>		
TANK STORAGE <u>YES</u> NO	ABOVE GROUND <u>X</u> UNDER GROUND BOTH		TYPE OF MATERIAL STORED <u>WASTE</u> RAW BOTH		
HAVE TANKS BEEN REGISTERED YES <u>NO</u>	CONDITION OF ABOVEGROUND TANKS GOOD FAIR <u>POOR</u>		ANY ART. XII VIOLATIONS <u>YES</u> NO		
<p>① Spills noted in drum storage area were cleaned up with absorbent material.</p> <p>② Empty drums outside dyked area had material within them.</p> <p>③ Drums containing material 840x55gal. Drums empty- 420x55gal.</p> <p>④ Article 12 Violations → Outside, unsecured, pad not impervious. etc.</p>					
PERMISSION IS GRANTED BY THIS FACILITY TO THE SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES TO CONDUCT ROUTINE SAMPLING OF CESSPOOLS, STORMDRAINS, AND OTHER DISCHARGE POINTS AT THE FACILITY.					
REINSPECTION SCHEDULED ON OR AFTER _____ FAILURE TO CORRECT UNSATISFACTORY CONDITIONS BY REINSPECTION DATE MAY RESULT IN A HEARING AND/OR FINE.					
SIGN. OF PERSON REC. REPORT		TITLE		INSPECTOR <u>DAVID OBR16</u> <u>D. G.</u>	

[illegible][illegible]

4.14.22




SUFFOLK COUNTY
DEPT OF

HEALTH SERVICES

JOB HWD INC 4.15.22
SHEET NO. PICONE BLVD. FARMING DATE OF
CALCULATED BY EE DATE
CHECKED BY DATE
SCALE


30 JUNE 82 - 11:50 AM



- ① OBSERVED NO WORK AT SITE DURING INSPECTION.
- ② OBSERVED NO OBVIOUS SPILLS
- ③ Drums were uncovered + exposed to weather.
- ④ New pad area has been constructed to the South of the old drum storage.
Drums two (2) high have been stored between the tanks + the transfer pump.
- ⑤ Waste pit North of Acid/Base mix tank covered with black plastic.

D. O'Bray

4.16.22



15 Sept - Acid tank to be pumped

Spill in down area had about material on floor

Empty down area and s.co. after area had been used in some.



4.17.22

M E M O R A N D U M

TO: James C. Maloney, P.E.
FROM: John V. Soderberg, P.E.
DATE: March 12, 1981
RE: Hazardous Waste Disposal (H.W.D.)

On March 11, 1981 the writer was requested to accompany representatives of the Toxic Waste Handling Group in their investigation of the above premises.

At the time of my inspection there were no visible emissions occurring from the process tank in question. However, the East Farmingdale Fire District indicated a visible plume of from 150 to 200' in vertical height on or about noon of that date.

As part of my inspection, I spoke with representatives of Pront Printing (11D Picone Boulevard, Farmingdale). They indicated that the situation has been occurring sporadically since last September and was particularly severe last Summer. Concerning the specific incident, they were unsure about specifics and reported no property damage or lost time that they can contribute directly to the incident.

I recommend first that a detailed industrial survey be made of the premises and secondly that the firm be placed under routine surveillance for at least three months.

JVS:mew

4.18.22

MEMORANDUM

TO: JAMES C. MALONEY
FROM: JOHN V SODERBERG
DATE: MARCH 16, 1981
RE: H W D.

In follow up to my memo concerning the March 11, 1981 investigation of the above firm, an air pollution emission inspection was not performed at that time (due to inclement weather and potential safety hazard).

The water pollution file contains no information either confirming or denying the presence of such sources (only the H. W. D. environmental checklist submitted by them to Babylon Town indicating no process emissions).

I have therefore requested that such a survey be performed.

JVS:ets

SUFFERN COUNTY DEPARTMENT OF HEALTH SERVICES
INDUSTRIAL WASTE AND HAZARDOUS MATERIALS CONTROL
65 Jordon Lane, P.O. Box G, Central Islip, NY 11722
(516) 234-2622, 4260

4.19.22

FACILITY		OWNER/OFFICER	PAGE 1 OF
COMPANY NAME		CONTACT	TEL.
PLANT ADDRESS	VILLAGE	TOWN	ZIP
MAILING ADDRESS			
DATE 12 MAY 81	TIME	ORIG. PERIODIC RE.	WASTE NO WASTE H & H
		SEWAGE SYSTEM	PUBLIC PRIVATE

INDUSTRY

IPDES OR IPDES PERMIT?	YES NO	360 PERMIT?	YES NO	PERMIT NO.
------------------------	--------	-------------	--------	------------

INDUSTRIAL PROCESSES

NO.	PROCESS	CHEMICALS USED AND APPROXIMATE QUANTITY	IND. LIQUID WASTE DISCHARGE	DISCHARGED TO	AIR POLL. SOURCE
	MR. JOSEPH PICONE				
		Pipe ended immediately North of Dryers			
		properly. End of pipe was covered up approx. 6-7 years			
		ago. Storm drain in garden may not be			
		covered. End			

CAVENDER

TEL.

CAVENDER APPROVED	YES NO	PICK UP RECORDS AVAILABLE	YES NO	RECORDS CONSISTENT WITH EXPECTED WASTE GENERATION	YES NO
-------------------	--------	---------------------------	--------	---	--------

AIR POLLUTION SOURCES

NO.	PROCESS	AIR POLL. SOURCE DESCRIPTION	EMISSION POINTS	TYPE OF EMISSION	AMT. OF EMISSION/CONSUME	HOURS/OP.	CONTROL TYPE

EATING SYSTEM
FUEL TYPE

MFG. NAME

FIRING RATE

WASTE

WASTE BURNED

CHARGING RATE

EMISSION IS LIMITED BY THIS FACILITY TO THE SUFFERN COUNTY DEPARTMENT OF HEALTH SERVICES TO CONDUCT ROUTINE SAMPLING OF CESSPOOLS, TORMIDAINS, AND OTHER DISCHARGE POINTS AT THE FACILITY.

INSPECTION SCHEDULED ON OR AFTER . . . FAILURE TO CORRECT UNSATISFACTORY CONDITIONS BY REINSPECTION DATE MAY RESULT IN HEARING AND/OR FINE.

IGN. OF PERSON
EC. REPORT

TITLE

INSPECTOR

4. 20. 22

INFORMATION OBTAINED FROM MR. JOSEPH PICONI, OF
USEPH PICONI & SON INC. AT #1637 BROAD HOLLOW RD. FARMINGDALE.


I INTERVIEWED MR. JOSEPH PICONI ON MAY 5, 1981,
BETWEEN 105 - 345 IN THE AFTERNOON AT HIS OFFICE AT
345 BROAD HOLLOW RD. FARMINGDALE.

THE INFORMATION REQUESTED ~~WAS~~ ^{WAS THE} CONSTRUCTION
DETAILS CONCERNING THE STREET STORM ~~WAS~~ ^{DRAIN} SYSTEM
LOCATED ON PICONI BLVD. FARMINGDALE.

MR. PICONI TOLD ME THAT HE INSTALLED THE STORM
DRAIN SYSTEM HIMSELF. WE THEN LEFT MR. PICONI'S OFFICE
AND BY CAR INSPECTED THE AREA IN QUESTION. WE DID
NOT GO TO THE IMMEDIATE VICINITY OF HWD INC. BECAUSE THE
ROAD WAS BLOCKED BY TRUCKS. HOWEVER MR. PICONI STATED
THAT ALL THE STORM DRAINING IN THAT VICINITY DO RUN INTO
A COMMON PIPE WHICH RUNS INTO THE SMALL SUMP
LOCATED TO THE NORTH EAST OF HWD INC. ~~BECAUSE~~. AT ONE TIME
THE PIPE ACTUALLY ENTERED THE SUMP, BUT HAS BEEN FILLED
IN AND THE END OF THE PIPE COVERED. MR. PICONI SAID THAT
THE DRAINAGE SYSTEM STILL WORKS BECAUSE ONLY DURING
THE HEAVIEST OF RAIN DO THEY HAVE ANY RUN-OFF PROBLEMS.

MR. PICONI ALSO STATED THAT THRU HIS LAWYER,
HE HAS ASKED HWD INC. TO LOCATE THEIR ESTABLISHMENT
BY JUNI. 1, 1981

②



FILE UNDER HWD INC.

4.22.22

CONTINUED: INSPECTORS OBSERVATIONS OR INTERVIEWS
5 MAY 81

JOSEPH PICONE + SON INC.
249-5800


1:00pm - 3:05pm

Information obtained from interview with Mr. Joseph Picone, of ~~Little Ferry~~ ^{Brookhaven Rd.} ~~Mobile Realty Inc.~~ located at Rt 110, Farmingdale.

The storm drain system was installed by Mr. Picone himself as Picone Blvd. is the vicinity of HWD Inc.

I accompanied Mr. Picone to the location and he pointed out the various drains and how they run. We did not go to the immediate vicinity of HWD Inc. because the road was blocked by trucks. However Mr. Picone stated that all the storm drains in that vicinity do ~~run~~ run into a common pipe which runs towards the small swamp located to the North East of the HWD Inc. property. At one time the pipe actually entered the swamp, but the swamp has been filled in and the end of the pipe has been covered. Mr. Picone said the the system still ~~works~~ works because only during the heaviest of rain do they have any run off problems.

Mr. Picone also stated that ~~they~~ ^{he} thru his ~~lawyer~~ lawyer has asked HWD Inc. to ~~move~~ vacate their establishment by June 1, 1981.



5.1.5


Uncontrolled Hazardous Waste Site Ranking System

A Users Manual
(HW-10)

Originally Published in
the July 16, 1982, *Federal Register*

**United States
Environmental Protection
Agency**

1984



Source: Climatic Atlas of the United States, U.S. Department of Commerce, National Climatic Center, Ashville, N.C., 1979.

FIGURE 4
MEAN ANNUAL LAKE EVAPORATION
(IN INCHES)

TABLE 2
PERMEABILITY OF GEOLOGIC MATERIALS*

Type of Material	Approximate Range of Hydraulic Conductivity	Assigned Value
Clay, compact till, shale; unfractured metamorphic and igneous rocks	$<10^{-7}$ cm/sec	0
Silt, loess, silty clays, silty loams, clay loams; less permeable limestone, dolomites, and sandstone; moderately permeable till	$10^{-5} - 10^{-7}$ cm/sec	1
Fine sand and silty sand; sandy loams; loamy sands; moderately permeable limestone, dolomites, and sandstone (no karst); moderately fractured igneous and metamorphic rocks, some coarse till	$10^{-3} - 10^{-5}$ cm/sec	2
Gravel, sand; highly fractured igneous and metamorphic rocks; permeable basalt and lavas; karst limestone and dolomite	$>10^{-3}$ cm/sec	3

*Derived from:

Davis, S. H., Porosity and Permeability of Natural Materials in Flow-Through Porous Media, R.J.M. DeWiest ed., Academic Press, New York, 1969

Freeze, R.A. and J.A. Cherry, Groundwater, Prentice-Hall, Inc., New York, 1979

TABLE 4
WASTE CHARACTERISTICS VALUES
FOR SOME COMMON CHEMICALS

CHEMICAL/COMPOUND	<div> <div>1</div> <div>2</div> <div>3</div> <div>4</div> </div>			
	1	2	3	4
Acetaldehyde	3	0	3	2
Acetic Acid	3	0	2	1
Acetone	2	0	3	0
Aldrin	3	3	1	0
Ammonia, Anhydrous	3	0	1	0
Aniline	3	1	2	0
Benzene	3	1	3	0
Carbon Tetrachloride	3	3	0	0
Chlordane	3	3	0 ^a	0 ^a
Chlorobenzene	2	2	3	0
Chloroform	3	3	0	0
Cresol-0	3	1	2	0
Cresol-M&P	3	1	1	0
Cyclohexane	2	2	3	0
Dioxin	3	3	1	0
Ethyl Benzene	2	1	3	0
Formaldehyde	3	0	2	0
Formic Acid	3	0	2	0
Hydrochloric Acid	3	0	0	0
Isopropyl Ether	3	1	3	1
Lindane	3	3	1	0
Methane	1	1	3	0
Methyl Ethyl Ketone	2	0	3	0
Methyl Parathion in Xylene Solution	3	0 ^a	3	2
Naphthalene	2	1	2	0
Nitric Acid	3	0	0	0
Parathion	3	0 ^a	1	2
PCB	3	3	0 ^a	0 ^a
Petroleum, Kerosene (Fuel Oil No. 1)	3	1	2	0
Phenol	3	1	2	0
Sulfuric Acid	3	0	0	2
Toluene	2	1	3	0
Trichlorobenzene	2	3	1	0
or-Trichloroethane	2	2	1	0
Xylene	2	1	3	0


¹ Sax, N. I., Dangerous Properties of Industrial Materials, Van Nostrand Reinhold Co., New York, 4th ed., 1975. The highest rating listed under each chemical is used.

² JED Associates, Inc., Methodology for Rating the Hazard Potential of Waste Disposal Sites, May 3, 1980.

³ National Fire Protection Association, National Fire Codes, Vol. 13, No. 49, 1977.

^a Professional judgment based on information contained in the U.S. Coast Guard CHRIS Hazardous Chemical Data, 1978.

⁴ Professional judgment based on existing literature.



Source: Rainfall Frequency Atlas of the United States, Technical Paper No. 40, U.S. Department of Commerce, U.S. Government Printing Office, Washington, D.C., 1961.

FIGURE 8
1-YEAR 24-HOUR RAINFALL
(INCHES)

5.5.5

7.1.5

ROUX ASSOCIATES, INC.

Telephone Conversation Sheet

Caller J. B. Lyons
 Company E. Farmingdale Water District
 Contact Mr. John Ferrera Telephone # (516) 299-4211

DATE

COMMENTS

7/8/87

Mr. Ferrera informed me that presently
 7 public supply-wells are in operation
 supplying ground water to 5200 people.

Four wells: #21222-72 Gazez Blk
 #31 - 1000 ft North of

Daniel St. on Rt 110.

#41 - Intersection of
 New Highway and Southern
 State Pkwy.

Boundaries of District:

West - Suffolk - Nassau Co. line

East - Wellwood Ave

North - Babylon - Oyster Bay town line

South - Southern State Pkwy

ROUX ASSOCIATES, INC.

Telephone Conversation Sheet

Caller

J. Byrnes

Company

Plainview - Bethpage Water District

Contact

Telephone # (516) 931-0093

Huntington Town Water District (516) 427-0303

DATE

Mr. K. Bonneau

COMMENTS

7/13

Plainview-
Bethpage
Water Dist

8,300 Served by supply wells

Boundaries: West - Seaford Oyster Bay Exp.
North - Miriam & Lark

South - Larkspur

East - Boquet - Suffolk & Nassau

7/13

Huntington
Water
District~~8,300~~ Has 9000 accounts in District. $9000 \times 3.8 (\# \text{ of people per household}) = 34,200$

Boundaries: W - Pinelawn Rd

E - Commack Rd

N - Old Country Rd

S - Bagatelle Ave (Bagatelle -
Huntington Border)


7.4.5



This is a detailed black and white map of the Farmingdale Water District and surrounding areas. The map shows various water districts including Plainview-Bethpage, E. Farmingdale, S. Farmingdale, and Babylon. It also depicts the Long Island National Cemetery, the Suffolk County Water Authority, and the New Monticore Electric Company. The map includes a grid of streets and a network of water lines. A large 'X' is drawn across the map, and a 'SITE' is marked in the center. The map is labeled with 'HUNTINGTON TOWN', 'WATER DISTRICT', 'PLAINVIEW - BETHPAGE', 'E. FARMINGDALE WATER DISTRICT', 'S. FARMINGDALE WATER DISTRICT', 'BABYLON DISTRICT', 'SUFFOLK COUNTY', 'WATER AUTHORITY', and 'NEW MONTICORE ELECTRIC COMPANY'.



8.1.3

SUFFOLK COUNTY WATER AUTHORITY



1986
Annual
Report

Communities Served



BABYLON DISTRICT

Amity Harbor
Amityville
Babylon
Capiogue
Deer Park
Dix Hills
Lindenhurst
North Amityville
North Babylon
North Lindenhurst
Pinelawn
West Babylon
Wheatley Heights
Wyandanch

BAY SHORE DISTRICT

Bay Shore
Brenwood
Brightwaters
Central Islip
East Islip
Edgewood
Great River
Islip
Islip Terrace
North Bay Shore
North Great River
Oakdale
West Bay Shore
West Islip

HUNTINGTON DISTRICT

Asharoken
Centerport
Cold Spring Harbor
Commack
Grab Meadow
East Huntington
East Neck
East Northport
Eatons Neck
Fort Salonga
Halesite
Huntington
Huntington Bay
Huntington Station
Lloyd Harbor
Northport

EAST HAMPTON DISTRICT

Amagansett
East Hampton
Freetown
Montauk
North Sea
Sag Harbor
Southampton

PATCHOGUE DISTRICT

Bayport
Bellport
Blue Point
Bohemia
Brookhaven
Coram
East Holbrook
East Patchogue
Farmingville
Gordon Heights
Holbrook
Holtsville
Lakeland
Lake Ronkonkoma
Mastic
Mastic Beach
Medford
North Bellport
North Patchogue
Patchogue
Ronkonkoma
Sayville
Selden
Shirley
South Centereach
South Holbrook
South Yaphank
West Bellport
West Ronkonkoma
West Sayville
Yaphank

PORT JEFFERSON DISTRICT

Belle Terre
Centereach
Coram
East Setauket
Lake Grove
Middle Island
Miller Place
Mount Sinai
North Centereach
North Selden
Poquott
Port Jefferson
Port Jefferson Station
Ridge
Rocky Point
Setauket
South Setauket
Sound Beach
South Strony Brook
Strony Brook
Strongs Neck
Terryville

SMITHTOWN DISTRICT

East Commack
Flowerfield*
Hauppauge
Kings Park
Nesconset
Saint James*
San Remo*
Smithtown
South Hauppauge
West St. James
West Smithtown*
Village of Head of The Harbor
Village of The Branch

WESTHAMPTON DISTRICT

Center Mariches
East Mariches
Eastport
East Quogue
Mariches
South Manor
Quogue
Quogue
Westhampton
Westhampton Beach


* Included in Wholesale Water District

Plant Facilities

AS OF MAY 31, 1985 ☐AS OF MAY 31, 1986 ☐

Service Areas or Plants	Wells Active Inactive				Pumping Plants				Storage Facilities				Active Services	
					No.	Capacity-1000 Gals.	Daily*		No.	Capacity in 1000 Gallons				
BABYLON	48	48	8	8	19	19	82,102	82,102	9	8	7,815	7,515	54,311	54,893
BAY SHORE	47	49	14	13	20	20	81,274	83,722	7	7	6,012	6,012	47,485	48,024
EAST HAMPTON	33	32	1	2	18	18	23,652	22,860	4	5	3,720	5,720	10,675	10,948
HUNTINGTON	52	53	3	3	21	21	63,878	64,886	11	11	11,842	11,842	28,676	28,880
PATCHOGUE	65	66	8	7	27	27	108,792	110,592	11	11	11,465	11,465	53,377	52,131
PORT JEFFERSON	67	69	2	1	28	28	107,741	109,901	7	7	7,404	7,404	33,885	34,880
SMITHTOWN	48	48	3	3	21	21	83,578	83,578	6	6	6,100	6,100	23,398	23,772
WESTHAMPTON	23	23	—	—	7	7	16,524	16,524	3	4	2,350	3,350	4,724	9,301
TOTALS	383	388	39	37	161	161	567,541	574,165	58	59	56,708	59,408	256,531	262,829

*Based on 24-hour operation and on actual capacity of pumping equipment for active wells.



9.1.9

USGS HEADER FILE 1987

Public-Supply and Observation
Well Data

USGS
5 Aerial Way
Syosset, New York

S	1329.	140404707325200504040470732520	7	SO	194	4156	3	00	46	000	0	0	004
S	1329.	140404707325200604040470732520	7	SO	194	4156	3	00	60	000	0	0	005
S	1350.	140404707325200204040470732520	211MGTY	7	SO	194	4156	3	260	60	000	0	002
S	1661.	1404156073212301 4041560732126	211MGTY	7	SO	452	0	0	0	00	0	0	001
S	1662.	1404156073212302 4041560732125	211MGTY	7	SO	452	0	0	0	00	0	0	001
S	3572.	1405005073271001 4050050732710	7	SF	318	7	0	0	00	26010470	0	0	001
S	3574.	1405005073271002 4050050732710	7	SF	318	7	0	0	00	24310559	0	0	002
S	6251.	1404834073243101 4048340732431	211MGTY	7	SH	435	7151	01440	202	000	149	0	20701
S	9771.	1405046073161401 4050460731615	112GLCLU7	7	SH	963	11169	01400	147	000	126	146	15101
S	10641.	1404220073190301X 4042190731905	112GLCLU7	7	SO	594	4157	0	190	60	000	37	58 6001
S	11891.	1405054073151001 4050540731510	112GLCLU7	7	SH	1024	11182	0	700	119	6814	86	108 32801
S	12016.	1404202073242301 4042030732422	112GLCLU7	7	SN	296	0	0	0	00	0	0	001
S	12072.	1404750073241501 4047500732415	211MGTY	7	SJ	431T	7148	01410	445	000	364	444	60201
S	12130.	1405126073273802 4051260732736	112GLCLU7	7	SE	326	7131	0	700	307	000	266	305 30802
S	13175.	1405015073234302 4050150732343	112GLCLU7	7	SG	513T	7151	01780	263	000	169	263	41802
S	13534.	1404531073150401X 4045290731504	112GLCLU7	7	SM	907T	8187	0	620	126	000	89	119 12601
S	13976.	1405015073263301 4050150732638	211MGTY	7	SF	358	7151	01200	298	000	246	298	44801
S	14213.	1404201073242301 4042030732424	112GLCLU7	7	SN	286	4156	0	350	85	000	54	84 8701
S	14521.	1405143073201901 4051430732019	112GLCLU7	7	SF	758	7137	02000	552	000	459	552	55201
S	14829.	1405114073261001 4051140732605	112GLCLU7	7	SF	401	7144	02220	508	000	355	440	59501
S	15472.	1404203073242201 4042030732419	112GLCLU7	7	SN	286	4166	0	420	87	000	53	87 8901
S	15776.	1405115073260901 4051150732608	112GLCLU7	7	SF	401	7144	02300	50423098	440	500	001	001
S	15898.	1404536073163301X 4045370731634	112GLCLU7	7	SM	823	8190	0	700	128	7841	95	128 13301
S	15923.	1405134073155901 4051450731554	112GLCLU7	7	SG	1006	11169	01400	264	000	148	263	36201
S	16042.	1404632073220701 4046320732207	112GLCLU7	7	SH	579	7133	02100	326	000	266	319	40001
S	16137.	1405027073250301 4050270732503	112GLCLU7	7	SF	449	7151	01600	604	000	540	602	60401
S	16175.	1404534073163101X 4045340731631	112GLCLU7	7	SM	823	8190	0	700	130	7314	95	130 13001
S	16176.	1404523073150901X 4045280731506	112GLCLU7	7	SM	907	8202	0	620	117	000	81	117 12101
S	16526.	1404707073252101 4047070732521	211MGTY	7	SJ	355T	7148	01200	301	000	0	0	001
S	16603.	1404733073153601 4047330731536	7	SK	929	8189	01100	140	000	110	140	16801	16801
S	16566.	1404528073150501X 4045290731505	211MGTY	7	SM	907	4187	0	620	383	000	322	383 65301
S	19049.	1404301073161901X 4043040731617	211MGTY	7	SO	773	8198	0	250	727	000	663	726 73501
S	19554.	1404240073225001 4042350732256	112GLCLU7	7	SN	385	4165	0	450	100	4129	65	100 10501
S	19565.	140432207322250104045230732222	7	SM	439	4161	0	00	93	4649	63	0	9801
S	20041.	1404444073251101 4044440732511	112GLCLU7	7	SL	303	4	0	0	800	268	000	190 264 001
S	20057.	14045190732251010 4045200732245	211MGTY	7	SL	453	4167	0	790	200	8101	170	200 20001
S	20300.	14045160732251010 4045210732243	211MGTY	7	SL	453	4167	0	750	232	6664	201	232 23201
S	20319.	1404733073153101 4047330731531	211MGTY	7	SL	920T	8189	01100	436	000	370	430	60501
S	20369.	1404936073152501 4049360731525	211MGTY	7	SJ	984	11169	01200	312	000	260	310	31201
S	20460.	1404240073225002 4042350732256	211MGTY	7	SN	385T	4165	0	470	499	4856	424	494 76902
S	20566.	1404317073153601X 4043400731541	211MGTY	7	SO	320	8137	0	260	755	2964	710	772 75501
S	20935.	1404156073212301 4041550732123	211MGTY	7	SO	453	4166	0	220	630	2299	557	627 63001
S	21066.	1404809073191301 4048090731913	112GLCLU7	7	SJ	728	7	0	01430	376	000	310	372 40201
S	21121.	1405134073235702 4051340732357	112GLCLU7	7	SF	532	7146	02200	60021800	490	555	62102	62102
S	21134.	1405106073174201 4051060731742	211MGTY	7	SG	887	7169	01600	547	000	489	540	68001
S	21244.	1404304073162901X 4043040731615	211MGTY	7	SO	773	8187	0	230	602	2750	465	593 73001
S	21366.	1404357073181601X 4043570731816	211MGTY	7	SN	683	8209	0	430	470	4652	414	454 47001
S	21375.	1404220073190302 4042220731904	211MGTY	7	SO	593	4157	0	180	501	2090	445	495 50302
S	21467.	14043200732224010 4043220732224	211MGTY	7	SM	439	4166	0	430	340	000	262	340 34001
S	22303.	1403621073182001 4038210731820	211MGTY	7	B SR	546	4	0	0	100	285	000	273 285 001
S	22362.	1404955073170401 4049570731704	112GLCLU7	7									

7407.	2404072073333213	40400207333332	211MGTY	7	NG1298	1	0	0	240	648	2394	480	645	013
7414.	14040560732611010	4040540732613	211MGTY	7	NL1282	3	0	0	220	533	000	373	530	001
7421.	14045570732705025	4045540732706	211MGTY	7	NL 837	3	0	0	1800	564	000	482	559	001
7446.	1404648073344301	4046480733443	211MGTY	7	NG 637	3	0	0	02220	498	000	443	493	001
7500.	1404418073345401	40441907333450	211MGTY	7	NG 928	1	0	3	920	458	000	405	458	001
7515.	14045370732711010	4045370732707	211MGTY	7	NL1033	3	0	0	630	352	000	289	347	002
7516.	14045370732711020	4045370732705	211MGTY	7	NL1033	3	0	0	630	589	000	495	584	58901
7523.	1404511073302501	4045090733026	211MGTY	7	NJ1066	1	0	0	810	684	8046	589	684	002
7525.	14047030732801010	4047030732801	211MGTY	7	NK 789	3	0	0	02280	691	000	570	688	69401
7534.	2404504073301105	4045050733011	211MGTY	7	NJ 973	3	0	0	01200	366	000	288	366	002
7535.	2404519073295805	4045190732958	211MGTY	7	NJ 981	3	0	0	01220	357	000	281	357	005
7549.	1404738073353201	4047380733531	211MGTY	7	NF 785	3	0	0	01930	504	20234	449	499	001
7561.	1404455073324902	4044550733246	211MGTY	7	NH 934	3	0	0	01170	551	11890	463	550	003
7562.	1404639073311103	4046340733111	211MGTY	7	NJ 813	3	0	0	01630	550	000	458	545	002
7593.	1404531073415401	4050450732830	211MGTY	7	NK 553	3	0	0	02530	473	25442	408	468	001
7635.	1404500073300401	4045000733004	211MGTY	7	NJ 973	3	0	0	01200	394	000	314	394	002
7636.	1404517073294301	4045170732949	211MGTY	7	NJ 991	3	0	0	01250	373	000	312	373	002
7637.	1404516073293502	4045170732942	211MGTY	7	NJ 991	3	0	0	01260	490	000	429	490	003
7665.	1405204073345401	4052050733500	112GLCLU7		NG 414	3	0	0	02180	375	22249	320	370	001
7772.	1405012073305501	4050120733102	211MGTY	7	NJ 527	3	0	0	02580	568	000	503	563	001
7773.	1405010073305901	4050100733059	211MGTY	7	NJ 527	3	0	0	02300	565	24540	500	560	001
7781.	1404751073322001	4047510733220	211MGTY	7	NH 754	3	0	0	02170	459	000	394	454	001
7785.	1404526073353401	4045260733534	211MGTY	7	NF 981	2	0	0	31080	404	000	330	400	001
7796.	1403950073341201	4039490733417	211MGTY	7	NG1350	1	0	0	110	700	000	525	585	004
7796.	2403949073341206	4039490733417	211MGTY	7	NG1350	1	0	0	110	590	000	525	585	006
7797.	1404510073331502	4045080733321	211MGTY	7	NH1007	1	0	0	800	550	8514	485	545	001
7831.	1404023073371301	4040220733713	211MGTY	78	NF1206	1	0	0	400	590	000	515	585	001
7852.	14044100732616120	4044100732616	211MGTY	7	NL 989	3	99	3	770	457	000	399	450	61505
7852.	24044110732618010	4044100732616	211MGTY	7	NL 989	3	99	3	770	457	000	400	450	007
7857.	1404420073353201	4044200733531	211MGTY	7	NF 998	1	0	3	960	523	9889	433	519	001
8004.	14043430732843010	4043440732840	211MGTY	7	NK1052	3	0	0	870	745	9528	679	740	001
8007.	1404543073354901	4045430733549	211MGTY	7	NF 879	2	0	0	31200	564	12882	490	564	001
8031.	2404046073305903	4040460733058	211MGTY	7	NJ1233	1	0	0	230	513	000	389	510	51303
8043.	1404757073283301	4047540732831	211MGTY	7	NK 763	3	0	0	02220	688	22216	515	688	001
8054.	14045570732705030	4045570732705	211MGTY	7	NL 837	3	0	0	01780	585	000	510	580	001
8124.	1404500073295501	4044460733000	211MGTY	7	NJ 935	3	0	0	01160	543	000	483	543	001
8183.	1405146073313401	4051460733134	112GLCLU7		NH 496	3	0	0	900	230	000	181	230	48702
8196.	2403952073351507	4039520733616	211MGTY	7	NF1350	1	0	0	240	625	2813	560	620	007
8214.	24041560732620040	4041560732620	211MGTY	7	NL1175	3	0	0	370	686	4078	605	686	004
8216.	1404000073371001	4040000733710	211MGTY	7	NF1209	1	0	0	340	665	000	600	660	001
8217.	2404034073371004	4040040733710	211MGTY	7	NF1208	1	0	0	360	508	000	0	0	004
8249.	1404639073311102	4046320733111	211MGTY	7	NJ 813	3	0	0	01630	495	000	400	490	001
8250.	3404100073371605	4041080733716	211MGTY	7	NE1291	1	0	0	480	485	4906	420	480	005
8253.	1404002073333301	4040030733334	211MGTY	7	NG1298	1	0	0	240	699	000	563	695	001
8272.	1404509073302901	4045090733026	211MGTY	7	NJ1066	1	0	0	810	547	8053	389	547	003
8321.	1404401073315103	4044000733147	211MGTY	7	NH1081	1	0	0	970	674	000	574	674	004
8326.	2405116073372903	4051160733729	112GLCLU7		NE 580	3100	0	530	168	5438	120	165		003
8327.	2405113073372607	4051130733726	112GLCLU7		NE 580	3100	0	530	168	5452	118	168		007
8415.	2404225073293307	4042260732933	211MGTY	7	NK1101	1	0	0	580	625	000	609	625	007
8570.	1404922073292501	4049190732931	211MGTY	7	NK 603	3126	02380	600	000	560	600	61001		
8457.	1404457073340701	4044570733407	211MGTY	7										

S	74265.	140443007322530474044300732253	211MGTY 1	SJ 314	0	0	01546	11515407	107	112	004
S	74536.	140443007324490304044300732449	211MGTY 1	SL 316	4	99	0 860	441 8575	433	436	003
S	74537.	140443007324490404044300732449	211MGTY 1	SL 316	4	99	0 860	196 8578	183	193	004
S	75033.	140443007324490504044300732449	112GLCLU1	SL 316	4	99	0 865	62 8599	47	52	005
S	75034.	140443007324490104044300732449	211MGTY 1	SL 316	4	99	0 865	698 8624	688	693	84001
S	75034.	240443007324490204044300732449	211MGTY 1	SL 316	0	0	0 865	698 8624	688	693	002
S	75454.	1404659073194001.4048590731940	211MGTY 1	SJ 721	7133	02307	74023056	730	735	85501	
S	75454.	2404659073194002.4048590731940	211MGTY 1	SJ 721	0	0	02307	74023056	730	735	002
S	75455.	1404659073194003.4048590731940	211MGTY 1	SJ 721	0	0	02302	50822988	500	505	003
S	75456.	1404659073194004.4048590731940	112GLCLU1	SJ 721	7133	02305	20322952	195	200	004	
S	76016.	2404530073181102X4045300731811	211MGTY 1	SM 721	0	0	0 635	762 6317	752	757	002
S	76017.	1404530073181103X4045300731811	211MGTY 1	SM 721	0	0	0 632	503 6285	495	500	003
S	76018.	1404530073181104X4045300731811	211MGTY 1	SM 721	0	0	0 700	194 6276	186	191	004
S	76019.	1404530073181105X4045300731811	112GLCLU1	SM 721	0	0	0 700	62 6286	57	62	005
S	76673.	1404942073175501.4049420731755	211MGTY 1	SH 848	7169	01300	63312867	625	630	74201	
S	76673.	2404942073175502.4049420731755	211MGTY 1	SH 848	0	0	01300	63312867	625	630	002
S	76674.	1404942073175503.4049420731755	211MGTY 1	SH 848	0	0	01300	46312908	455	460	003
S	76675.	1404942073175504.4049420731755	211MGTY 1	SH 848	0	0	01300	25312928	245	250	004
S	79407.	140393507323500304039370732350	211LLYD.1	SP 256	4158	3 781219	74211921214124003				
S	79408.	140393507323500404039370732350	211MGTY 1	SP 256	4158	3 78	680 722 670	675	70204		
S	1.	140435407322590104043540732259	112GLCLU1	SM 4048	4	0	0 599	30 000	0	0	001
S	1.	240435407322590204043540732259	112GLCLU1	SM 4048	4	0	0 598	50 000	0	0	002
S	1.	340435307322590304043530732259	112GLCLU1	SM 4048	4	0	0 580	69 000	0	0	001
S	1.	440435407322590404043540732259	112GLCLU1	SM 404C	4	0	0 596	70 000	0	0	003
S	4.	140432207323040104043220732304	112GLCLU1	SM 398A	4	0	0 531	24 000	0	0	001
S	4.	2404322073230402.4043220732304	112GLCLU1	SM 398B	4	0	0 531	49 000	0	0	002
S	4.	3404322073230403.4043220732304	112GLCLU1	SM 398C	4	0	0 532	90 000	0	0	003
S	5.	1404326073223901.4043260732238	112GLCLU1	SM 418A	4	0	0 537	26 000	0	0	001
S	5.	2404326073223902.4043260732238	112GLCLU1	SM 418B	4	0	0 539	46 000	0	0	002
S	5.	3404326073223903.4043260732238	112GLCLU1	SM 418C	4	0	0 538	77 000	0	0	003
S	12.	1404312073221501X4043120732215	112GLCLU1	SN 431A	4	0	0 398	25 000	0	0	001
S	12.	2404312073221502X4043120732215	112GLCLU1	SN 431B	4	0	0 397	46 000	0	0	002
S	12.	3404312073221503X4043120732215	112GLCLU1	SN 431C	4	0	0 398	70 000	0	0	003
S	12.	4404312073221504X4043120732215	112GLCLU1	SN 431B	4	0	0 00	54 000	0	0	004
S	12.	5404312073221505X4043120732215	112GLCLU1	SN 431C	4	0	0 400	84 000	0	0	005
S	100.	1404350073231401.4043500732314	1	SM 394	4	0	0 00	205 000	0	0	001
S	125.	1404354073225301.4043540732253	112GLCLU1	SM 414B	4	0	0 00	44 000	0	0	001
N	107.	1404732073352401.4047330733524	211MGTY 7	NF 796	3118	02110	49520259	455	495	001	
N	103.	2403931073343102.40481907333531	7	NF 780	0	89	02450	298 000	275	298	002
N	131.	2403949073341705.4039490733417	211MGTY 7	NG1350	1	13	0 110	530 000	467	523	005
N	132.	1403952073342001.4039510733418	211MGTY 7	NG1350	1	13	0 200	515 000	466	507	001
N	133.	1403952073342002.4039530733420	211MGTY 7	NG1259	1	13	0 200	529 000	471	512	001
N	134.	1403951073341601.4039500733415	211MGTY 7	NG1360	1	13	0 200	528 000	467	517	001
N	142.	1404444073321001.4044410733207	211MGTY 7	NH 976	3104	01150	15811617	128	153	001	
N	142.	140462707331120104046260733112	112GLCLU7	NJ 813	3104	01620	15316306	130	150	001	
N	150.	140462707331120204046290733111	112GLCLU7	NJ 813	3104	01620	148 000	122	142	001	
N	157.	1404831073345101.4048420733448	211MGTY 7	NG 628	3	0	02180	36021841	335	360	001
N	180.	240444907326430104044490732648	211MGTY 7	NL 955	3	92	31450	184 000	149	184	19002
N	192.	240443207329010204044320732901	211MGTY 7	NK 937	3	92	01045	176 000	112	173	17602
N	1402.	2403950073361401.4039500733614	112GLCLU7	NF1350	1	27	0 190	32 000	0	0	3201
N	198.	2404917073292202.4049170732922	211MGTY 7								

5167.	2404041073343302	4040410733438	211MGTY 7	NG1234	1	0	0	370	501	000	445	495	002
5259.	2404120073322501	4041190733227	211MGTY 7	NH1159	1	0	0	390	317	000	241	312	002
5302.	1404246073314301	4042460733143	211MGTY 7	NJ1009	1	25	3	660	489	000	431	484	001
5305.	1404325073293501	4045240732944	211MGTY 7	NJ 991	3	0	0	1290	167	000	115	167	001
5319.	1404155073345001	4041540733453	211MGTY 7	NG1125	1	0	0	580	315	000	260	310	001
5320.	1404155073344801	4041550733447	211MGTY 7	NG1135	1	0	0	600	384	000	319	379	001
5321.	1404245073320201	4042420733157	211MGTY 7	NH1180	1	0	0	710	514	7048	449	509	001
5322.	1404245073315902	4042430733202	211MGTY 7	NH1170	1	0	0	700	515	000	470	510	001
5336.	2404441073320901	4044410733207	211MGTY 7	NH 976	3	0	0	1140	528	000	472	523	003
5404.	3404419073364304	4044200733644	211MGTY 7	NF 928	1	0	3	900	575	9130	500	572	004
5405.	3404425073365503	4044230733655	211MGTY 7	NF 918	1	0	3	920	557	9449	473	553	003
5596.	1404453073372501	4044540733726	211MGTY 7	NE 984	2	0	0	21060	46810652	403	463	001	
5654.	1404451073352601	4044510733526	211MGTY 7	NF 995	2	0	3	980	340	9959	275	335	001
5695.	1403925073354301	4039220733543	211MGTY 7	NF1383	1	0	0	240	529	2533	466	526	001
5696.	2403940073341501	4039450733415	211MGTY 7	NG1360	1	0	0	200	523	000	468	518	002
5703.	140415407326190304041560732620	211MGTY 7	NL1175	3	0	0	370	459	000	384	459	001	
5707.	1404054073294901	4040540732948	211MGTY 7	NJ1292	1	0	0	260	384	000	305	384	001
5803.	14040320732900304040320732800	211MGTY 7	NK1295	3	0	0	90	143	000	0	0	003	
5824.	140403207328002504040320732800	211MGTY 7	NK1295	3	0	0	90	127	000	0	0	025	
5994.	1405211073371901	4052110733718	211MGTY 7	NE 493	3	0	0	1300	226	000	173	226	001
6045.	2404432073365602	4044320733656	211MGTY 7	NF 917	1	0	3	970	328	8721	277	328	002
6046.	2404419073354501	4044160733548	211MGTY 7	NF 979	1	0	0	31010	175	9060	145	175	002
6076.	240465007329110204046500732911	211MGTY 7	NK 821	3	0	0	1580	358	000	296	358	002	
6077.	240465107329130104046490732910	211MGTY 7	NK 821	3	0	0	1580	465	000	398	460	002	
6079.	140453707328480104045350732848	211MGTY 7	NK 849	3	0	0	1230	28012970	225	275	001		
6092.	1404906073275101	4049120732751	211MGTY 7	NK 624	3	0	0	2410	637	000	561	631	001
6093.	1404906073275102	4049060732751	211MGTY 7	NK 694	3	0	0	2590	612	000	546	606	001
6148.	2404216073273301	4042160732733	211MGTY 7	NL1112	3	0	0	510	566	000	462	561	002
6149.	240421507326220304042150732622	211MGTY 7	NL1173	3	0	0	420	640	000	585	640	003	
6150.	240424607329030104042450732903	211MGTY 7	NK1039	3	0	0	610	612	000	545	607	002	
6191.	2404776073305301	4047070733049	211MGTY 7	NJ 739	3	0	0	1760	555	000	489	550	002
6315.	1404525073362602	4045260733626	211MGTY 7	NF 941	2	0	0	31070	35310436	298	348	001	
6442.	140412307328500304041230732852	211MGTY 7	NK1149	3	0	0	310	612	000	524	612	002	
6443.	140412307328500204041230732852	211MGTY 7	NK1149	3	0	0	310	268	000	190	268	003	
6507.	2404630073293901	4046300732938	211MGTY 7	NK 803	3	0	0	1580	60116003	523	596	002	
6544.	140440907327130104044060732713	211MGTY 7	NL 939	3	0	0	31010	227	000	175	222	23301	
6706.	140404107328340104040390732835	211MGTY 7	NK1264	3	0	0	260	626	2739	566	626	001	
6707.	140404307328360104040390732835	211MGTY 7	NK1264	3	0	0	260	492	2748	414	492	002	
6893.	1404046073354501	4040490733544	211MGTY 7	NF1283	1	0	0	420	565	000	500	560	003
6915.	140440007328320104044010732831	211MGTY 7	NK1060	3	0	0	950	516	9445	558	606	001	
6916.	240435607328310204043560732831	211MGTY 7	NK1061	3	0	0	950	613	9433	561	611	002	
6956.	140455707327050104045560732705	211MGTY 7	NL 837	3	0	0	1780	602	000	514	597	002	
7057.	1404635073331901	4046350733311	211MGTY 7	NH 812	3	0	0	1580	53116280	480	530	001	
7076.	1404339073330401	40433907333040	211MGTY 7	NJ1043	1	0	0	910	674	9239	569	674	002
7293.	1404305073371201	4043050733714	211MGTY 7	NE1097	1	0	0	610	587	000	394	444	002
7298.	2404305073371403	4043050733714	211MGTY 7	NE1097	1	0	2	610	444	000	394	444	003
7377.	140431207327480104043130732750	211MGTY 7	NK1096	3	0	0	670	758	000	608	758	001	
7407.	1404002073333203	4040020733332	211MGTY 7	NG1298	1	0	0	240	0	2394	378	530	003
7407.	2404002073333213	4040020733332	211MGTY 7	NG1298	1	0	0	240	648	2394	480	645	013
7414.	140405607326110104040540732613	211MGTY 7	NI 1282	3	0	0	220	537	000	372	530	001	

9.5.9

198.	2404917073292902	4049170732929	211MGTY 7	NK 603	3126	02370	616	000	566	616	002
199.	1404920073293101	4049220732924	211MGTY 7	NK 613	3126	02330	61123351	544	599		001
1605.	1404454073295401	4044550732955	211MGTY 7	NJ 984	3	0	01200	109	000	68	101
1606.	1404441073295201	4045000732956	211MGTY 7	NJ 983	3	0	01220	108	000	81	103
1798.	1404516073295304	4045180732953	211MGTY 7	NJ 981	3	0	01250	105	000	80	105
1850.	2404516073293501	4045170732942	211MGTY 7	NJ 991	3	0	01260	175	000	135	165
1923.	1404441073295001	4044420732953	211MGTY 7	NJ 986	3	0	01140	359	000	293	348
1937.	1404409073271101	4044090732711	211MGTY 7	NL 939	3	99	31060	150	000	121	146
2072.	1404639073311101	4046340733111	112GLCLU7	NJ 813	3	0	01620	159	000	138	159
2316.	1405106073372501	4051070733723	112GLCLU7	NE 581	3	0	01570	170	000	0	170
2528.	2405107073343401	4050010733432	211MGTY 7	NG 538	3	0	0	930	328	9396	278
2580.	2404523073314504	4043230733145	211MGTY 7	NH1095	1	0	0	750	357	000	321
2603.	14040560732605020	4040560732605	112GLCLU7	NL1292	3	0	0	240	71	000	34
2747.	2404446073365001	4044460733650	211MGTY 7	NF 925	2	52	3	920	333	9297	278
2748.	3404445073365101	4044450733651	211MGTY 7	NF 915	2	52	3	940	515	9306	460
3436.	4404302073332504	4043020733325	211MGTY 7	NH1007	1	0	0	770	560	000	494
3457.	1404310073331601	4043080733320	211MGTY 7	NH1007	1	0	0	800	325	000	280
3463.	1404132073311701	4041320733114	211MGTY 7	NJ1118	1	0	0	300	303	000	247
3465.	4404305073333104	4043050733331	211MGTY 7	NG1097	1	0	0	770	585	000	519
3466.	1405115073372501	4051130733727	112GLCLU7	NE 580	3100	0	530	177	4940	148	173
3468.	2404445073310101	4044450733104	211MGTY 7	NJ 925	3	0	01170	169	000	116	169
3552.	2404453073320401	4044540733203	211MGTY 7	NH 974	3	0	01190	169	000	116	169
3553.	2404455073324901	4044530733246	211MGTY 7	NH 934	3	0	01170	152	000	99	152
3613.	1404360073314701	4043360733046	211MGTY 7	NJ1043	1	0	0	990	420	7850	377
3700.	2404226073293501	4042260732935	112GLCLU7	NK1101	1	0	0	580	142	000	89
3766.	1404355073291201	4043520732911	211MGTY 7	NK1021	3	0	0	910	386	000	328
3893.	1404226073293401	4042280732933	211MGTY 7	NK1101	1	0	0	580	150	000	98
3895.	2404119073323001	4041190733231	211MGTY 7	NH1159	1	0	0	410	349	000	312
3934.	1404473073370901	4044020733708	211MGTY 7	NF1001	1	14	2	860	422	8834	377
3935.	1404401073370501	4044000733705	211MGTY 7	NF1001	1	14	2	840	415	8625	370
4042.	1404309073274501	4043090732745	112GLCLU7	NL1006	3	0	0	520	154	000	96
4063.	2404533073284901	4045320732849	211MGTY 7	NK 940	3	0	01240	233	000	145	233
4077.	1404631073293901	4046310732939	211MGTY 7	NK 803	3	0	01580	470	000	413	463
4133.	1404605073303001	4046090733034	211MGTY 7	NJ 751	3	0	01920	445	000	400	450
4144.	2404533073284901	4045330732848	211MGTY 7	NK 940	3	0	01240	235	000	153	235
440.	1404011073310536	4040110733105	7	NJ1227	1	46	0	90	80	000	0
4706.	1404524073363201	4045240733632	211MGTY 7	NF 931	2	0	01060	36010869	305	355	
4746.	1404602073313201	4046020733128	211MGTY 7	NJ 702	3	0	02000	459	000	403	453
4765.	1404755073372401	4047550733724	211MGTY 7	NE 783	2	0	02150	49019961	435	485	
4800.	2405221073300701	4051540732958	211MGTY 7	NJ 485	3	0	0	360	302	3590	214
4825.	1404301073371401	4042590733715	211MGTY 7	NE1098	1	0	2	580	365	000	325
4843.	1404306073332901	4043070733328	211MGTY 7	NG1097	1	0	0	790	555	8514	500
4850.	1404323073314601	4043230733136	211MGTY 7	NH1095	1	0	0	810	472	000	415
4851.	3404429073305502	4044290733055	211MGTY 7	NJ 937	1	0	01100	40810923	353	403	
4803.	1404154073261302	4041540732620	211MGTY 7	NL1175	3	0	0	370	184	000	113
4702.	1404524073295601	4045180733018	211MGTY 7	NJ 961	3	0	01220	169	000	149	169
4756.	2404207073345501	4042060733452	211MGTY 7	NG1124	1	0	0	610	312	000	245
4757.	2404209073345501	4042100733454	211MGTY 7	NG1124	1	0	0	590	324	000	257
4758.	2404209073345001	4042090733448	211MGTY 7	NG1124	1	0	0	550	446	000	363
4759.	2404206073344902	4042050733447	211MGTY 7	NG1134	1	0	0	560	360	000	283
4757.	2404206073344902	4042050733447	211MGTY 7	NG1134	1	0	0	560	360	000	283

9.6.9

57551.	1405141073191001	4051380731905	211MGTY	7	SG	821	7149	01710	60916576	515	605	66301
57551.	1404230073225001	4042320732256	211MGTY	7	SN	375	4165	0 420	583 3638	0	574	59301
58192.	1404520073150402	4045310731501	211MGTY	7	SM	906	8180	0 659	306 000	0	0	60502
58705.	1405135073235501	4051350732400	211MGTY	7	SF	532	7146	51050	66620157	572	663	70201
59024.	1404350073191001	4043570731915	211MGTY	7	SN	683	8198	0 450	623 000	0	623	65501
59709.	1404450073225201	4044560732522	211MGTY	7	SL	292	4 0 3	850 712	000 650	705	72301	
60330.	1404321073226010	4043240732222	211MGTY	7	SM	439	4166	0 430	328 000	262	328	33701
60497.	1404600073174002	4046040731752	211MGTY	7	SL	757	4 0 0	740 283	7429 220	280	70802	
61353.	1403017073163301	4038170731633	211MGTY	7	SS	640	0 0 0	100 290	000 0	0	001	
62225.	1405015073234201	4050150732343	211MGTY	7	SG	513	7 0 0	01100 790	18000 690	785	79001	
62762.	1404305073161401	4043050731615	211MGTY	7	SO	783	8187	0 260	714 2102	650	710	73901
63001.	1405115073260901	4051140732609	112GLCLU7	7	SF	401	7146	02300	53323000	446	526	59701
63633.	1404804073204401	4048040732044	211MGTY	7	SJ	636	7133	01636	72516434	658	720	75001
63639.	1404605073203701	4046040732047	211MGTY	7	SJ	636	7133	01545	74515600	660	735	74801
63840.	1404218073190400	4042180731904	211MGTY	7	SO	594	0 0 0	00 315	000 251	311	38401	
63935.	1404651073185101	4048510731851	112GLCLU7	7	SJ	763	4159	02850	60528500	539	599	66001
63935.	1404432073151300	4044320731513	211MGTY	7	SN	374	8187	0 390	713 3740	649	710	002
63939.	1404605073174001	4046040731746	211MGTY	7	SL	767	0 0 0	760 655	6775 550	651	66301	
64806.	1404214073242001	4042040732420	211MGTY	7	SN	286	0 0 0	430 509	3669 428	505	52301	
64807.	1404604073252100	4046040732521	211MGTY	7	SO	194	0 0 0	260 648	1732 554	645	65702	
64947.	1404515073225502	4045190732245	211MGTY	7	SL	453	0 0 0	900 534	7311 470	530	53402	
64947.	1404605073245001	4046040732458	211MGTY	7	SN	254T	0 0 0	450 560	000 540	560	001	
64942.	2404206073245002	4042060732458	045.00	7	T		0 0 0	450 0	000 0	0	002	
65346.	1404432073151303	4044320731513	211MGTY	7	SN	874	0 0 0	390 668	3645 604	665	003	
651214.	1404210073250201	4042100732502	211MGTY	7	SN	244	0 0 0	450 395	000 330	390	39501	
651457.	1404321073226020	4043230732222	211MGTY	7	SM	439	4157	0 00	623 3241	0	623	002
651673.	1404225073193001	4042250731930	211MGTY	7	SO	572	0 0 0	00 763	2227 669	760	77201	
66049.	1404230073204101	4042320732041	211MGTY	7	SN	519	4 0 0	240 746	2366 671	743	78001	
65360.	1405032073162902	4050340731618	211MGTY	7	SH	954	0 0 0	01410 703	13790 551	667	002	
65361.	1405135073155001	4051430731556	211MGTY	7	SG	1006	0169	01480	52114307	437	517	001
65367.	1405140073191001	4051360731902	211MGTY	7	SG	821	0 0 0	01710 453	000 370	448	001	
65463.	1404215073250202	4042150732502	211MGTY	7	SN	244	0 0 0	450 423	000 338	421	002	
654731.	1403622073155001	4036220731550	211MGTY	7	SS	691	8 0 0	80 750	000 699	750	001	
65520.	1405144073313501	4051440733135	112PGWF	7	NH	496	3 0 0	900 517	000 451	512	55601	
65734.	1404320073174102	4043200731741	211MGTY	7	SN	708	0 0 0	00 0	000 0	0	002	
65734.	1405126073273303	4051260732737	112GLCLU7	7	SE	326	7 0 0	500 257	000 213	254	27303	
65703.	1404936073152701	4049360731525	211MGTY	7	SJ	984	0 0 0	01320 423	12470 329	389	001	
65937.	1404419073171601	4044190731716	211MGTY	7	SN	752	0 0 0	510 463	000 388	458	51501	
663966.	1405055073150001	4050550731509	211MGTY	7	SH	1034	11169	0 790	653 6903	560	650	001
66505.	1404352073215001	4043520732158	211MGTY	7	SM	466	4167	0 540	650 000	575	645	001
66505.	2403921073353201	4039220733532	211MGTY	7	NF	1393	1 13 0	200 510	000 450	500	002	
666366.	1405150073254001	405150732548	112GLCLU7	7	SE	446	7146	01700	479 000	400	460	001
66629.	1404320073174103	4043200731741	211MGTY	7	SN	708	8209	0 00	718 2983	0	718	003
66556.	1404308073243101	4043080732431	211MGTY	7	SM	307	4 0 3	500 728	000 647	707	75301	
67064.	1403825073182301	4038250731823	211MGTY	7	SR	546	4 0 0	90 205	000 167	172	001	
71063.	1404320073150701	4043200731507	211MGTY	7	SM	907	8187	0 619	798 5643	0	798	001
72.	1404255073371901	4042590733716	211MGTY	7	NE	1098	1 16 0	590 135	000 82	131	001	
72.	2404259073371609	4042590733716	211MGTY	7	NE	1098	1 16 0	590 381	000 336	375	009	
72.	2404256073370901	4042520733714	211MGTY	7	NE	1099	1 16 2	619 450	000 338	428	002	
80.	1404256073371501	4042560733712	211MGTY	7	NF	1098	1 16 2	550 483	5794 423	475	001	
81.	1404256073371501	4042560733709	211MGTY	7	NF	1097	1 16 2	550 483	5794 423	475	001	

22369.	1404357073181502X	4043570731814	211MGTY 7	SN 683	8209	0	449	466	000	0	465	50302	
22471.	1404922073162901	4049220731629	211MGTY 7	SJ 914	7169	01650	383	000	312	381	60201		
22543.	1404705073190701X	4047060731902	211MGTY 7	SK 716	7159	01140	41511	1668	347	403	54101		
23145.	1405226073231701	4052250732317	112GLCLU7	SE 597	7141	01950	600	000	520	600	60501		
23445.	1404659073164101X	4046590731642	211MGTY 7	SL 842	8189	01100	61011	1356	541	605	61001		
23522.	1404606073191301	4046060731913	112GLCLU7	SJ 728	7133	01450	424	000	358	420	42401		
23523.	1404750073215001	4047500732150	112GLCLU7	SJ 576	7133	01900	445	000	327	440	45801		
23715.	1404955073170402	4049550731704	112GLCLU7	SH 898	11169	01550	340	000	238	310	34002		
23932.	1404922073162701	4049220731628	211MGTY 7	SJ 914	7169	01650	40517	000	313	402	40901		
23943.	140443073211301X	4044300732113	211MGTY 7	SM 523	4167	0	500	634	5234	558	631	66901	
23997.	1405050073214501	4050440732147	211MGTY 7	SG 643	7141	02000	62519	250	540	621	70501		
23999.	1405140073222101	4051400732221	211MGTY 7	SF 635	7141	02200	60122	670	525	597	66601		
24246.	1404639073151401X	4046390731514	211MGTY 7	SL 927	8189	0	900	597	000	461	517	59701	
24674.	1404431073211401X	4044310732115	211MGTY 7	SM 523	4167	0	500	625	5330	550	625	65401	
26071.	2404720073261002	4047200732610	211MGTY 7	SJ 301	7	0	02600	334	000	293	334	33402	
26247.	1405059073233701	4050590732337	211MGTY 7	SF 548	7146	01780	447	000	264	447	50101		
26248.	14046070732530010	4046070732530	211MGTY 7	SK 312	7	0	51000	552	000	512	552	54701	
26555.	1404316073153801X	4043380731540	211MGTY 7	SO 620	8187	0	260	776	2925	710	773	78201	
27070.	1405134073235602	4051340732358	112GLCLU7	SF 532	7151	02090	560	000	494	557	61202		
26554.	14040470732523010	4040470732521	112GLCLU7	SO 194	4156	3	250	79	000	53	78	8501	
26555.	14040470732521040	4040470732521	7	SO 194	4156	3	250	78	000	0	0	7804	
29491.	14041200732216010	4041210732246	211MGTY 7	SO 364	4161	0	250	499	2451	390	493	65201	
29352.	1405042073195501	4050420731957	211MGTY 7	SG 747	7139	01900	607	000	530	601	69001		
29952.	1404632073220702	4046320732207	112GLCLU7	SH 579	7133	02080	675	000	485	546	67702		
30007.	14046070732530020	4046070732530	211MGTY 7	SK 312	7148	01010	595	000	510	590	002		
30008.	1405056073233801	4050560732338	211MGTY 7	SF 548	7146	01850	488	000	423	483	48501		
30506.	14043150732255010	4043200732244	211MGTY 7	SL 453	4167	0	750	614	7746	546	618	63001	
31038.	1404155073212205	4041560732125	211MGTY 7	SO 452	4166	0	190	528	000	424	525	55505	
31104.	1404723073164401X	4047000731641	211MGTY 7	SL 842	8189	01100	65810	547	592	655	66501		
32412.	1404736073153201	4047360731532	7	SK 929	8189	01100	900	000	0	0	90001		
32501.	14040460732521015	4040470732521	211MGTY 7	SO 194	4156	3	260	632	1967	560	630	66301	
33006.	1405132073155901	4051430731554	211MGTY 7	SG1006	11169	01470	50414	194	436	503	51201		
33621.	1403826073173201	4038260731732	7	B SR 597	4	0	0	110	306	000	295	305	30601
34021.	14047230732313010	4047030732313	211MGTY 7	SJ 479	7133	02600	710	000	615	705	71001		
34030.	1404536073210801X	4045360732108	211MGTY 7	SL 554	4167	0	540	538	5845	0	538	56301	
34031.	1404534073210801X	4045340732108	211MGTY 7	SL 555	4167	0	541	521	000	0	521	56301	
34032.	1404606073191201	4046060731912	112GLCLU7	SJ 738	7133	01500	441	000	369	436	44101		
34063.	1404635073214001X	4046350732140	211MGTY 7	SK 556	7148	02000	736	000	656	736	74201		
34064.	1404635073214002X	4046350732140	211MGTY 7	SK 556	7148	02000	632	000	0	0	66402		
34595.	14042030732422020	4042040732422	211MGTY 7	SN 286	4156	0	436	482	3765	412	482	51302	
34731.	1401735073173201	4036200731735	7	SR 588	4157	0	00	310	000	300	310	31002	
35007.	1404916073253201	4049160732532	211MGTY 7	SG 397	7144	02320	66023	250	575	660	70101		
35059.	1405140073190301	4051390731904	211MGTY 7	SG 821	7149	01710	53317	541	468	530	62201		
35714.	1404456073182502X	4044560731824	211MGTY 7	SM 704	4159	0	630	308	000	244	304	35402	
36743.	1404219073190401	4042190731904	211MGTY 7	SO 594	4157	0	140	336	1400	272	336	38301	
36791.	1405014073161401	4050470731615	211MGTY 7	SH 963	7169	01400	67413	752	534	670	68001		
36976.	1404923073162201	4049230731628	211MGTY 7	SJ 913	0169	01600	418	000	331	418	45801		
37100.	1405116073205701	4051160732057	7	SG 700	7141	0	00	688	000	542	688	68801	
37351.	1405141073191001	4051360731905	211MGTY 7	SG 821	7149	01710	60916	576	515	605	66301		
37551.	14042360732257010	4042320732254	211MGTY 7	SN 375	4165	0	420	583	3638	0	574	58301	

9.8.9

10.1.1



5.5 EPA Form 2070-12

Hazardous Waste Disposal



Potential Hazardous Waste Site

Preliminary Assessment



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY 152113

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common or descriptive name of site) Hazardous Waste Disposal		02 STREET, ROUTE NO. OR SPECIFIC LOCATION IDENTIFIER 11A Picone Blvd.			
03 CITY Farmingdale		04 STATE NY	05 ZIP CODE 11735	06 COUNTY Suffolk	07 COUNTY CODE DIS
08 COORDINATES: LATITUDE 40° 44' 43"		LONGITUDE 73° 25' 13"			

09 DIRECTIONS TO SITE (Starting from nearest public road)
From L.I.E. take Rt. 110 south, Take left on Picone Blvd.

III. RESPONSIBLE PARTIES

01 OWNER (Name) Little Joseph Realty, Inc.		02 STREET (Business name, address) 1637 Broad Hollow Rd.			
03 CITY Farmingdale		04 STATE NY	05 ZIP CODE 11735	06 TELEPHONE NUMBER (516) 249-3400	
07 OPERATOR (Name and organization) Mr. George Lawrence		08 STREET (Business name, address) 1 Shore Rd.			
09 CITY Glenwood Landing		10 STATE NY	11 ZIP CODE 11747	12 TELEPHONE NUMBER 516-273-3150	
13 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A PRIVATE <input type="checkbox"/> B FEDERAL <input type="checkbox"/> C STATE <input type="checkbox"/> D COUNTY <input type="checkbox"/> E MUNICIPAL <input type="checkbox"/> F OTHER <input type="checkbox"/> G UNKNOWN					

14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply)
☐ A RCRA 3001 DATE RECEIVED MONTH DAY YEAR ☐ B UNCONTROLLED WASTE SITE (RCRA 103) DATE RECEIVED MONTH DAY YEAR ☐ C NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON SITE INSPECTION <input checked="" type="checkbox"/> YES DATE 6/25/87 <input type="checkbox"/> NO		BY (Check all that apply) <input type="checkbox"/> A EPA <input type="checkbox"/> B EPA CONTRACTOR <input type="checkbox"/> C STATE <input checked="" type="checkbox"/> D OTHER CONTRACTOR <input type="checkbox"/> E LOCAL HEALTH OFFICIAL <input type="checkbox"/> F OTHER CONTRACTOR NAME(S) Roux Associates, Inc.			
02 SITE STATUS (Check one) <input type="checkbox"/> A ACTIVE <input checked="" type="checkbox"/> B INACTIVE <input type="checkbox"/> C UNKNOWN		03 YEARS OF OPERATION 1979 1982 <input type="checkbox"/> UNKNOWN BEGINNING YEAR ENDING YEAR			

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT (KNOWN OR ALLEGED)
Chlorinated and non-chlorinated hydrocarbons, waste resin, paint sludge.

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND OR POPULATION
If wastes have been released into soil then a potential threat to ground water exists.

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one) (High or medium or other) (Complete Part 2: Waste information and Part 3: List of other hazardous conditions and incidents)
☐ A HIGH ☐ B MEDIUM ☐ C LOW ☐ D NONE
(Immediate or required action) (Inspection or other possible basis) (No further action needed) (Complete current inspection report)

VI. INFORMATION AVAILABLE FROM

01 CONTACT J. Patrick Brynes Joanne Yeary		02 OF (Agency, Organization) Roux Associates, Inc.		03 TELEPHONE NUMBER 516-673-7200
04 PERSON RESPONSIBLE FOR ASSESSMENT J. Patrick Brynes		05 AGENCY	06 ORGANIZATION	07 TELEPHONE NUMBER 516-673-7200
08 DATE 6/25/87 MONTH DAY YEAR				



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 2 - WASTE INFORMATION

I. IDENTIFICATION
01 STATE NY 02 SITE NUMBER 152113

II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

01 PHYSICAL STATES (See 40 CFR 300.106) A SOLID B POWDER FINE X SLUDGE D OTHER _____ E SOLUBLE X LIQUID X GAS	02 WASTE QUANTITY AT SITE (See 40 CFR 300.106) TONS: unknown CUBIC YARDS: unknown NO. OF DRUMS: ± 1900	03 WASTE CHARACTERISTICS (See 40 CFR 300.106) X TOXIC X CORROSIVE X RADIOACTIVE X PERSISTENT E SOLUBLE X INFECTIOUS X FLAMMABLE X IRRITABLE X HIGHLY VOLATILE X EXPLOSIVE X REACTIVE X INCOMPATIBLE X NOT APPLICABLE
--	---	---

III. WASTE TYPE

01 CATEGORY	02 SUBSTANCE NAME	03 GROSS AMOUNT	04 UNIT OF MEASURE	05 COMMENTS
SLO	SLUDGE	Unknown		
OWW	OLY WASTE	Unknown		
SOL	SOLVENTS	Unknown		
PST	PESTICIDES			
OCG	OTHER ORGANIC CHEMICALS	Unknown		
IOC	INORGANIC CHEMICALS			
ACD	ACIDS	Unknown		
BAS	BASES			
MES	HEAVY METALS			

IV. HAZARDOUS SUBSTANCES (See 40 CFR 300.106, 300.107, 300.108, 300.109, 300.110, 300.111, 300.112, 300.113, 300.114, 300.115, 300.116, 300.117, 300.118, 300.119, 300.120, 300.121, 300.122, 300.123, 300.124, 300.125, 300.126, 300.127, 300.128, 300.129, 300.130, 300.131, 300.132, 300.133, 300.134, 300.135, 300.136, 300.137, 300.138, 300.139, 300.140, 300.141, 300.142, 300.143, 300.144, 300.145, 300.146, 300.147, 300.148, 300.149, 300.150, 300.151, 300.152, 300.153, 300.154, 300.155, 300.156, 300.157, 300.158, 300.159, 300.160, 300.161, 300.162, 300.163, 300.164, 300.165, 300.166, 300.167, 300.168, 300.169, 300.170, 300.171, 300.172, 300.173, 300.174, 300.175, 300.176, 300.177, 300.178, 300.179, 300.180, 300.181, 300.182, 300.183, 300.184, 300.185, 300.186, 300.187, 300.188, 300.189, 300.190, 300.191, 300.192, 300.193, 300.194, 300.195, 300.196, 300.197, 300.198, 300.199, 300.200, 300.201, 300.202, 300.203, 300.204, 300.205, 300.206, 300.207, 300.208, 300.209, 300.210, 300.211, 300.212, 300.213, 300.214, 300.215, 300.216, 300.217, 300.218, 300.219, 300.220, 300.221, 300.222, 300.223, 300.224, 300.225, 300.226, 300.227, 300.228, 300.229, 300.230, 300.231, 300.232, 300.233, 300.234, 300.235, 300.236, 300.237, 300.238, 300.239, 300.240, 300.241, 300.242, 300.243, 300.244, 300.245, 300.246, 300.247, 300.248, 300.249, 300.250, 300.251, 300.252, 300.253, 300.254, 300.255, 300.256, 300.257, 300.258, 300.259, 300.260, 300.261, 300.262, 300.263, 300.264, 300.265, 300.266, 300.267, 300.268, 300.269, 300.270, 300.271, 300.272, 300.273, 300.274, 300.275, 300.276, 300.277, 300.278, 300.279, 300.280, 300.281, 300.282, 300.283, 300.284, 300.285, 300.286, 300.287, 300.288, 300.289, 300.290, 300.291, 300.292, 300.293, 300.294, 300.295, 300.296, 300.297, 300.298, 300.299, 300.300, 300.301, 300.302, 300.303, 300.304, 300.305, 300.306, 300.307, 300.308, 300.309, 300.310, 300.311, 300.312, 300.313, 300.314, 300.315, 300.316, 300.317, 300.318, 300.319, 300.320, 300.321, 300.322, 300.323, 300.324, 300.325, 300.326, 300.327, 300.328, 300.329, 300.330, 300.331, 300.332, 300.333, 300.334, 300.335, 300.336, 300.337, 300.338, 300.339, 300.340, 300.341, 300.342, 300.343, 300.344, 300.345, 300.346, 300.347, 300.348, 300.349, 300.350, 300.351, 300.352, 300.353, 300.354, 300.355, 300.356, 300.357, 300.358, 300.359, 300.360, 300.361, 300.362, 300.363, 300.364, 300.365, 300.366, 300.367, 300.368, 300.369, 300.370, 300.371, 300.372, 300.373, 300.374, 300.375, 300.376, 300.377, 300.378, 300.379, 300.380, 300.381, 300.382, 300.383, 300.384, 300.385, 300.386, 300.387, 300.388, 300.389, 300.390, 300.391, 300.392, 300.393, 300.394, 300.395, 300.396, 300.397, 300.398, 300.399, 300.400, 300.401, 300.402, 300.403, 300.404, 300.405, 300.406, 300.407, 300.408, 300.409, 300.410, 300.411, 300.412, 300.413, 300.414, 300.415, 300.416, 300.417, 300.418, 300.419, 300.420, 300.421, 300.422, 300.423, 300.424, 300.425, 300.426, 300.427, 300.428, 300.429, 300.430, 300.431, 300.432, 300.433, 300.434, 300.435, 300.436, 300.437, 300.438, 300.439, 300.440, 300.441, 300.442, 300.443, 300.444, 300.445, 300.446, 300.447, 300.448, 300.449, 300.450, 300.451, 300.452, 300.453, 300.454, 300.455, 300.456, 300.457, 300.458, 300.459, 300.460, 300.461, 300.462, 300.463, 300.464, 300.465, 300.466, 300.467, 300.468, 300.469, 300.470, 300.471, 300.472, 300.473, 300.474, 300.475, 300.476, 300.477, 300.478, 300.479, 300.480, 300.481, 300.482, 300.483, 300.484, 300.485, 300.486, 300.487, 300.488, 300.489, 300.490, 300.491, 300.492, 300.493, 300.494, 300.495, 300.496, 300.497, 300.498, 300.499, 300.500, 300.501, 300.502, 300.503, 300.504, 300.505, 300.506, 300.507, 300.508, 300.509, 300.510, 300.511, 300.512, 300.513, 300.514, 300.515, 300.516, 300.517, 300.518, 300.519, 300.520, 300.521, 300.522, 300.523, 300.524, 300.525, 300.526, 300.527, 300.528, 300.529, 300.530, 300.531, 300.532, 300.533, 300.534, 300.535, 300.536, 300.537, 300.538, 300.539, 300.540, 300.541, 300.542, 300.543, 300.544, 300.545, 300.546, 300.547, 300.548, 300.549, 300.550, 300.551, 300.552, 300.553, 300.554, 300.555, 300.556, 300.557, 300.558, 300.559, 300.560, 300.561, 300.562, 300.563, 300.564, 300.565, 300.566, 300.567, 300.568, 300.569, 300.570, 300.571, 300.572, 300.573, 300.574, 300.575, 300.576, 300.577, 300.578, 300.579, 300.580, 300.581, 300.582, 300.583, 300.584, 300.585, 300.586, 300.587, 300.588, 300.589, 300.590, 300.591, 300.592, 300.593, 300.594, 300.595, 300.596, 300.597, 300.598, 300.599, 300.600, 300.601, 300.602, 300.603, 300.604, 300.605, 300.606, 300.607, 300.608, 300.609, 300.610, 300.611, 300.612, 300.613, 300.614, 300.615, 300.616, 300.617, 300.618, 300.619, 300.620, 300.621, 300.622, 300.623, 300.624, 300.625, 300.626, 300.627, 300.628, 300.629, 300.630, 300.631, 300.632, 300.633, 300.634, 300.635, 300.636, 300.637, 300.638, 300.639, 300.640, 300.641, 300.642, 300.643, 300.644, 300.645, 300.646, 300.647, 300.648, 300.649, 300.650, 300.651, 300.652, 300.653, 300.654, 300.655, 300.656, 300.657, 300.658, 300.659, 300.660, 300.661, 300.662, 300.663, 300.664, 300.665, 300.666, 300.667, 300.668, 300.669, 300.670, 300.671, 300.672, 300.673, 300.674, 300.675, 300.676, 300.677, 300.678, 300.679, 300.680, 300.681, 300.682, 300.683, 300.684, 300.685, 300.686, 300.687, 300.688, 300.689, 300.690, 300.691, 300.692, 300.693, 300.694, 300.695, 300.696, 300.697, 300.698, 300.699, 300.700, 300.701, 300.702, 300.703, 300.704, 300.705, 300.706, 300.707, 300.708, 300.709, 300.710, 300.711, 300.712, 300.713, 300.714, 300.715, 300.716, 300.717, 300.718, 300.719, 300.720, 300.721, 300.722, 300.723, 300.724, 300.725, 300.726, 300.727, 300.728, 300.729, 300.730, 300.731, 300.732, 300.733, 300.734, 300.735, 300.736, 300.737, 300.738, 300.739, 300.740, 300.741, 300.742, 300.743, 300.744, 300.745, 300.746, 300.747, 300.748, 300.749, 300.750, 300.751, 300.752, 300.753, 300.754, 300.755, 300.756, 300.757, 300.758, 300.759, 300.760, 300.761, 300.762, 300.763, 300.764, 300.765, 300.766, 300.767, 300.768, 300.769, 300.770, 300.771, 300.772, 300.773, 300.774, 300.775, 300.776, 300.777, 300.778, 300.779, 300.780, 300.781, 300.782, 300.783, 300.784, 300.785, 300.786, 300.787, 300.788, 300.789, 300.790, 300.791, 300.792, 300.793, 300.794, 300.795, 300.796, 300.797, 300.798, 300.799, 300.800, 300.801, 300.802, 300.803, 300.804, 300.805, 300.806, 300.807, 300.808, 300.809, 300.810, 300.811, 300.812, 300.813, 300.814, 300.815, 300.816, 300.817, 300.818, 300.819, 300.820, 300.821, 300.822, 300.823, 300.824, 300.825, 300.826, 300.827, 300.828, 300.829, 300.830, 300.831, 300.832, 300.833, 300.834, 300.835, 300.836, 300.837, 300.838, 300.839, 300.840, 300.841, 300.842, 300.843, 300.844, 300.845, 300.846, 300.847, 300.848, 300.849, 300.850, 300.851, 300.852, 300.853, 300.854, 300.855, 300.856, 300.857, 300.858, 300.859, 300.860, 300.861, 300.862, 300.863, 300.864, 300.865, 300.866, 300.867, 300.868, 300.869, 300.870, 300.871, 300.872, 300.873, 300.874, 300.875, 300.876, 300.877, 300.878, 300.879, 300.880, 300.881, 300.882, 300.883, 300.884, 300.885, 300.886, 300.887, 300.888, 300.889, 300.890, 300.891, 300.892, 300.893, 300.894, 300.895, 300.896, 300.897, 300.898, 300.899, 300.900, 300.901, 300.902, 300.903, 300.904, 300.905, 300.906, 300.907, 300.908, 300.909, 300.910, 300.911, 300.912, 300.913, 300.914, 300.915, 300.916, 300.917, 300.918, 300.919, 300.920, 300.921, 300.922, 300.923, 300.924, 300.925, 300.926, 300.927, 300.928, 300.929, 300.930, 300.931, 300.932, 300.933, 300.934, 300.935, 300.936, 300.937, 300.938, 300.939, 300.940, 300.941, 300.942, 300.943, 300.944, 300.945, 300.946, 300.947, 300.948, 300.949, 300.950, 300.951, 300.952, 300.953, 300.954, 300.955, 300.956, 300.957, 300.958, 300.959, 300.960, 300.961, 300.962, 300.963, 300.964, 300.965, 300.966, 300.967, 300.968, 300.969, 300.970, 300.971, 300.972, 300.973, 300.974, 300.975, 300.976, 300.977, 300.978, 300.979, 300.980, 300.981, 300.982, 300.983, 300.984, 300.985, 300.986, 300.987, 300.988, 300.989, 300.990, 300.991, 300.992, 300.993, 300.994, 300.995, 300.996, 300.997, 300.998, 300.999, 300.1000)

5.6 EPA Form 2070-13

Hazardous Waste Disposal



Potential Hazardous Waste Site

Site Inspection Report



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION
01 STATE NY 02 SITE NUMBER 152113

II. SITE NAME AND LOCATION

01 SITE NAME Hazardous Waste Disposal	02 STREET ROUTE NO. OR SPECIFIC LOCATION IDENTIFIER 11A Picone Blvd.
03 CITY Farmingdale	04 STATE NY 05 ZIP CODE 11735 06 COUNTY Suffolk
07 COORDINATES 40° 44' 43" N 73° 25' 13" W	08 TYPE OF OWNERSHIP <input checked="" type="checkbox"/> A PRIVATE <input type="checkbox"/> B FEDERAL <input type="checkbox"/> C STATE <input type="checkbox"/> D COUNTY <input type="checkbox"/> E MUNICIPAL <input type="checkbox"/> F OTHER

III. INSPECTION INFORMATION

01 DATE OF INSPECTION 6/25/87	02 SITE STATUS <input type="checkbox"/> ACTIVE <input checked="" type="checkbox"/> INACTIVE	03 YEARS OF OPERATION 1979 1982 UNKNOWN
04 AGENCY PERFORMING INSPECTION <input type="checkbox"/> A EPA <input type="checkbox"/> B EPA CONTRACTOR <input type="checkbox"/> C MUNICIPAL <input type="checkbox"/> D MUNICIPAL CONTRACTOR <input checked="" type="checkbox"/> E STATE <input checked="" type="checkbox"/> F STATE CONTRACTOR Roux Associates <input type="checkbox"/> G OTHER		

05 CHIEF INSPECTOR J. Patrick Byrnes	06 TITLE Geologist	07 ORGANIZATION Roux Associates	08 TELEPHONE NO. '516'673-7200
09 OTHER INSPECTORS Joanne Yeary	10 TITLE Geologist	11 ORGANIZATION Roux Associates	12 TELEPHONE NO. '516'673-7200
			()
			()
			()
			()
13 SITE REPRESENTATIVES INTERVIEWED Mr. V. Emanuelo	14 TITLE Attorney	15 ADDRESS Farmingdale, NY	16 TELEPHONE NO. '516'249-3400
Mr. Ed Lynch	Property Manager	Farmingdale, NY	'516'249-3400
			()
			()
			()
			()

17 ACCESS GAINED BY <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT	18 TIME OF INSPECTION 9:50 am	19 WEATHER CONDITIONS Clear, sunny, breezy - 75°F
---	----------------------------------	--

IV. INFORMATION AVAILABLE FROM

01 CONTACT J. Byrnes, J. Yeary	02 OF Agency Organization Roux Associates	03 TELEPHONE NO. '516'673-7200
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM J. Patrick Byrnes	05 AGENCY	06 ORGANIZATION
		07 TELEPHONE NO.
		08 DATE 6/25/87



I HIGHLY VOLATILE
 J EXPLOSIVE
 K REACTIVE
 L INCOMPATIBLE
 M NO APPLICABLE

PA FORM 2070-13 (7-81)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION
01 STATE NY 02 SITE NUMBER 152113

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A GROUNDWATER CONTAMINATION 02 ☐ OBSERVED DATE _____ ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ B SURFACE WATER CONTAMINATION 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ C CONTAMINATION OF AIR 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ D FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ E DIRECT CONTACT 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ F CONTAMINATION OF SOIL 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ G DRINKING WATER CONTAMINATION 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ H WORKER EXPOSURE/INJURY 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

N/A

01 ☐ I POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

N/A



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

1 IDENTIFICATION

01 STATE 02 SITE NUMBER
NY 152113

HAZARDOUS CONDITIONS AND INCIDENTS (continued)

1 = J. DAMAGE TO FLORA
4 NARRATIVE DESCRIPTION

02 = OBSERVED (DATE _____)

= POTENTIAL

= ALLEGED

N/A

1 = K. DAMAGE TO FAUNA
4 NARRATIVE DESCRIPTION

02 = OBSERVED (DATE _____)

= POTENTIAL

= ALLEGED

N/A

1 = L. CONTAMINATION OF FOOD CHAIN
4 NARRATIVE DESCRIPTION

02 = OBSERVED (DATE _____)

= POTENTIAL

= ALLEGED

N/A

1 = M. UNSTABLE CONTAINMENT OF WASTES
3 POPULATION POTENTIALLY AFFECTED _____
4 NARRATIVE DESCRIPTION

02 = OBSERVED (DATE _____)

= POTENTIAL

= ALLEGED

N/A

1 = N. DAMAGE TO OFF-SITE PROPERTY
4 NARRATIVE DESCRIPTION

02 = OBSERVED (DATE _____)

= POTENTIAL

= ALLEGED

N/A

1 = O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPS
4 NARRATIVE DESCRIPTION

02 = OBSERVED (DATE _____)

= POTENTIAL

= ALLEGED

N/A

1 = P. ILLEGAL UNAUTHORIZED DUMPING
4 NARRATIVE DESCRIPTION

02 = OBSERVED (DATE _____)

= POTENTIAL

= ALLEGED

N/A

5 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

TOTAL POPULATION POTENTIALLY AFFECTED _____

COMMENTS

No wastes observed on site

SOURCES OF INFORMATION (List all sources of information used in the inspection)

Roux Site Inspection June 25, 1987



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I IDENTIFICATION
01 STATE NY 02 SITE NUMBER 152113

II PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Circle all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A NPDES				
<input type="checkbox"/> B UIC				
<input type="checkbox"/> C AIR				
<input type="checkbox"/> D RCRA				
<input type="checkbox"/> E RCRA INTERIM STATUS				
<input type="checkbox"/> F SPCC PLAN				
<input type="checkbox"/> G STATE <small>Spec. 1</small>				
<input type="checkbox"/> H LOCAL <small>Spec. 1</small>				
<input type="checkbox"/> I OTHER <small>Spec. 1</small>				
<input type="checkbox"/> J NONE				

III SITE DESCRIPTION

01 STORAGE DISPOSAL <small>Circle all that apply</small>	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT <small>Circle all that apply</small>	05 OTHER
<input type="checkbox"/> A SURFACE IMPOUNDMENT			<input type="checkbox"/> A INCINERATION	<input type="checkbox"/> A BUILDINGS ON SITE
<input type="checkbox"/> B PILES			<input type="checkbox"/> B UNDERGROUND INJECTION	
<input type="checkbox"/> C DRUMS ABOVE GROUND			<input type="checkbox"/> C CHEMICAL PHYSICAL	
<input type="checkbox"/> D TANK ABOVE GROUND			<input type="checkbox"/> D BIOLOGICAL	
<input type="checkbox"/> E TANK BELOW GROUND			<input type="checkbox"/> E WASTE OIL PROCESSING	
<input type="checkbox"/> F LANDFILL			<input type="checkbox"/> F SOLVENT RECOVERY	
<input type="checkbox"/> G LANDFARM			<input type="checkbox"/> G OTHER RECYCLING RECOVERY	
<input type="checkbox"/> H OPEN DUMP			<input type="checkbox"/> H OTHER <small>(Specify)</small>	
<input type="checkbox"/> I OTHER <small>(Specify)</small>				

06 COMMENTS

No wastes presently at site

IV CONTAINMENT

01 CONTAINMENT OF WASTES Circle all that apply

☐ A ADEQUATE SECURE ☐ B MODERATE ☐ C INADEQUATE POOR ☐ D INSECURE UNSOUND DANGEROUS

02 DESCRIPTION OF DRUMS DRUM LINES BARRIERS ETC

V ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE ☐ YES ☐ NO

02 COMMENTS

VI SOURCES OF INFORMATION Can include telephone #, date, and name of person interviewed

Roux Site Inspection June 25, 1987



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE NY 02 SITE NUMBER 152113

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY (CHECK IN APPROPRIATE)	02 STATUS	03 DISTANCE TO SITE															
<table border="1"><tr><td>SURFACE</td><td>WELL</td></tr><tr><td>COMMUNITY A =</td><td>B <input checked="" type="checkbox"/></td></tr><tr><td>NON-COMMUNITY C =</td><td>D =</td></tr></table>	SURFACE	WELL	COMMUNITY A =	B <input checked="" type="checkbox"/>	NON-COMMUNITY C =	D =	<table border="1"><tr><td>ENDANGERED</td><td>AFFECTED</td><td>MONITORED</td></tr><tr><td>A =</td><td>B =</td><td>C =</td></tr><tr><td>D =</td><td>E =</td><td>F =</td></tr></table>	ENDANGERED	AFFECTED	MONITORED	A =	B =	C =	D =	E =	F =	A _____ (ft.) B _____ (ft.)
SURFACE	WELL																
COMMUNITY A =	B <input checked="" type="checkbox"/>																
NON-COMMUNITY C =	D =																
ENDANGERED	AFFECTED	MONITORED															
A =	B =	C =															
D =	E =	F =															

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (CHECK ONE)

☒ A ONLY SOURCE FOR DRINKING ☐ B DRINKING (FOR RESIDENTIAL USE ONLY)
☐ C COMMERCIAL INDUSTRIAL IRRIGATION (FOR RESIDENTIAL USE ONLY)
☐ D NOT USED (UNUSEABLE)

02 POPULATION SERVED BY GROUND WATER _____	03 DISTANCE TO NEAREST DRINKING WATER WELL _____ (ft.)			
04 DEPTH TO GROUNDWATER 25-30 (ft.)	05 DIRECTION OF GROUNDWATER FLOW south-southeast	06 DEPTH TO AQUIFER OF CONCERN 25-30 (ft.)	07 POTENTIAL YIELD OF AQUIFER _____ (gpd)	08 SOLE SOURCE AQUIFER <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO

09 DESCRIPTION OF WELLS (including depth, type, and location relative to site boundaries)

10 RECHARGE AREA <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO COMMENTS	11 DISCHARGE AREA <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO COMMENTS
---	--

IV. SURFACE WATER

01 SURFACE WATER USE (CHECK ONE)

☐ A RESERVOIR RECREATION DRINKING WATER SOURCE ☐ B IRRIGATION ECONOMICALLY IMPORTANT RESOURCES ☐ C COMMERCIAL INDUSTRIAL ☒ D NOT CURRENTLY USED

02 AFFECTED POTENTIALLY AFFECTED BODIES OF WATER

NAME	AFFECTED	DISTANCE TO SITE
No surface-water bodies in report area	=	+ 3 (ft.)
	=	(ft.)
	=	(ft.)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN ONE (1) MILE OF SITE A 30,000 NO. OF PERSONS	TWO (2) MILES OF SITE B _____ NO. OF PERSONS	THREE (3) MILES OF SITE C 90,000 NO. OF PERSONS	02 DISTANCE TO NEAREST POPULATION _____ (ft.)
--	--	---	--

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE _____	04 DISTANCE TO NEAREST OFF SITE BUILDING 30 ft. (ft.)
--	--

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site e.g. type, density, proximity to site, etc.)

Site located in industrial park surrounding by small industrial buildings.
Heavily populated residential area is located about a mile to the east.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

1 IDENTIFICATION
01 STATE: NY 02 SITE: 152113

VI ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (check one)

☐ A $10^{-8} - 10^{-9}$ cm/sec ☐ B $10^{-6} - 10^{-7}$ cm/sec ☐ C $10^{-4} - 10^{-5}$ cm/sec ☒ D GREATER THAN 10^{-3} cm/sec

02 PERMEABILITY OF BEDROCK (check one)

☒ A IMPERMEABLE (less than 10^{-8} cm/sec) ☐ B RELATIVELY IMPERMEABLE ($10^{-6} - 10^{-7}$ cm/sec) ☐ C RELATIVELY PERMEABLE ($10^{-5} - 10^{-4}$ cm/sec) ☐ D VERY PERMEABLE (greater than 10^{-3} cm/sec)

03 DEPTH TO BEDROCK

1200 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

N/A (ft)

05 SOIL TYPE

06 NET PRECIPITATION

46 (in)

07 ONE YEAR 24 HOUR RAINFALL

3.0 (in)

08 SLOPE
SITE SLOPE

DIRECTION OF SITE SLOPE

south

TERRAIN AVERAGE SLOPE

18

09 FLOOD POTENTIAL

SITE IS IN _____ YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND COASTAL HIGH HAZARD AREA RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (check one)

ESTUARINE

OTHER

A 3 (mi)

B 6 (mi)

12 DISTANCE TO CRITICAL HABITAT or presence of species

None (mi)

ENDANGERED SPECIES _____

13 LAND USE IN VICINITY

DISTANCE TO

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS NATIONAL STATE PARKS
FORESTS OR WILDLIFE RESERVES

AGRICULTURAL LANDS
PRIME AG LAND AG LAND

site in industrial park

A _____ (mi)

B 1 (mi)

C _____ (mi)

D _____ (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

Site is located on an outwash plain which slopes gently to the south away from the morainal topographic highs north of the site.

VII SOURCES OF INFORMATION (see instruction sheet for details)

Pluhowski and Kantrowitz, 1964.
Krulik, 1981.
USGS, 1969. Amityville Quadrangle.
Roux Site Visit, July 25, 1987.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION
01 STATE NY 02 SITE NUMBER 152113

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER	None		
SURFACE WATER	None		
WASTE	None		
AIR	None		
RUNOFF	None		
SPILL	None		
SOIL	None		
VEGETATION	None		
OTHER	None		

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS
	Air measurements taken with a photoionization meter.
	All photoionization meter readings were at background levels.

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input checked="" type="checkbox"/> GROUND <input type="checkbox"/> AERIAL	02 IN CUSTODY OF Roux Associates
03 MAPS <input type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS

V. OTHER FIELD DATA COLLECTED

Roux Associates Site Visit, July 25, 1987.

VI. SOURCES OF INFORMATION



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

IDENTIFICATION
01 STATE 02 SITE NUMBER
NY 152113

II CURRENT OWNERS				PARENT COMPANY			
01 NAME Little Joseph Realty		02 D-B NUMBER		08 NAME		09 D-B NUMBER	
03 STREET ADDRESS P.O. Box, RFD, etc. 1637 Broad Hollow Rd.		04 SIC CODE		10 STREET ADDRESS P.O. Box, RFD, etc.		11 SIC CODE	
05 CITY Farmingdale		06 STATE 07 ZIP CODE NY 11735		12 CITY		13 STATE 14 ZIP CODE	
01 NAME		02 D-B NUMBER		08 NAME		09 D-B NUMBER	
03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE		10 STREET ADDRESS P.O. Box, RFD, etc.		11 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		12 CITY		13 STATE 14 ZIP CODE	
01 NAME		02 D-B NUMBER		08 NAME		09 D-B NUMBER	
03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE		10 STREET ADDRESS P.O. Box, RFD, etc.		11 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		12 CITY		13 STATE 14 ZIP CODE	
01 NAME		02 D-B NUMBER		08 NAME		09 D-B NUMBER	
03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE		10 STREET ADDRESS P.O. Box, RFD, etc.		11 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		12 CITY		13 STATE 14 ZIP CODE	
01 NAME		02 D-B NUMBER		08 NAME		09 D-B NUMBER	
03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE		10 STREET ADDRESS P.O. Box, RFD, etc.		11 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		12 CITY		13 STATE 14 ZIP CODE	
III. PREVIOUS OWNERS				IV. REALTY OWNERS			
01 NAME Joseph Picone		02 D-B NUMBER		01 NAME		02 D-B NUMBER	
03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE		03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE	
05 CITY Farmingdale		06 STATE 07 ZIP CODE NY 11735		05 CITY		06 STATE 07 ZIP CODE	
01 NAME		02 D-B NUMBER		01 NAME		02 D-B NUMBER	
03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE		03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		05 CITY		06 STATE 07 ZIP CODE	
01 NAME		02 D-B NUMBER		01 NAME		02 D-B NUMBER	
03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE		03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		05 CITY		06 STATE 07 ZIP CODE	
V. SOURCES OF INFORMATION							
NYSDEC and SCDHS files Roux Site Inspection June 25, 1987							



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NY 152113

II. CURRENT OPERATOR

OPERATOR'S PARENT COMPANY

01 NAME Used as a parking lot		02 D-B NUMBER		10 NAME		11 D-B NUMBER	
03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE		12 STREET ADDRESS P.O. Box, RFD, etc.		13 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		14 CITY		15 STATE 16 ZIP CODE	
08 YEARS OF OPERATION		09 NAME OF OWNER					

III. PREVIOUS OPERATOR(S)

PREVIOUS OPERATORS' PARENT COMPANIES

01 NAME Mr. George Lawrence		02 D-B NUMBER		10 NAME		11 D-B NUMBER	
03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE		12 STREET ADDRESS P.O. Box, RFD, etc.		13 SIC CODE	
05 CITY Glenwood Landing		06 STATE 07 ZIP CODE NY 11747		14 CITY		15 STATE 16 ZIP CODE	
08 YEARS OF OPERATION 3		09 NAME OF OWNER DURING THIS PERIOD Joseph Picone					

01 NAME		02 D-B NUMBER		10 NAME		11 D-B NUMBER	
03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE		12 STREET ADDRESS P.O. Box, RFD, etc.		13 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		14 CITY		15 STATE 16 ZIP CODE	
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

01 NAME		02 D-B NUMBER		10 NAME		11 D-B NUMBER	
03 STREET ADDRESS P.O. Box, RFD, etc.		04 SIC CODE		12 STREET ADDRESS P.O. Box, RFD, etc.		13 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		14 CITY		15 STATE 16 ZIP CODE	
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

IV. SOURCES OF INFORMATION

NYSDEC Site File
SCDHS Site File
Roux Site Inspection June 25, 1987



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

1 IDENTIFICATION
C1 STATE C2 SITE NUMBER
NY 152113

II ON-SITE GENERATOR

C1 NAME None		C2 D-B NUMBER	
C3 STREET ADDRESS P.O. Box, RFD, etc.		C4 SIC CODE	
C5 CITY	C6 STATE	C7 ZIP CODE	

III OFF-SITE GENERATOR(S)

C1 NAME None		C2 D-B NUMBER	C1 NAME	C2 D-B NUMBER	
C3 STREET ADDRESS P.O. Box, RFD, etc.		C4 SIC CODE	C3 STREET ADDRESS P.O. Box, RFD, etc.	C4 SIC CODE	
C5 CITY	C6 STATE	C7 ZIP CODE	C5 CITY	C6 STATE	C7 ZIP CODE
C1 NAME		C2 D-B NUMBER	C1 NAME		C2 D-B NUMBER
C3 STREET ADDRESS P.O. Box, RFD, etc.		C4 SIC CODE	C3 STREET ADDRESS P.O. Box, RFD, etc.		C4 SIC CODE
C5 CITY	C6 STATE	C7 ZIP CODE	C5 CITY	C6 STATE	C7 ZIP CODE

IV TRANSPORTER(S)

C1 NAME None		C2 D-B NUMBER	C1 NAME	C2 D-B NUMBER	
C3 STREET ADDRESS P.O. Box, RFD, etc.		C4 SIC CODE	C3 STREET ADDRESS P.O. Box, RFD, etc.	C4 SIC CODE	
C5 CITY	C6 STATE	C7 ZIP CODE	C5 CITY	C6 STATE	C7 ZIP CODE
C1 NAME		C2 D-B NUMBER	C1 NAME		C2 D-B NUMBER
C3 STREET ADDRESS P.O. Box, RFD, etc.		C4 SIC CODE	C3 STREET ADDRESS P.O. Box, RFD, etc.		C4 SIC CODE
C5 CITY	C6 STATE	C7 ZIP CODE	C5 CITY	C6 STATE	C7 ZIP CODE

V SOURCES OF INFORMATION

Roux Site Inspection June 25, 1987



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

1 IDENTIFICATION
01 STATE 02 SITE NUMBER
NY 152113

II. PAST RESPONSE ACTIVITIES

01 <input type="checkbox"/> A WATER SUPPLY CLOSED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> B TEMPORARY WATER SUPPLY PROVIDED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> C PERMANENT WATER SUPPLY PROVIDED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input checked="" type="checkbox"/> D SPILLED MATERIAL REMOVED 04 DESCRIPTION In November 1982 HWD allegedly removed all wastes from site	02 DATE 1982	03 AGENCY HWD
01 <input type="checkbox"/> E CONTAMINATED SOIL REMOVED 04 DESCRIPTION Allegedly, HWD pumped out and removed sludge from the 2 on-site drywells	02 DATE 1982	03 AGENCY HWD
01 <input type="checkbox"/> F WASTE REPACKAGED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input checked="" type="checkbox"/> G WASTE DISPOSED ELSEWHERE 04 DESCRIPTION HWD allegedly removed all wastes from site and disposed of wastes elsewhere	02 DATE 1982	03 AGENCY HWD
01 <input type="checkbox"/> H ON SITE BURIAL 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> I IN SITU CHEMICAL TREATMENT 04 DESCRIPTION HWD allegedly recycled spent solvent for resale	02 DATE 1982	03 AGENCY HWD
01 <input type="checkbox"/> J IN SITU BIOLOGICAL TREATMENT 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> K IN SITU PHYSICAL TREATMENT 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> L ENCAPSULATION 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> M EMERGENCY WASTE TREATMENT 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> N CUTOFF WALLS 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> O EMERGENCY DIKING SURFACE WATER DIVERSION 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> P CUTOFF TRENCHES/SLUMP 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> Q SUBSURFACE CUTOFF WALL 04 DESCRIPTION	02 DATE _____	03 AGENCY _____



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

IDENTIFICATION

01 STATE 02 SITE NUMBER
NY 152113

II PAST RESPONSE ACTIVITIES

01 = R BARRIER WALLS CONSTRUCTED
04 DESCRIPTION

02 DATE

03 AGENCY

01 = S CAPPING COVERING
04 DESCRIPTION

02 DATE 1982

03 AGENCY HWD

Allegedly a sludge pit was capped (paved over) the pit was cement lined and used during site clean-up

01 = T BULK TANKAGE REPAIRED
04 DESCRIPTION

02 DATE

03 AGENCY

01 = L GROUT CURTAIN CONSTRUCTED
04 DESCRIPTION

02 DATE

03 AGENCY

01 = V BOTTOM SEALED
04 DESCRIPTION

02 DATE

03 AGENCY

01 = W GAS CONTROL
04 DESCRIPTION

02 DATE

03 AGENCY

01 = X FIRE CONTROL
04 DESCRIPTION

02 DATE

03 AGENCY

01 = Y LEACHATE TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

01 = Z AREA EVACUATED
04 DESCRIPTION

02 DATE

03 AGENCY

01 = 1 ACCESS TO SITE RESTRICTED
04 DESCRIPTION

02 DATE

03 AGENCY

01 = 2 POPULATION RELOCATED
04 DESCRIPTION

02 DATE

03 AGENCY

01 = 3 OTHER REMEDIAL ACTIVITIES
04 DESCRIPTION

02 DATE

03 AGENCY

HWD allegedly removed all wastes from site in November 1982. Site inspections confirmed this. No visible wastes or hazardous conditions were observed during Roux Associates site inspection.

III SOURCES OF INFORMATION

NYSDEC Site File
SCDHS Site File
Roux site inspection June 25, 1987.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

1 IDENTIFICATION	
01 STATE	02 SITE NUMBER
NY	152113

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY ENFORCEMENT ACTION ☐ YES ☐ NO

02 DESCRIPTION OF FEDERAL STATE LOCAL REGULATORY ENFORCEMENT ACTION

NYSDEC VS. HWD for violation 6 NYCRR-Part 360; Constructing and operating a solid waste management facility without a permit. 6/24/81

Town of Babylon was going to proceed with legal action against HWD for alleged zoning law violations. No further information.

III. SOURCES OF INFORMATION Can include references to other reports, maps, etc.

NYSDEC and SCDHS files.

5.7 NYSDEC Inactive Hazardous Waste Disposal Report

HAZARDOUS WASTE DISPOSED: TYPE	Confirmed-X	Suspected- QUANTITY (units)
paint lacquer		
ink thinners		
chlorinated solvents		
non-chlorinated solvents		
waste oils		
waste resins		
acids		

ANALYTICAL DATA AVAILABLE:

Air- Surface Water- Groundwater- Soil- Sediment- None-X

CONTRAVENTION OF STANDARDS:

Groundwater- Drinking Water- Surface Water- Air-

LEGAL ACTION:

TYPE...: State- Federal-
 STATUS: Negotiation in Progress- Order Signed-

REMEDIAL ACTION:

Proposed- Under design- In Progress- Completed-
 NATURE OF ACTION:

GEOTECHNICAL INFORMATION:

SOIL TYPE: Sand and gravel

GROUNDWATER DEPTH: approximately 25-30 ft.

ASSESSMENT OF ENVIRONMENTAL PROBLEMS:

Potential for several pathways of contaminant migration.

ASSESSMENT OF HEALTH PROBLEMS:

Medium	Contaminants Available	Migration Potential	Potentially Exposed Population	Need for Investigation
<u>Air</u>	<u>.</u>	<u></u>	<u></u>	<u></u>
Surface Soil				
Groundwater				
Surface Water				

Health Department Site Inspection Date :

MUNICIPAL WASTE ID:

6. DATA ADEQUACY AND RECOMMENDATION

6.1 Data Adequacy

The available data is insufficient for completing final HRS Scores. The Hazardous Waste Quantity score of five (5) was based on previous site inspections performed by state and local agencies. A relatively high total total ground-water route score ($S_{gw} = 46.67$) was calculated based on high containment and waste characteristics targets scores. The surface water route score of zero (0) is because natural surface water bodies are not located within a 3-mile radius of the site.

Previous site inspections performed by local, state and federal agencies reported that hazardous wastes were spilled and/or leaked from on-site drums. These allegations provide sufficient evidence that hazardous wastes were possibly released into the environment. Analytical data needs to be obtained in order to confirm, the presence of soil and/or ground-water contamination.

6.2 RECOMMENDATIONS

A Phase II investigation is recommended to obtain analytical data necessary to determine if ground water is contaminated. Public-supply wells in the vicinity provide drinking water for thousands of people.

6.2.1 Task 1 - Site Reconnaissance

After a complete review of the Phase I study and any available updated information a site visit will be conducted to characterize site accessibility for Phase II studies. The site reconnaissance is a relatively rapid screening process for collection of preliminary information on:

- o Drill rig access
- o Subsurface utilities
- o Location of potential monitoring wells or test borings
- o Site hazards

For health and safety purposes a photoionization meter (HNU or TIP II) will be utilized to monitor air quality throughout the site. While on site, visual observations will be made to help in evaluating site hazards, for


example, conditions that may result in or contact with liquid, sludge and solids, corrosive materials and other general conditions. However, based on Phase I studies, Level D protection is to be expected during site investigations.

6.2.2 Task 2 - Magnetometer Survey

A preliminary screening of the site will be undertaken using a magnetometer. The magnetometer survey will provide the initial screening of the site, help in locating buried metallic objects (pipes, drums) and aid in the selection of locations for potential test borings and well installations.

6.2.3 Task 3 - Soil Borings/Monitoring Wells

Roux Associates recommends that four (4) soil borings be drilled and four (4) monitoring wells installed to NYSDEC specifications. Locations of proposed soil borings and monitoring wells are shown on Figure 3. The purpose of the soil borings is to evaluate the subsurface geology of the site and to determine the type of contamination, if present. The installation of monitoring wells will characterize the ground-water



TITLE			
PROPOSED SOIL BORING/MONITORING WELL LOCATIONS			
PREPARED FOR			
N.Y. S.D.E.C.			
FOUO3			
ROUX ASSOCIATES INC.			
SCALE			
1" = 30'			
DATE			
8/87			
FIGURE			
3			


regime at the site. One (1) monitoring well (MW-1) will be located in the north end of the site. This up-gradient well will monitor the quality of ground water entering the site. Two (2) wells (MW-2 and MW-3) will be utilized to monitor ground-water quality downgradient of the storage area. The fourth monitoring well (MW-4) will be located within the alleged storage area.

A truck mounted hollow stem auger rig will be used. Soil samples will be collected at five-foot intervals until ground water is encountered or the bottom of boring reached. The split-spoons used to collect samples are driven one and one-half feet at a time ahead of the auger flights into undisturbed sediments using a standard 140 lb. weight. A geologist will open the spoon, log the core in detail and then place the soil in sample jars. After each sample is collected the bore-hole is advanced five feet where the next sample is collected. A photoionization meter (HNU or TIP II) will be used to screen soil samples and possible organic vapor emissions from drilling operations. Soil samples will be collected for grain size analysis. Auger flights which have come into contact with subsurface materials will be steam-cleaned and split-spoon samplers will be steam-cleaned after each soil sample.

After each boring is completed a ten-foot, two-inch diameter, flush joint, threaded PVC screen (.020 slot) will be set from 28 to 38 feet below land surface and approximately 28 feet of blank PVC pipe will be installed into each boring through the hollow stem auger flights. Because solvents had been alleged to be at the site the well screens will be set at this horizon to bridge the water table, which is approximately 30 feet.

The auger flights are then pulled out of the hole to two feet above the screen zone. Morie No. 2 sand is placed around the screen zone and up to a level of two feet above the screen.

A minimum two foot layer of bentonite pellets is emplaced above the sand pack. The remaining annular space is then pressure grouted with a cement/bentonite slurry (6:1 ratio) to three feet below land surface. A steel curb box with locking lid is then cemented over the wells for protection at land surface. Well construction details, in accordance with NYSDEC guidelines, are given in a well completion diagram shown on Figure 4.



TITLE

MONITORING WELL CONSTRUCTION DETAILS

PREPARED FOR

N. Y. S. D. E. C.

ROUX

Consulting Ground-Water Geologists
ROUX ASSOCIATES INC.

SCALE
None
DATE
7/87

FIGURE
4

After well installation, the wells are developed by pumping to remove fine material and ensure a good hydraulic connection between the screen and the formation. The wells are then surveyed to a vertical precision of .01 feet using designated measuring points on the PVC casings. Water levels in the monitoring wells are subsequently recorded using a steel measuring tape and electric probe.

6.2.4 Task 4 - Well Sampling and Analyses

A Quality Assurance/Quality Control (QA/QC) Plan will be developed by Roux Associates and approved by the NYSDEC before work is started.

Analytical data is not available. Alleged wastes include solvents, waste oils and resins. Based on these allegations the sampling program for every water and soil sample will include the target compound list for the Superfund Program. In addition, to the soil and water sampling, Roux Associates recommends that both on-site drywells be sampled and analyzed.

One water sample will be collected and analyzed from each of the monitoring wells. The analytical data will

be evaluated to determine if ground-water contamination is present. A minimum of three soil samples will be analyzed. Additional soil samples may be warranted depending on field observations which may include elevated organic volatile readings or visual/smell detections in split-spoon cores.

Air quality will be monitored, using a photoionization meter (HNU or TIP II), to record volatile organics that may be present on-site.

6.2.5 Task 5 - Quality Assurance/Quality Control

On a daily basis, a project manager will be responsible for the supervision, direction, and review of project activities. The project manager will also be responsible for QA/QC protocols which will be developed by Roux Associates in accordance with NYSDEC guidelines and approval.

6.2.6 Task 6 - Health and Safety Plan

A Health and Safety Plan provides an integrated approach for reducing harm to workers on site. The level of

protection selected will be based on the types and measured concentrations of the chemical substance(s) in the ambient atmosphere and its toxicity and the potential for exposure to substances in air, splashes of liquids, or other direct contact with material due to work being done. In situations where the type of chemical, concentration and possibilities of contact are not known, the appropriate level of protection will be selected based on professional experience and judgment until the hazards can be better identified.

During Phase II operations the site Health and Safety Plan will be in accordance with OSHA Standards as stated in 29 CFR 1900 to 1999 and the U.S. EPA office of Emergency and Remedial Response Interim Standard Operating Safety Guide.

6.2.7 Task 7 - Site Assessment

Roux Associates, utilizing data obtained from Phase II investigations, will:

- o Complete EPA Form 2070-13
- o Complete EPA Form 2070-12 (Part I) L. Alden letter
Item 21
- o Finalize HRS scores

- o Summarize site history
- o Discuss potential risks to population if contamination is confirmed.

6.2.8 Task 8 - Phase II Report

The Phase II report will be prepared in accordance with current NYSDEC guidelines. Included in this report are:

- o Phase II field results
 - a. Site reconnaissance
 - b. Magnetometer
 - c. Soil borings and monitoring wells
 - d. Sampling and analysis
 - e. Maps/plans
 - f. Task presentation
 - g. Other collected information
- o Final HRS Scores
- o Remedial alternatives with cost estimates

APPENDIX A

APPENDIX A

BIBLIOGRAPHY

<u>REFERENCE #</u>	<u>DESCRIPTION OF REFERENCE</u>
A-1	J. Yeary (Roux Associates) telephone conversation with George Lawrence (Environmental Services Inc.) on June 10, 1987.
A-2	J. Yeary (Roux Associates) telephone conversation with Vic Emanuelo (Attorney for Little Joseph Realty) on June 10, 1987.
A-3	NYSDEC listing of HWD's permits (9/25/79 - 3/17/80).
A-4	RCRA Inspection Form, September 2, 1981.
A-5	SCDHS Inspection Form, September 14, 1982.

<u>REFERENCE #</u>	<u>DESCRIPTION OF REFERENCE</u>
A-6	J. Soderberg, P.E. memorandums to J. Maloney, P.E. on March 12, 1981 and March 16, 1981.
A-7	Kevin Dunn inspection record of HWD, March 17, 1981.
A-8	J. Soderberg, P.E. memorandum to J. Maloney, P.E. on March 25, 1981.
A-9	A. Machlin (NYSDEC) memorandum to D. Middleton on April 28, 1981.
A-10	J. Scherb (Regional Attorney, NYSDEC) letter to W. Southard (ICC) on May 29, 1981.
A-11	J. Byrnes (Roux Associates) telephone conversation with D. Odrig (SCDHS) on July 15, 1987.

ROUX ASSOCIATES, INC.

Telephone Conversation Sheet

Caller Joanne Yeary

Company Environmental Services Inc.

Contact George Lawrence

Office Telephone # 273-3150

in Reference to Hazardous Waste Disposal.

DATE _____

COMMENTS

June 10th - Lawrence said that Hazardous Waste Disposal has been closed by the Suffolk County Health Dept. He said that if we wanted to visit the site we would have to get in touch with the owner - Joseph Picone CH 9-3400.

ROUX ASSOCIATES, INC.

Telephone Conversation Sheet

Caller Joanne Yearn

Company Little Joseph Realty Inc.

Contact Vic Emanuelo Telephone # CH9-3400

in Reference to Hazardous Waste Disposal

DATE _____

COMMENTS

June 10th Asked to speak to owner of HWD, Joseph Picone. He (Vic Emanuel) told me that HWD is owned by Little Joseph Reuter, Inc. He wants me to mail him letters of authorization before he lets me set up a visit to the site. He wanted to know if I was in contact with the NEC, and who at the NEC. He says he will call back after reviewing the letters.


Mailed letter w/ authorization letters June 10th. (12)

Little Joseph Realty, Inc

1637 Broad Hollow Rd.

Farmingdale, NY 11735

New York State Department of Environmental Conservation

Robert F. Flacke
Commissioner

9/25/79 Ltr, SCDHS to HWD at Valley Stream address
re: SPDES permit for Picone Blvd Site.

10/8/79 Ltr of authorization for Donnelly Engineering
to represent HWD for Picone Blvd Vicinity.

10/17/79 HWD to DEC: Request change of address listing to
Picone Blvd address.

11/2/79 Part 364 Permit for Valley Stream site.

12/18/79 Part 364 Permit for Picone Blvd site.

1/22/80 Ltr, HWD to DEC: "aware of requirements..." etc.

3/17/80 Application to Construct.

move to F,dale Location

**RCRA TREATMENT, STORAGE AND DISPOSAL FACILITY INSPECTION FORM
FOR TSD FACILITIES ONLY**

COMPANY NAME: HAZARDOUS WASTE
DISPOSAL, INC.

EPA I.D. Number: NYT 0100003574

COMPANY ADDRESS: 11A PILEONE BLVD.
FARMINGDALE, N.Y. 11735

COMPANY CONTACT OR OFFICIAL:
MR. GEORGE R. LAWRENCE

OTHER ENVIRONMENTAL PERMITS HELD

BY FACILITY: ☐ NPDES

TITLE: PRESIDENT

☐ AIR

☒ OTHER

NY 300 PERMIT
HALLAS PERMIT

INSPECTOR'S NAME:

DATE OF INSPECTION: 9-2-81

GLENN CAUSEY / REGIONAL CARRITY
Branch/ORGANIZATION: *State*

TIME OF DAY INSPECTION TOOK PLACE: 2:15 P.M.

SCAID WASTE

- (1) Is there reason to believe that the facility has hazardous waste on site?

- a. If yes, what leads you to believe it is hazardous waste?
Check appropriate box:

☒ Company admits that its waste is hazardous during the inspection.

☒ Company admitted the waste is hazardous in its RCRA notification and/or Part A Permit Application.

☒ The waste material is listed in the regulations as a hazardous waste from a nonspecific source (\$261.31)

☐ The waste material is listed in the regulations as a hazardous waste from a specific source (\$261.32)

☐ The material or product is listed in the regulations as a discarded commercial chemical product (\$261.33)

☐ EPA testing has shown characteristics of ignitability, corrosivity, reactivity or extraction procedure toxicity, or has revealed hazardous constituents (please attach analysis report)

☐ Company is unsure but there is reason to believe that waste materials are hazardous. (Explain):

YES NO DON'T
KNOW

- b. Is there reason to believe that there are hazardous wastes on-site which the company claims are merely products or raw materials?

Please explain:

COMPANY CLAIMS THAT A LOT OF THE SOLVENT IS USED AS AN ALTERNATE FUEL SUPPLIES.

- c. Identify the hazardous wastes that are on-site, and estimate approximate quantities of each.

SPENT SOLVENTS AND ACIDS.
1900 DRUMS, PLUS A 250 GAL. ACID TANK.

- | | | | |
|--|-------------------------------------|--------------------------|--------------------------|
| (2) Does the facility <u>generate</u> hazardous waste? | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| (3) Does the facility <u>transport</u> hazardous waste? | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| (4) Does the facility <u>treat, store or dispose of</u> hazardous waste? | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

RECEIVE

OCT 26 1981

DIRECTOR'S OFFICE
DIVISION OF SOLID WASTE

OCT 11 3 56 PM '81
ENVIRONMENTAL PROTECTION
AGENCY
NEW YORK, N.Y. 10007

VISUAL OBSERVATIONS

- | | YES | NO | DON'T KNOW |
|--|-------------------------------------|-------------------------------------|--------------------------|
| (5) <u>SITE SECURITY</u> (\$265.14) | | | |
| a. Is there a 24-hour surveillance system?
<i>24-HOUR SECURITY GUARDS - 7 DAYS PER WEEK.</i> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| b. Is there a suitable barrier which completely surrounds the active portion of the facility?
<i>FENCE</i> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| c. Are there "Danger-Unauthorized Personnel Keep Out" signs posted at each entrance to the facility?
<i>THERE IS A WARNING SIGN, BUT IS NOT THE ONE REQUIRED BY THE REGULATIONS.</i> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| (6) Are there <u>ignitable</u> , reactive or incompatible wastes on site? (\$265.27) | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| a. If "YES", what are the approximate quantities?
<i>1900 DRUMS COMPRISED OF HAZARDOUS AND NONHAZARDOUS WASTE.</i> | | | |
| b. If "YES", have precautions been taken to prevent accidental ignition or reaction of ignitable or reactive waste? <i>NATHANSON BONDING WARE AND 2,4-DINITRO-FLUOR WASTE ARE USED, THE STORAGE DRUMS ARE LITAKING AND EXPLOD TO THE ELEMENTS.</i> | | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| c. If "YES", explain | | | |
| d. In your opinion, are proper precautions taken so that these wastes do not: | | | |
| - generate extreme heat or pressure, fire or explosion, or violent reaction? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| - produce uncontrolled toxic mists, fumes, dusts, or gases in sufficient quantities to threaten human health? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| - produce uncontrolled flammable fumes or gases in sufficient quantities to pose a risk of fire or explosions? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| - damage the structural integrity of the device or facility containing the waste? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| - threaten human health or the environment? | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |

Please explain your answers, and comment if necessary.

- e. Are there any additional precautions which you *YES, A COMPLETE RENOVATION* would recommend to improve hazardous waste *OF THE STORAGE AREA. THE* handling procedures at the facility? *IMPRESSION IS THAT THE OWNER OF THE FACILITY SIMPLY PUT THE*
- (7) Does the facility comply with preparedness and prevention requirements including maintaining: *DRUMS WHEREVER THERE IS AVAILABLE SPACE, WITH MINIMAL ATTEMPTS TO SAFEGUARD HIS EMPLOYEES. SAFETY, PUBLIC HEALTH AND THE ENVIRONMENT.*
- (\$265.32)

YES NO DON'T
KNOW

A4-3

- an internal communications or alarm system? ☒ ☐ ☐
- a telephone or other device to summon emergency assistance from local authorities? ☒ ☐ ☐
- portable fire equipment? ☒ ☐ ☐
- adequate aisle space? ☐ ☒ ☐
- in your opinion, do the types of wastes on site require all of the above procedures, or are some not needed? Explain. ☒ ☐ ☐

ALL OF THE ABOVE PROCEDURES ARE NEEDED.

In your opinion, do the types of wastes on site require all of the above procedures, or are some not needed? Explain.

ALL OF THE ABOVE PROCEDURES ARE NEEDED

- *(8) Have you inspected to verify that the groundwater monitoring wells (if any) mentioned in the facility's groundwater monitoring plan (see no. 19 below) are properly installed? ☐ ☒ ☐

N/A.
FACILITY IS NOT A LANDFILL, HOWEVER, A DRY WELL IS LOCATED WITHIN 30 FEET OF THE STORAGE AREA. IF YOU HAVE, PLEASE COMMENT, AS APPROPRIATE.

- (9) a. Is there any reason to believe that groundwater contamination already exists from this facility? ☐ ☒ ☐
If "YES", explain.

- b. Do you believe that operation of this facility may affect groundwater quality? ☒ ☐ ☐

c. If "YES", explain. THE LOCATION OF THE DRYWELL IS SUCH THAT MODERATE (OR HEAVY) PRECIPITATION WILL RESULT IN GROUNDWATER RE CONTAMINATION ASSUMING GROUND WATER TO EXIST UNDER THE FACILITY. ADDITIONALLY, THE RECORDS INSPECTION SPACE BETWEEN THE STORAGE AREA AND THE DRYWELL IS SIMPLY UNOCCUPIED GROUND.

- (10) Has the facility received hazardous waste from an off-site source since Nov. 19, 1980 (effective date of the regulations)? ☒ ☐ ☐

- a. If "YES", does it appear that the facility has a copy of a manifest for each hazardous waste load received? ☒ ☐ ☐
- b. How many post-November 19 manifests does it have? (If the number is large, you may estimate)
COMPANY RECEIVES WASTES A FEW TIMES PER WEEK.
- c. Does each manifest (or a representative sample) have the following information?
- a manifest document number ☒ ☐ ☐

(13) PERSONNEL TRAINING (\$265.16)

a. Is there written documentation of the following:

- job title for each position at the facility related to hazardous waste management and the name of the employee filling each job? ☐ ☐ ☐
- type and amount of training to be given to personnel in jobs related to hazardous waste management? ☐ ☐ ☐
- actual training or experience received by personnel? ☐ ☐ ☐

INADVERTENT;
NOT
OBTAINED

(14) Does the facility have a written contingency plan for emergency procedures designed to deal with fires, explosion or any unplanned release of hazardous waste? (\$265.51)

a. Does the plan describe arrangements made with local authorities? ☒ ☐ ☐b. Has the contingency plan been submitted to local authorities? ☒ ☐ ☐

How do you know?

c. Does the plan list names, addresses, and phone numbers of Emergency Coordinators? ☒ ☐ ☐d. Does the plan have a list of what emergency equipment is available? ☒ ☐ ☐e. Is there a provision for evacuating facility personnel? ☒ ☐ ☐f. Was an Emergency Coordinator present or on call at the time of the inspection? ☒ ☐ ☐

(15) Does the owner/operator keep a written operating record with: (\$265.73)

- a description of wastes received with methods and dates of treatment, storage or disposal? ☒ ☐ ☐- location and quantity of each waste? ☒ ☐ ☐- detailed records and results of waste analysis and treatability tests performed on wastes coming into the facility? ☒ ☐ ☐

(ATTACHED ENVIRONMENTAL STATEMENT) KEEPS DETAILED RECORDS OF ALL ANALYSES, LOG IS MAINTAINED THERE.

- detailed operating summary reports and description of all emergency incidents that required the implementation of the facility contingency plan? ☒ ☐ ☐

*(16) Does the facility have written closure and post-closure plans? (\$265.110)

FACILITY IS UNDER COURT ORDER TO SHUT DOWN, PARTIALLY SATISFYING CLOSURE REQUIREMENTS

a. Does the written closure plan include: (SEE ATTACHED COURT ORDER)

- a description of how and when the facility will be partially (if applicable) and ultimately closed? ☐ ☐ ☐

* Effective date for this requirement is May 19, 1981.

SEE
C-481
OP-DEP

- an estimate of the maximum inventory of wastes in storage or treatment at any time during the life of the facility? ☐ ☐ ☐
- a description of the steps necessary to decontaminate facility equipment during closure? ☐ ☐ ☐
- a schedule for final closure including the anticipated date when wastes will no longer be received and when final closure will be completed? ☐ ☐ ☐
- b. What is the anticipated date for final closure? ☐ ☐ ☐
- 1c. Does the owner/operator have a written post-closure plan identifying the activities which will be carried on after closure and the frequency of these activities? ☐ ☐ ☐
- d. Does the written post-closure plan include:
 - a description of planned groundwater monitoring activities and their frequencies during post-closure? ☐ ☐ ☐
 - a description of planned maintenance activities and frequencies to ensure integrity of final cover during post-closure? ☐ ☐ ☐
 - the name, address and phone number of a person or office to contact during post-closure? ☐ ☐ ☐
- *(17) Does the owner/operator have a written estimate of the cost of closing the facility? (\$265.142) What is it? ☐ ☒ ☐
ORAL ESTIMATE BY MR. LAWRENCE IS \$200,000
- *(18) Does the owner/operator have a written estimate of the cost for post-closure monitoring and maintenance? What is it? (\$265.144) ☐ ☐ ☐
- *(19) Has a groundwater monitoring plan been submitted to the Regional Administrator for facilities containing a surface impoundment, landfill or land treatment process? (This requirement does not apply to recycling facilities.) (\$265.90) ☐ ☒ ☐
N/A
- a. Does the plan indicate that at least one monitoring well has been installed hydraulically upgradient from the limit of the waste management area? ☐ ☒ ☐
N/A
- b. Does the plan indicate that there are at least three monitoring wells installed hydraulically downgradient at the limit of the waste management area? ☐ ☒ ☐
N/A

† This section applies only to disposal facilities.

* Effective date for this requirement is May 19, 1981.

SITE-SPECIFIC

Please circle all appropriate activities and answer questions on indicated pages for all activities circled. When you submit your report, include only those site-specific pages that you have used.

<u>STORAGE</u>	<u>TREATMENT</u>	<u>DISPOSAL</u>
Waste Pile p. 9	Tank p. 8	Landfill pp. 10-11
Surface Impoundment p. 8	Surface Impoundment pp. 8-9	Land Treatment pp. 9, 10
Container p. 7	Incineration pp. 12-13	Surface Impoundment p. 8
Tank, above ground p. 8	Thermal Treatment pp. 12-13	Other _____
Tank, below ground p. 8	Land Treatment pp. 9-10	
Other _____	Chemical, Physical p. 13 and Biological Treatment (other than in tanks, surface impoundment or land treatment facilities)	
	Other _____	

YES NO DON'T KNOW

CONTAINERS (\$265.170)

1. Are there any leaking containers?
It "YES", explain. MAJORITY OF CONTAINERS WERE LEAKING (SEE COMMENTS IN GENERATOR INSPECTION FORM, P. 4.)
2. Are there any containers which appear in danger of leaking?
If "YES", explain. YES
3. Do wastes appear compatible with container materials? YES
4. Are all containers closed except those in use? YES
5. Do containers appear to be opened, handled or stored in a manner which may rupture the containers or cause them to leak? YES
6. How often does the plant manager claim to inspect container storage areas? _____
7. Does it appear that incompatible wastes are being stored in close proximity to one another?
If "YES", explain. YES
8. Are containers holding ignitable or reactive wastes located at least 15 meters (50 feet) from the facility's property line? YES
9. What is the approximate number and size of containers with hazardous wastes?

1900

- | <u>TANKS (\$265.190)</u> | <u>YES</u> | <u>NO</u> | <u>DON'T
KNOW</u> |
|---|-----------------------------------|--------------|-----------------------|
| 1. Are there any leaking tanks?
If "YES", explain. | --- | <u>✓</u> | --- |
| 2. Are there any tanks which appear in danger of
leaking.
If "YES", explain. | --- | <u>✓</u> | --- |
| 3. Are wastes or treatment reagents being
placed in tanks which could cause them to
rupture, leak, corrode or otherwise fail?
If "YES", explain. | --- | --- | <u>✓</u> |
| 4. Do uncovered tanks have at least 2 feet
of freeboard or an adequate containment
structure? | --- | <u>N/A</u> | --- |
| 5. Where hazardous waste is continuously
fed into a tank, is the tank equipped with
a means to stop this inflow? | <u>✓</u> | --- | --- |
| 6. Does it appear that incompatible wastes
are being stored in close proximity to one
another, or in the same tank?
If "YES", explain. | <u>✓</u> | --- | --- |
| 7. How often does the plant manager claim to
inspect container storage areas? | --- | <u>DAILY</u> | --- |
| 8. Are ignitable or reactive wastes stored in
a manner which protects them from a source
of ignition or reaction?
If "YES", explain. | --- | <u>N/A</u> | --- |
| 9. What is the approximate number and size of
tanks containing hazardous wastes? | <u>ONE 2570 GALLON ACID TANK.</u> | | |

- | <u>SURFACE IMPOUNDMENTS (\$265.220)</u> | <u>YES</u> | <u>NO</u> | <u>DON'T
KNOW</u> |
|--|------------|------------|-----------------------|
| 1. Is there at least 2 feet of freeboard
in the impoundment? | --- | <u>N/A</u> | --- |
| 2. Do all earthen dikes have a protective
cover to preserve their structural integrity?
If "YES", specify type of covering. | --- | --- | --- |
| 3. Is there reason to believe that incompatible
wastes are being placed in the same surface
impoundment?
If "YES", explain. | --- | --- | --- |

A4-8

4. Are ignitable or reactive wastes being placed in surface impoundments without being treated to remove these characteristics?
If "YES", explain.

___ ___ ___

5. Are there any leaks, failures or is there any deterioration in the impoundments?
If "YES", explain.

___ ___ ___

6. Give the approximate size of surface impoundments (gallons or cubic feet).

WASTE PILES (\$265.250)

N/A

1. Is the waste pile protected from wind erosion?

___ ___ ___

a. Does it appear to need such protection?

___ ___ ___

b. Explain what type of protection exists.

2. Does it appear that incompatible wastes are being stored in the same waste pile?
If "YES", explain.

___ ___ ___

3. Is leachate run-off from a pile a hazardous waste?

___ ___ ___

If "YES", explain this determination and answer (a) and (b) below.

a. Is the pile placed on an impermeable base that is compatible with the waste?

___ ___ ___

b. Is the pile protected from precipitation and run-on?

___ ___ ___

4. In your judgment, are ignitable or reactive wastes managed in such a way that they are protected from any material or conditions which may cause them to ignite?
Please explain or indicate if no such wastes are present.

___ ___ ___

Are they placed on an existing pile so that they no longer meet the definition of ignitable or reactive waste?
Please explain.

___ ___ ___

5. How many waste piles are on site, and approximately how large are they?

LAND TREATMENT (\$265.270)

N/A

1. Can the facility operator demonstrate that the hazardous waste has been made less or non-hazardous by biological degradation or chemical reactions occurring in or on the soil?
Please explain.

___ ___ ___

2. Is run-on diverted away from the active portions of the land treatment facility? ☐ ☐ ☐
3. Is run-off collected? ☐ ☐ ☐
4. Are food chain crops being grown on the facility property? ☐ ☐ ☐
- a. If "YES", can the facility operator document that arsenic, lead and mercury:
- will not be transferred to the crop or ingested by food chain animals or ☐ ☐ ☐
 - will not occur in greater concentrations in the crops grown on the land treatment facility than in the same crops grown on untreated soils. ☐ ☐ ☐
- b. Has notification of the growing of the food chain crops been made to the Regional Administrator? ☐ ☐ ☐
5. Is there a written and implemented plan for unsaturated zone monitoring? ☐ ☐ ☐
6. Are there records of the application dates, application rates, quantities and location of each hazardous waste placed in the facility? ☐ ☐ ☐
7. Do the closure and post-closure plans address:
- a. control of migration of hazardous wastes into the groundwater? ☐ ☐ ☐
 - b. control of run-off, release of airborne particulate contaminants? ☐ ☐ ☐
 - c. compliance with requirements for the growth of food-chain crops (if they are present)? ☐ ☐ ☐
8. Is ignitable or reactive waste immediately incorporated into the soil so the resulting waste no longer meets that definition? ☐ ☐ ☐
- If "YES", explain.
9. Are incompatible wastes placed in the same land treatment area? ☐ ☐ ☐
- If "YES", explain.
10. What is the area of the land receiving hazardous waste treatment? ☐ ☐ ☐

LANDFILLS (\$265.300) N/A

11. Is run-on diverted away from the active portions of the landfill? ☐ ☐ ☐
12. Is run-off from active portions of the landfill collected? ☐ ☐ ☐

* Effective date for these requirements is May 19, 1981.

† These requirements are effective November 19, 1981.

3. Is waste which is subject to wind dispersal controlled?
Explain.

4. Does the owner/operator maintain a map with:

- the exact location and dimensions of each cell
- the contents of each cell and approximate location of each hazardous waste type

5. Do the closure and post-closure plans address:

- control of pollutant migration via ground water?
- control of surface water infiltration?
- prevention of erosion?

6. Is ignitable or reactive waste treated before being placed in the landfill?
Explain how you know.

7. Are precautions taken to insure that incompatible wastes are not placed in the same landfill cell?
If "NO", explain.

8. Are bulk or non-containerized wastes containing free liquids placed in the landfill?
If "YES",

- a. Does the landfill have a liner which is chemically and physically resistant to the added liquid?

- b. Is the waste treated and stabilized so that free liquids are no longer present?

9. Are containers holding liquid waste or waste containing free liquids placed in the landfill?

10. Are empty containers (e.g. those containing less than 1/2 inch of liquid) placed in the landfills?

If so, are they crushed flat, shredded or similarly reduced in volume before they are buried?

11. What is the approximate area of the hazardous waste landfill?

* Effective date for this requirement is November 19, 1981.

INCINERATORS AND THERMAL TREATMENT *N/A*
 (\$\$265.340 and 265.379)

YES NO DON'T
KNOW

1. What type of incinerator or thermal treatment is at the site (e.g. waterwall incinerator, boiler, fluidized bed, etc.)? ___

2. Was hazardous waste being incinerated or thermally treated during your inspection? ___
 If "YES", answer all following questions.
 If "NO", answer only questions 3 and 7.

3. Has waste analysis been performed (and written records kept) to include:

- heating value of the waste	___	___	___
- halogen content	___	___	___
- sulfur content	___	___	___
- concentration of lead	___	___	___
- concentration of mercury	___	___	___

NOTE: Waste analysis need not be performed on each waste load if if there are documented data available to show waste characteristics that do not vary. If there are such documented data available, check here .

4. Does it appear that the owner/operator brings his thermal treatment process to steady state (normal) conditions of operation before introducing hazardous wastes? ___

5. Did it appear during your inspection that there was adequate monitoring and inspection by owner/operator every 15 minutes during hazardous waste incineration for: ___

- | | | | |
|---------------------------|-----|-----|-----|
| - waste feed | ___ | ___ | ___ |
| - auxiliary fuel feed | ___ | ___ | ___ |
| - air flow | ___ | ___ | ___ |
| - incinerator temperature | ___ | ___ | ___ |
| - scrubber flow | ___ | ___ | ___ |
| - scrubber pH | ___ | ___ | ___ |
| - relevant level controls | ___ | ___ | ___ |

Every hour for:

- | | | | |
|-----------------------------------|-----|-----|-----|
| - stack plume (color and opacity) | ___ | ___ | ___ |
|-----------------------------------|-----|-----|-----|

5. Is there open burning of hazardous waste? ___

a. If "YES", what is being burned?
(only burning or detonation
of explosives is permitted)

b. If open burning or detonation of explosives is taking
place, approximately what is the distance from the open
burning or detonation to the property of others?

- | | YES | NO | DON'T
KNOW |
|---|-----|-----|---------------|
| 6. Does the incinerator appear to be operating properly? (Do emergency shutdown controls and system alarms seem to be in good working order?) Please explain. | --- | --- | --- |
| a. Is there any evidence of fugitive emissions? | --- | --- | --- |
| 7. Is the residue from the incinerator treated by the owner as a hazardous waste? Please explain. | --- | --- | --- |
| 8. What types of air pollution control devices (if any) are installed on the incinerator? | --- | --- | --- |

CHEMICAL, PHYSICAL AND BIOLOGICAL TREATMENT (\$265.400) N/A

1. Does the treatment process system show any signs of ruptures, leaks, or corrosion? Please explain.

2. Is there a means to stop the inflow of continuously-fed hazardous wastes?

3. Is there ignitable or reactive waste fed into the treatment system?

If "YES", has it been treated or protected from any material or conditions which may cause it to ignite or react? If so, explain how.

Are the incompatible wastes placed in the same treatment process? If "YES", explain.


5. Describe the treatment system at this facility.

SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
INDUSTRIAL WASTE AND HAZARDOUS MATERIALS CONTROL
65 JETSON LA., P.O. BOX 6, CENTRAL ISLIP, N.Y. 11722
(516) 234-2622

File
A5-1

NAME OF FACILITY		OWNER/OFFICER <u>George Lawrence.</u>		PAGE 1 OF	
COMPANY NAME <u>HWD INC.</u>		CONTACT		TEL.	
PLANT ADDRESS <u>PICONE BLVD.</u>		VILLAGE <u>Farmingdale</u> TOWN <u>Bab.</u>		ZIP	
MAILING ADDRESS					
DATE <u>14 Sept. 82</u>	TIME <u>9:00 AM</u>	ORIG. PERIODIC <u>RE</u>	WASTE	NO WASTE <u>NBN</u>	SEWAGE SYSTEM PUBLIC PRIVATE
INDUSTRY <u>Industrial Waste Sweeper.</u>					
SPDES OR NPDES PERMIT? YES NO PERMIT NO.			360 PERMIT? YES NO PERMIT NO.		
SCAVENGER TEL.					
SCAVENGER APPROVED YES NO		PICK UP RECORDS AVAILABLE YES NO		RECORDS CONSISTENT WITH EXPECTED WASTE GENERATION YES NO	
HEATING SYSTEM-MFG. NAME				FUEL TYPE	FIRING RATE
INCIN. NAME				WASTE BURNED	RATE
DRUM STORAGE <u>YES</u> NO	NUMBER OF DRUMS STORED <u>840-CONTAIN MATERIAL 420-EMPTY</u>		TYPE OF MATERIAL STORED WASTE RAW <u>BOTH</u>		
TANK STORAGE <u>YES</u> NO	ABOVE GROUND <u>X</u> UNDER GROUND BOTH		TYPE OF MATERIAL STORED <u>WASTE</u> RAW BOTH		
HAVE TANKS BEEN REGISTERED YES <u>NO</u>	CONDITION OF ABOVEGROUND TANKS GOOD FAIR <u>POOR</u>		ANY ART. XII VIOLATIONS <u>YES</u> NO		
<p>① Spills noted in drum storage area were cleaned up with absorbent material.</p> <p>② Empty drums outside dyked area had material within them.</p> <p>③ Drums containing material 840X55gal. Drums empty- 420X55gal.</p> <p>④ Article 12 Violations → Outside, unsecured, pad not impervious. etc.</p>					
<p>PERMISSION IS GRANTED BY THIS FACILITY TO THE SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES TO CONDUCT ROUTINE SAMPLING OF CESSPOOLS, STORMDRAINS, AND OTHER DISCHARGE POINTS AT THE FACILITY.</p> <p>REINSPECTION SCHEDULED ON OR AFTER _____. FAILURE TO CORRECT UNSATISFACTORY CONDITIONS BY REINSPECTION DATE MAY RESULT IN A HEARING AND/OR FINE.</p> <p>DAVID OBR16</p>					
SIGN. OF PERSON REC. REPORT		TITLE		INSPECTOR <u>D. G.</u>	

INDUSTRIAL WASTE PROCESS

[illegible][illegible]


A5-1



SUFFOLK COUNTY
DEPT OF
HEALTH SERVICES


JOB HWD INC (A5-3)
SHEET NO. PICONS BLVD. OF FARMING DATE
CALCULATED BY E DATE _____
CHECKED BY _____ DATE _____
SCALE _____

30 JUNE 82 - 11:50 AM



- ① OBSERVED NO WORK AT SITE DURING INSPECTION.
- ② OBSERVED NO OBVIOUS SPILLS
- ③ Drums were uncovered + exposed to weather.
- ④ New pad area has been constructed to the South of the old drum storage.
Drums two (2) high have been stored between the fence + the transfer pump.
- ⑤ Waste pit North of Acid/Base mix tank covered with black plastic.

D. O'Bray



15 Sept - Acid tank to be pumped

Spillies down area had abundant material on floor
Empty drums and 5.00 dpt. room had material in some.



M E M O R A N D U M

TO: James C. Maloney, P.E.
FROM: John V. Soderberg, P.E.
DATE: March 12, 1981
RE: Hazardous Waste Disposal (H.W.D.)

On March 11, 1981 the writer was requested to accompany representatives of the Toxic Waste Handling Group in their investigation of the above premises.

At the time of my inspection there were no visible emissions occurring from the process tank in question. However, the East Farmingdale Fire District indicated a visible plume of from 150 to 200' in vertical height on or about noon of that date.

As part of my inspection, I spoke with representatives of Pront Printing (110 Picone Boulevard, Farmingdale). They indicated that the situation has been occurring sporadically since last September and was particularly severe last Summer. Concerning the specific incident, they were unsure about specifics and reported no property damage or lost time that they can contribute directly to the incident.

I recommend first that a detailed industrial survey be made of the premises and secondly that the firm be placed under routine surveillance for at least three months.

JVS:mew

M E M O R A N D U M

TO: JAMES C. MALONEY
FROM: JOHN V SODERBERG
DATE: MARCH 16, 1981
RE: H W D.

In follow up to my memo concerning the March 11, 1981 investigation of the above firm, an air pollution emission inspection was not performed at that time (due to inclement weather and potential safety hazard).

The water pollution file contains no information either confirming or denying the presence of such sources (only the H. W. D. environmental checklist submitted by them to Babylon Town indicating no process emissions).

I have therefore requested that such a survey be performed.

JVS:ets

20. Continued Recorded Existing Conditions Noted by Inspector 3/17/81

Visited HWD and spoke with Andrew Conely, Gen'l. Manager, who was very cooperative in supplying information on the plant. It was determined that there exists an Ammonium-Hydrosulfide scrubbing process on an acid storage tank that is operating without a certificate to operate. A violation was raised to Mr. Conely for operating without that permit.

A tour of the grounds further disclosed that only 3 of the 6-10 large steel cylinder tanks remained referred to by D. O'Brig in his report of 3/11/81 were remaining at the location indicated by Mr. O'Brig. None of the 55 gal. drums were there. There was liquid waste in one of the tanks and sludge waste in the other 2. The liquid & sludge waste were going to be transferred to 55 gal. drums for further transfer to a waste treatment plant in New Jersey via the yard foreman.

Kevin Drenn

MEMORANDUM

TO: James C. Maloney, P.E.
FROM: John V. Soderberg, P.E. *[Signature]*
DATE: March 25, 1981
RE: H.W.D. - Farmingdale

In accordance with procedure I have, subsequent to Mr. Dunn's inspection, requested certificate application from the above firm.

In light of the issuance of a violation to the firm for failure to obtain a permit to construct, do you wish me to initiate formal litigatory proceedings at either local or State level.

JVS:mew

Yes gm

*Yes. Prepare legal action
to go to the State. Mr
Roberts will have to
make final determination.*

3/31/81

JCM

TS 11278
New York State Department of Environmental Conservation

MEMORANDUM

TO: D. Middleton
FROM: A. Machlin
SUBJECT: Monthly Report - Environmental Quality, April 1981
DATE: April 28, 1981

A. Accomplishments

1. Town of Oyster Bay - Solid Waste

A meeting was held with the Town and representatives of DEC, NCDH, and USEPA on the Town's proposed resource-recovery facility to expedite necessary permits including the PSD permit being handled by USEPA.

In addition, the Town has submitted a report on wastewater management for the proposed resource-recovery project, as well as landfill leachate and incinerator discharges, which were reviewed at a meeting with the Town, its consultants (Lockwood, Kessler & Bartlett), and NCDH.

2. Town of North Hempstead/PASNY/Resource Recovery

PASNY is preparing a proposal to build a resource-recovery facility which will be presented to the Town on or about June 1, 1981. This Department has been involved in meetings with PASNY, USEPA, NCDH, and the Town to expedite necessary permits including the PSD permit presently being handled by USEPA.

3. Groundwater Management Program

Continued progress was made towards completion of early work tasks of the project and initiation of intermediate technical tasks. The final draft report of Criteria for Defining Groundwater/Water Supply Problems was transmitted to USEPA.

4. POC Projects

- Meetings were held on 4/23/81 with USEPA Consultants and Region staff, local agencies, and DEC staff to initiate Consumer Products, Spill Response, and Fertilizer/Pesticides projects in terms of contract preparations, work plans, etc., and to determine the nature and extent of involvement of USEPA consultants in the projects.

5. Beach Erosion & Hurricane Protection Program

The final Wetlands permit was issued for the Moriches Inlet breach repair revetment project.

6. Air Resources - Agreements with RCDF and SCDF

Memoranda of Agreement for carrying out DEC programs by RCDF and SCDF have been completed.

2. Applied Environmental Services-(AES) and Hazardous Waste Disposal (HWD) Corp.

On 4/14/81, a meeting was held between representatives of the Bureau of Hazardous Waste and this Region concerning the carrying out of that program in this Region. It was indicated that Region 1 had the most commercial hazardous waste facilities in the State. Also, a major part of the discussion related to HWD in Farmingdale and AES in Glenwood Landing. Since HWD was not a pre-existing facility and commenced operation in July of 1979 without a Part 360 Permit, it was determined that it was operating illegally and should be closed until a permit is received. On the other hand, AES was a pre-existing facility but does not yet have a completed Part 360 application which would allow it to operate legally. It was determined that an Order on Consent would be utilized to allow the continued operation of AES, with a three-month milestone to allow for completion of the application and continued cleanup. If the application is completed at that time, the Order on Consent would continue to be utilized to allow the operation until the permit process was completed.

On 4/23/81, a meeting was held with representatives of AES and HWD to inform them of this Department's determinations. The owner of the firm indicated that, if HWQ was closed, the firm could not afford to keep AES open since the operations were interdependent. The owner offered to correct any deficiencies on HWD as soon as possible if DEC would allow continued operation. The Division of Solid Waste attorney stated that he would bring this matter to the attention of this Department's Executive Staff for a review and determination within the week.

3. Water Quality Accidents

There were forty-four new spills reported: twenty-eight in Nassau County and sixteen in Suffolk County

4. Sheridan Industrial Waste Oil Corp.

Nassau County Department of Public Works has indicated that it cannot temporarily accept the oil-contaminated water that is removed from Sheridan's waste oil collection operation, as originally hoped, because it is considered a hazardous waste by USEPA and would need an extensive effort on their part to meet USEPA regulatory requirements. Since Sheridan presently has no disposal point for this material, it is not picking up this material which will probably result in increased illegal disposal.


5. Town of Hempstead Solid Waste

The Town of Hempstead has indicated several provisions of the Order on Consent with the County, and a conference has been scheduled for 5/6/81 on this matter.

6. Town of Northtown Solid Waste

The Part 360 Permit issued to the town calls for involvement in resource recovery.

New York State Department of Environmental Conservation
Building 40 - State University of New York
Stony Brook, New York 11794
(516) 751-7900



Robert F. Flacke
Commissioner

May 29, 1981

Mr. William R. Southard
Assistant Regional Director
Interstate Commerce Commission
Suite 501
150 Causeway Street
Boston, Massachusetts 02114

Dear Mr. Southard:

Please be advised that Hazardous Waste Disposal, Inc. has been operating without the required Part 360 Permit, pursuant to Article 27, Title 7, of the New York State Environmental Conservation Law. They have also been operating without a Siting Board Permit, as required under Section 27-1105.

They are, therefore, operating illegally and I am attaching hereto, a copy of the Department's Notice of Hearing and Complaint. I would suggest that you consider these facts in reviewing their temporary Permit to Operate.

Very truly yours,

JOAN B. SCHERB
Regional Attorney

JBS:cm
Attachment
cc: Town of North Hempstead
bc: Morris Bruckman

ROUX ASSOCIATES, INC.

Telephone Conversation Sheet

Caller J. BYRNESCompany Suffolk County Department of Health ServiceContact Mr. David O'Brig Telephone # (516) 451-963

DATE


COMMENTS

7/15

In reference to the alledge sludge pit: Mr. O'Brig informed me that the cement lined pit was used during clean-up operations. Wastes from on-site drums were emptied into this pit and after wastes solidified they were removed from pit and transported off-site.

Storm drains - the 2 storm drains empty into the nearby sump. This was proven when a dye test was performed by Mr. O'Brig and the local fire department.

Mr. O'Brig also stated that very early samples were taken from the on-site storm drains and high concentrations of Styrene found.



APPENDIX B

(47-15-11 (10/83)

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
DIVISION OF SOLID AND HAZARDOUS WASTE
INACTIVE HAZARDOUS WASTE DISPOSAL SITE REPORT

PRIORITY CODE: _____ SITE CODE: 152113
NAME OF SITE: Hazardous Waste Disposal REGION: I
STREET ADDRESS: 11 A Picone Blvd.
TOWN/CITY: Farmingdale COUNTY: Suffolk
NAME OF CURRENT OWNER OF SITE: Little Joseph Realty, Inc.
ADDRESS OF CURRENT OWNER OF SITE: 1637 Broad Hollow Rd., Farmingdale, NY
TYPE OF SITE: OPEN DUMP ☒ STRUCTURE ☐ LAGOON ☐
LANDFILL ☐ TREATMENT POND ☐
ESTIMATED SIZE: 0.5 ACRES

SITE DESCRIPTION: Located in an industrial park, the site is a paved and fenced in lot. the site was used for the temporary storage of hazardous wastes. Wastes were stored in 55-gallon drums, sludge pit and tanks. The DEC conducted a site inspection in July 1985 and observed several poorly conditioned drums and a strong solvent odor.

As of Roux Associates' site inspection on June 25, 1987, the site shows no signs of any hazardous materials or conditions.

HAZARDOUS WASTE DISPOSED:	CONFIRMED <input checked="" type="checkbox"/>	SUSPECTED <input type="checkbox"/>
TYPE AND QUANTITY OF HAZARDOUS WASTES DISPOSED:		
TYPE	QUANTITY	(POUNDS, DRUMS, TONS, GALLONS)
<u>chlorinated and non-chlorinated solvents</u>	_____	<u>unknown</u>
<u>paint sludge</u>	_____	<u>unknown</u>
<u>waste oils</u>	_____	<u>unknown</u>
<u>waste resins</u>	_____	<u>unknown</u>
_____	_____	_____

TIME PERIOD SITE WAS USED FOR HAZARDOUS WASTE DISPOSAL:

_____, 19 79 TO _____, 19 84

OWNER(S) DURING PERIOD OF USE: George Lawrence

SITE OPERATOR DURING PERIOD OF USE: George Lawrence

ADDRESS OF SITE OPERATOR: 1 Shore Rd., Glenwood Landing, NY

ANALYTICAL DATA AVAILABLE: AIR ☐ SURFACE WATER ☐ GROUNDWATER ☐
SOIL ☐ SEDIMENT ☐ NONE ☒

CONTRAVENTION OF STANDARDS: GROUNDWATER ☒ DRINKING WATER ☐
SURFACE WATER ☐ AIR ☐

SOIL TYPE: unconsolidated sand and gravel

DEPTH TO GROUNDWATER TABLE: 25 - 30 feet

LEGAL ACTION: TYPE: _____ STATE ☐ FEDERAL ☐

STATUS: IN PROGRESS ☐ COMPLETED ☐

REMEDIAL ACTION: PROPOSED ☐ UNDER DESIGN ☐

IN PROGRESS ☐ COMPLETED ☐

NATURE OF ACTION: _____

ASSESSMENT OF ENVIRONMENTAL PROBLEMS:

Potential soil and ground-water contamination

ASSESSMENT OF HEALTH PROBLEMS:

N/A

PERSON(S) COMPLETING THIS FORM:

NEW YORK STATE DEPARTMENT OF
ENVIRONMENTAL CONSERVATION

NAME J. Patrick Byrnes

TITLE Geologist

NAME Roux Associates, Inc.

TITLE _____

DATE: _____

NEW YORK STATE DEPARTMENT OF HEALTH

NAME _____

TITLE _____

NAME _____

TITLE _____

DATE: _____

Facility name: <u>Hazardous Waste Disposal</u>	
Location: <u>11 A Picone Blvd., Farmingdale, NY (Suffolk Co.)</u>	
EPA Region: <u>II</u>	
Person(s) in charge of the facility: <u>Little Joseph Realty</u>	
<u>(Attorney Vic Emanuelo, Ed Lynch)</u>	
Name of Reviewer: <u>Roux Associates</u>	Date: <u>June 25, 1987</u>
General description of the facility:	
(For example: landfill, surface impoundment, pile, container; types of hazardous substances; location of the facility; contamination route of major concern; types of information needed for rating; agency action, etc.)	
<u>The Site, located in Farmingdale, NY, consists of a fenced-in</u>	
<u>paved parking lot. All waste materials have been removed and site</u>	
<u>is visually clean. From 1979-1982 the site was used as a</u>	
<u>hazardous waste storage facility. Wastes were contained in 55-gal.</u>	
<u>drums and large tanks. Site inspections reported leaks in on-site</u>	
<u>drums. Spilled wastes pose a potential threat to ground water.</u>	
Scores: $S_M = 26.98 (S_{GW} = 46.67 \quad S_{SW} = 0 \quad S_A = 0)$	
$S_{FE} =$ Not scored	Maximum $S_M = 31.13$
$S_{DC} = 0$	

FIGURE 1
HRS COVER SHEET

Ground Water Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)	
1 Observed Release	0 45	1	0	45	3.1	
If observed release is given a score of 45, proceed to line 4 . If observed release is given a score of 0, proceed to line 2 .						
2 Route Characteristics					3.2	
Depth to Aquifer of Concern	0 1 (2) 3	2	4	6		
Net Precipitation	0 1 2 (3)	1	3	3		
Permeability of the Unsaturated Zone	0 1 2 (3)	1	3	3		
Physical State	0 1 2 (3)	1	3	3		
Total Route Characteristics Score			13	15		
3 Containment	0 1 2 (3)	1	3	3	3.3	
4 Waste Characteristics					3.4	
Toxicity/Persistence	0 3 6 (9) 12 15 18	1	9	18		
Hazardous Waste Quantity	0 1 2 3 4 (5) 6 7 8	1	5	8		
Total Waste Characteristics Score			14	26		
5 Targets					3.5	
Ground Water Use	0 1 2 (3)	3	9	9		
Distance to Nearest Well/Population Served	0 4 6 8 10 12 16 18 20 24 30 32 35 (40)	1		40		
Total Targets Score			49	49		
6	If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5		26,754	57,330		
7	Divide line 6 by 57,330 and multiply by 100		S _{gw} = 46.67			

FIGURE 2
GROUND WATER ROUTE WORK SHEET

Surface Water Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)	
1 Observed Release	0 45	1	0	45	4.1	
If observed release is given a value of 45, proceed to line 4 . If observed release is given a value of 0, proceed to line 2 .						
2 Route Characteristics					4.2	
Facility Slope and Intervening Terrain	① 1 2 3	1	0	3		
1-yr. 24-hr. Rainfall	0 1 ② 3	1	2	3		
Distance to Nearest Surface Water	① 1 2 3	2	0	6		
Physical State	0 1 2 ③	1	3	3		
Total Route Characteristics Score			5	15		
3 Containment	0 1 2 ③	1	.3	3	4.3	
4 Waste Characteristics					4.4	
Toxicity/Persistence	0 3 6 ⑨ 12 15 18	1	9	18		
Hazardous Waste Quantity	0 1 2 3 4 ⑤ 6 7 8	1	5	8		
Total Waste Characteristics Score			14	26		
5 Targets					4.5	
Surface Water Use	① 1 2 3	3	0	9		
Distance to a Sensitive Environment	① 1 2 3	2	0	6		
Population Served/Distance to Water Intake Downstream	① 4 6 8 10 12 16 18 20 24 30 32 35 40	1	0	40		
Total Targets Score			0	55		
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			0	64,350		
7 Divide line 6 by 64,350 and multiply by 100			S _{sw} = 0			

FIGURE 7
SURFACE WATER ROUTE WORK SHEET

NOTE: There are no wastes visibly present on-site.

Air Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)	
1 Observed Release	0 45	1	0	45	5.1	
Date and Location:						
Sampling Protocol:						
If line 1 is 0, the $S_a = 0$. Enter on line 5 . If line 1 is 45, then proceed to line 2 .						
2 Waste Characteristics					5.2	
Reactivity and Incompatibility	0 1 2 3	1		3		
Toxicity	0 1 2 3	3		9		
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1		8		
Total Waste Characteristics Score				20		
3 Targets					5.3	
Population Within 4-Mile Radius	0 9 12 15 18 21 24 27 30	1	27	30		
Distance to Sensitive Environment	0 1 2 3	2	0	6		
Land Use	0 1 2 3	1	3	3		
Total Targets Score				30	39	
4 Multiply 1 x 2 x 3			0	35,100		
5 Divide line 4 by 35,100 and multiply by 100			$S_a = 0$			

FIGURE 9
AIR ROUTE WORK SHEET

	s	s ²
Groundwater Route Score (S _{gw})	46.67	2178.01
Surface Water Route Score (S _{sw})	0	0
Air Route Score (S _a)	0	0
$S_{gw}^2 + S_{sw}^2 + S_a^2$		2178.01
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2}$		46.67
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2} / 1.73 = S_M =$		26.98

FIGURE 10
WORKSHEET FOR COMPUTING S_M

Maximum S_M = 31.13

Site visit did not document a demonstrated fire or explosion threat. During Roux Associates Site Visit, all photoionization meter readings were at background levels, and there was no waste visible at site.

Fire and Explosion Work Sheet						
Rating Factor	Assigned Value (Circle One)		Multi- plier	Score	Max. Score	Ref. (Section)
1 Containment	1	3	1		3	7.1
2 Waste Characteristics						7.2
Direct Evidence	0	3	1		3	
Ignitability	0	1 2 3	1		3	
Reactivity	0	1 2 3	1		3	
Incompatibility	0	1 2 3	1		3	
Hazardous Waste Quantity	0	1 2 3 4 5 6 7 8	1		8	
Total Waste Characteristics Score					20	
3 Targets						7.3
Distance to Nearest Population	0	1 2 3 4 5	1		5	
Distance to Nearest Building	0	1 2 3	1		3	
Distance to Sensitive Environment	0	1 2 3	1		3	
Land Use	0	1 2 3	1		3	
Population Within 2-Mile Radius	0	1 2 3 4 5	1		5	
Buildings Within 2-Mile Radius	0	1 2 3 4 5	1		5	
Total Targets Score					24	
4 Multiply 1 x 2 x 3					1,440	
5 Divide line 4 by 1,440 and multiply by 100				SFE = Not Scored		

FIGURE 11
FIRE AND EXPLOSION WORK SHEET

NOTE: There are no wastes visibly present on-site.

Direct Contact Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)	
1 Observed Incident	<u>0</u> 45	1	0	45	8.1	
If line 1 is 45, proceed to line 4 If line 1 is 0, proceed to line 2						
2 Accessibility	<u>0</u> 1 2 3	1	0	3	8.2	
3 Containment	<u>0</u> 15	1	0	15	8.3	
4 Waste Characteristics Toxicity	0 1 2 3	5		15	8.4	
5 Targets					8.5	
Population Within a 1-Mile Radius	0 1 2 3 4 <u>5</u>	4	20	20		
Distance to a Critical Habitat	<u>0</u> 1 2 3	4	0	12		
Total Targets Score			20	32		
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			0	21,600		
7 Divide line 6 by 21,600 and multiply by 100			SDC = 0			

FIGURE 12
DIRECT CONTACT WORK SHEET